

IN THE SUPREME COURT OF THE STATE OF NEVADA

Case No. 84345

and

Case No. 84640

Electronically Filed
May 02 2023 04:04 PM
Elizabeth A. Brown
Clerk of Supreme Court

CITY OF LAS VEGAS, a political subdivision of the State of Nevada

Appellant

v.

180 LAND CO, LLC, a Nevada limited-liability company, FORE STARS LTD.,
a Nevada limited liability company,

Respondents

District Court Case No.: A-17-758528-J
Eighth Judicial District Court of Nevada

**CITY OF LAS VEGAS' REPLY APPENDIX
VOLUME 6**

LAS VEGAS CITY ATTORNEY'S OFFICE Bryan K. Scott (#4381) Jeffrey Galliher (#8078) Rebecca Wolfson (#14132) 495 S. Main Street, 6th Floor Las Vegas, NV 89101 Phone: 702.229.6629 Fax: 702.386.1749 bscott@lasvegasnevada.gov jgalliher@lasvegasnevada.gov rwolfson@lasvegasnevada.gov	McDONALD CARANO LLP George F. Ogilvie III (#3552) Amanda C. Yen (#9726) Christopher Molina (#14092) 2300 W. Sahara Ave, Suite 1200 Las Vegas, NV 89102 Phone: 702.873.4100 Fax: 702.873.9966 gogilvie@mcdonaldcarano.com ayen@mcdonaldcarano.com cmolina@mcdonaldcarano.com
--	--

LEONARD LAW, PC Debbie Leonard (#8260) 955 S. Virginia St., Suite #220 Reno, NV 89502 775-964-4656 debbie@leonardlawpc.com	SHUTE, MIHALY & WEINBERGER, LLP Andrew W. Schwartz (CA Bar No. 87699) (Admitted pro hac vice) Lauren M. Tarpey (CA Bar No. 321775) (Admitted pro hac vice) 396 Hayes Street San Francisco, California 94102
--	--

CHRONOLOGICAL INDEX TO CITY'S REPLY APPENDIX

DATE	DOCUMENT	VOLUME	PAGE RANGE
2022-08-10	Plaintiff Landowners' Motion to Determine Take and for Summary Judgment on the Third and Fifth Claims for Relief, Case No. A-18-773268-C	1	REPLY APP 0001 - REPLY APP 0030
2022-08-11	Plaintiff Landowners' Appendix of Exhibits in Support of: Plaintiff Landowners' Motion to Determine Take and for Summary Judgment on the Third and Fifth Claims for Relief, Volume 22, Exhibit 214, Case No. A-18-773268-C	1	REPLY APP 0031 - REPLY APP 0227
2022-08-24	Defendant City of Las Vegas' Supplemental Appendix of Exhibits in Support of City's Renewed Motion for Summary Judgment and Motions in Limine Volume 26, Exhibits KKKKK - LLLLL, Case No. A-18-773268-C	2	REPLY APP 0228 - REPLY APP 0364
2022-09-12	Plaintiff Landowners Reply Re: Plaintiff Landowners' Motion to Determine Take and For Summary Judgment on the Third and Fifth Claims for Relief, Case No. A-18-773268-C	2	REPLY APP 0365 - REPLY APP 0395

DATE	DOCUMENT	VOLUME	PAGE RANGE
2022-09-13	Defendant City of Las Vegas' Second Supplemental Appendix of Exhibits in Support of City's Renewed Motion for Summary Judgment and Motions in Limine Volume 32, Case No. A-18-773268-C	2	REPLY APP 0396 - REPLY APP 0432
2022-11-23	Defendant City of Las Vegas' Supplemental Appendix of Exhibits in Support of City's Countermotion for Summary Judgment on Just Compensation Volume 34, Case No. A-18-773268-C	3	REPLY APP 0433 - REPLY APP 0652
2022-11-23	Defendant City of Las Vegas' Supplemental Appendix of Exhibits in Support of City's Countermotion for Summary Judgment on Just Compensation Volume 35, Case No. A-18-773268-C	4 5	REPLY APP 0653 - REPLY APP 0902 REPLY APP 0903 - REPLY APP 0907
2022-11-23	Defendant City of Las Vegas' Supplemental Appendix of Exhibits in Support of City's Countermotion for Summary Judgment on Just Compensation Volume 36, Case No. A-18-773268-C	5	REPLY APP 0908 - REPLY APP 1096
2022-11-23	Defendant City of Las Vegas' Supplemental Appendix of Exhibits in Support of City's Countermotion for Summary Judgment on Just Compensation Volume 37, Case No. A-18-773268-C	6	REPLY APP 1097 - REPLY APP 1240

DATE	DOCUMENT	VOLUME	PAGE RANGE
2022-11-23	Defendant City of Las Vegas' Supplemental Appendix of Exhibits in Support of City's Countermotion for Summary Judgment on Just Compensation Volume 38, Case No. A-18-773268-C	7	REPLY APP 1241 - REPLY APP 1406
2022-11-23	Defendant City of Las Vegas' Supplemental Appendix of Exhibits in Support of City's Countermotion for Summary Judgment on Just Compensation Volume 39, Case No. A-18-773268-C	7	REPLY APP 1407 - REPLY APP 1476
2023-01-23	Defendant City of Las Vegas' Appendix of Exhibits in Support of Motion to Retax Memorandum of Costs, Volume 1, Exhibits B - C, Case No. A-18-773268-C	8	REPLY APP 1477 - REPLY APP 1667
2022-09-12	Plaintiff Landowners Second Supplement to Appendix of Exhibits in Support of Motion to Determine Take and for Summary Judgment on the Third and Fifth Claims for Relief Volume 24, Excerpt from Exhibit 228, Case No. A-18-773268-C	9	REPLY APP 1668 - REPLY APP 1742

ALPHABETICAL INDEX TO CITY'S REPLY APPENDIX

DATE	DOCUMENT	VOLUME	PAGE RANGE
2023-01-23	Defendant City of Las Vegas' Appendix of Exhibits in Support of Motion to Retax Memorandum of Costs, Volume 1, Exhibits B - C, Case No. A-18-773268-C	8	REPLY APP 1477 - REPLY APP 1667
2022-09-13	Defendant City of Las Vegas' Second Supplemental Appendix of Exhibits in Support of City's Renewed Motion for Summary Judgment and Motions in Limine Volume 32, Case No. A-18-773268-C	2	REPLY APP 0396 - REPLY APP 0432
2022-08-24	Defendant City of Las Vegas' Supplemental Appendix of Exhibits in Support of City's Renewed Motion for Summary Judgment and Motions in Limine Volume 26, Exhibits KKKKK - LLLLL, Case No. A-18-773268-C	2	REPLY APP 0228 - REPLY APP 0364
2022-11-23	Defendant City of Las Vegas' Supplemental Appendix of Exhibits in Support of City's Countermotion for Summary Judgment on Just Compensation Volume 34, Case No. A-18-773268-C	3	REPLY APP 0433 - REPLY APP 0652
2022-11-23	Defendant City of Las Vegas' Supplemental Appendix of Exhibits in Support of City's Countermotion for Summary Judgment on Just Compensation Volume 35, Case No. A-18-773268-C	4	REPLY APP 0653 - REPLY APP 0902
		5	REPLY APP 0903 - REPLY APP 0907

DATE	DOCUMENT	VOLUME	PAGE RANGE
2022-11-23	Defendant City of Las Vegas' Supplemental Appendix of Exhibits in Support of City's Countermotion for Summary Judgment on Just Compensation Volume 36, Case No. A-18-773268-C	5	REPLY APP 0908 - REPLY APP 1096
2022-11-23	Defendant City of Las Vegas' Supplemental Appendix of Exhibits in Support of City's Countermotion for Summary Judgment on Just Compensation Volume 37, Case No. A-18-773268-C	6	REPLY APP 1097 - REPLY APP 1240
2022-11-23	Defendant City of Las Vegas' Supplemental Appendix of Exhibits in Support of City's Countermotion for Summary Judgment on Just Compensation Volume 38, Case No. A-18-773268-C	7	REPLY APP 1241 - REPLY APP 1406
2022-11-23	Defendant City of Las Vegas' Supplemental Appendix of Exhibits in Support of City's Countermotion for Summary Judgment on Just Compensation Volume 39, Case No. A-18-773268-C	7	REPLY APP 1407 - REPLY APP 1476
2022-09-12	Plaintiff Landowners Reply Re: Plaintiff Landowners' Motion to Determine Take and For Summary Judgment on the Third and Fifth Claims for Relief, Case No. A-18-773268-C	2	REPLY APP 0365 - REPLY APP 0395

DATE	DOCUMENT	VOLUME	PAGE RANGE
2022-09-12	Plaintiff Landowners Second Supplement to Appendix of Exhibits in Support of Motion to Determine Take and for Summary Judgment on the Third and Fifth Claims for Relief Volume 24, Excerpt from Exhibit 228, Case No. A-18-773268-C	9	REPLY APP 1668 - REPLY APP 1742
2022-08-11	Plaintiff Landowners' Appendix of Exhibits in Support of: Plaintiff Landowners' Motion to Determine Take and for Summary Judgment on the Third and Fifth Claims for Relief, Volume 22, Exhibit 214, Case No. A-18-773268-C	1	REPLY APP 0031 - REPLY APP 0227
2022-08-10	Plaintiff Landowners' Motion to Determine Take and for Summary Judgment on the Third and Fifth Claims for Relief, Case No. A-18-773268-C	1	REPLY APP 0001 - REPLY APP 0030

DATED this 2nd day of May, 2023.

BY: /s/ Debbie Leonard

LAS VEGAS CITY ATTORNEY'S OFFICE Bryan K. Scott (#4381) Jeffrey Galliher (#8078) Rebecca Wolfson (#14132) 495 S. Main Street, 6th Floor Las Vegas, NV 89101 Phone: 702.229.6629 Fax: 702.386.1749 bscott@lasvegasnevada.gov jgalliher@lasvegasnevada.gov rwolfson@lasvegasnevada.gov	McDONALD CARANO LLP George F. Ogilvie III (#3552) Amanda C. Yen (#9726) Christopher Molina (#14092) 2300 W. Sahara Ave, Suite 1200 Las Vegas, NV 89102 Phone: 702.873.4100 Fax: 702.873.9966 gogilvie@mcdonaldcarano.com ayen@mcdonaldcarano.com cmolina@mcdonaldcarano.com
LEONARD LAW, PC Debbie Leonard (#8260) 955 S. Virginia St., Suite #220 Reno, NV 89502 775-964-4656 debbie@leonardlawpc.com	SHUTE, MIHALY & WEINBERGER, LLP Andrew W. Schwartz (CA Bar No. 87699) (Admitted pro hac vice) Lauren M. Tarpey (CA Bar No. 321775) (Admitted pro hac vice) 396 Hayes Street San Francisco, California 94102

Attorneys for City of Las Vegas

CERTIFICATE OF SERVICE

I HEREBY CERTIFY that I am an employee of Leonard Law, PC, and that on this date a copy of Appendix Volumes 2-9 were electronically filed with the Clerk of the Court for the Nevada Supreme Court by using the Nevada Supreme Court's E-Filing system (E-Flex). Participants in the case who are registered with E-Flex as users will be served by the E-Flex system. All others will be served by U.S. mail.

Kermitt L. Waters
James J. Leavitt
Michael A. Schneider
Autumn L. Waters
Law Offices of Kermitt L. Waters
704 South Ninth Street
Las Vegas, Nevada 89101
Attorneys for Landowners

Micah S. Echols
Claggett & Sykes Law Firm
4101 Meadows Lane, Suite 100
Las Vegas, Nevada 89107
Attorneys for Landowners

Elizabeth Ham
EHB Companies
1215 S. Fort Apache Road, Suite 120
Las Vegas, NV 89117
Attorneys for Landowners

Karl Hall
Jonathan Shipman
City of Reno
1 E. First Street
P. O. Box 1900
Reno, NV 89505
Attorneys for Amicus Curiae

Steven M. Silva
Nossaman, LP
895 Pinebrook Road
Reno, NV 89509
Attorneys for Amicus Curiae

Brandon P. Kemble
Amanda B. Kern
Nicholas G. Vaskov
Henderson City Attorney's Office
P.O. Box 95050, MSC 144
Henderson, NV 89009
Attorneys for Amicus Curiae

Micaela Moore
North Las Vegas City Attorney's Office
2250 Las Vegas Blvd. North, #810
North Las Vegas, NV 89030
Attorneys for Amicus Curiae

Robert D. Sweetin
Davison Van Cleve
300 South 4th Street, Suite 1400
Las Vegas, NV 89101
Attorneys for Amicus Curiae


Nancy Porter
Lauren A. Landa
Goicoechea, Di Grazia, Coyle &
Stanton, Ltd.
530 Idaho Street
Elko, NV 89801
Attorneys for Amicus Curiae

Leo Cahoon
501 Mill Street
Ely, NV 89301
Attorneys for Amicus Curiae

Dated: May 2, 2023

/s/ Tricia Trevino

Tricia Trevino



1 **APEN**

2 Bryan K. Scott (NV Bar No. 4381)
3 Philip R. Byrnes (NV Bar No. 166)
4 Rebecca Wolfson (NV Bar No. 14132)
5 LAS VEGAS CITY ATTORNEY'S OFFICE
6 495 South Main Street, 6th Floor
7 Las Vegas, Nevada 89101
8 Telephone: (702) 229-6629
9 Facsimile: (702) 386-1749
10 bscott@lasvegasnevada.gov
11 pbyrnes@lasvegasnevada.gov

12 (Additional Counsel Identified on Signature Page)

13 *Attorneys for Defendant City of Las Vegas*

14 **DISTRICT COURT**

15 **CLARK COUNTY, NEVADA**

16 FORE STARS, LTD, SEVENTY ACRES, LLC, a
17 Nevada limited liability company, DOE
18 INDIVIDUALS I through X, DOE
19 CORPORATIONS I through X, DOE LIMITED
20 LIABILITY COMPANIES I through X,

21 Plaintiffs,

22 CITY OF LAS VEGAS, political subdivision of the
23 State of Nevada, THE EIGHTH JUDICIAL
24 DISTRICT COURT, County of Clark, State of
25 Nevada, DEPARTMENT 24 (the HONORABLE JIM
26 CROCKETT, DISTRICT COURT JUDGE, IN HIS
27 OFFICIAL CAPACITY), ROE government entities I
28 through X, ROE Corporations I through X, ROE
INDIVIDUALS I through X, ROE LIMITED
LIABILITY COMPANIES I through X, ROE quasi-
governmental entities I through X,

Defendants.

Case No. A-18-773268-C
Dept. No. XXIX

**SUPPLEMENTAL APPENDIX OF
EXHIBITS IN SUPPORT OF CITY'S
COUNTERMOTION FOR SUMMARY
JUDGMENT ON JUST COMPENSATION**

VOLUME 37

23 The City of Las Vegas ("City") submits this Supplemental Appendix of Exhibits in support of its
24 Countermotion for Summary Judgment on Just Compensation. This appendix supplements the Appendix
25 of Exhibits in Support of City's Renewed Motion for Summary Judgment and Motions in Limine filed
26 August 11, 2022 (Volumes 1 through 25); the Supplemental Appendix of Exhibits in Support of City's
27 Renewed Motion for Summary Judgment and Motions in Limine filed August 24, 2022 (Volumes 26
28

through 27); the Second Supplemental Appendix of Exhibits in Support of City's Renewed Motion for Summary Judgment and Motions in Limine filed September 12, 2022 (Volumes 28 through 32); and the Third Supplemental Appendix of Exhibits in Support of City's Renewed Motion for Summary Judgment and Motions in Limine filed September 14, 2022 (Volume 33).

Exhibit	Exhibit Description	Vol.	Bates No.
A	City records regarding William Peccole's Petition to Annex 2,246 acres to the City of Las Vegas	1	0001-0011
B	City records regarding the Peccole Land Use Plan and the Z-34-81 rezoning application	1	0012-0030
C	City records regarding the Venetian Foothills Master Plan and the Z-30-86 rezoning application	1	0031-0050
D	Excerpts of the 1985 City of Las Vegas General Plan	1	0051-0061
E	City records regarding Peccole Ranch Master Plan and phase I rezoning application (Z-139-88)	1	0062-0106
F	City records regarding Z-40-89 rezoning application	1	0107-0113
G	Ordinance No. 3472 (establishing the Gaming Enterprise District) and related records	1	0114-0137
H	City records regarding the Amended Peccole Ranch Master Plan and phase II rezoning application (Z-17-90)	1	0138-0194
I	Excerpts of 1992 City of Las Vegas General Plan	2	0195-0248
J	City records related to Badlands Golf Course expansion	2	0249-0254
K	Excerpt of land use case files for GPA-24-98 and GPA-6199	2	0255-0257
L	Ordinance No. 5250 and Excerpts of Las Vegas 2020 Master Plan	2	0258-0273
M	Miscellaneous Southwest Sector Land Use Maps from 2002-2005	2	0274-0277
N	Ordinance No. 5787 and Excerpts of 2005 Land Use Element	2	0278-0291
O	Ordinance No. 6056 and Excerpts of 2009 Land Use & Rural Neighborhoods Preservation Element	2	0292-0301
P	Ordinance No. 6152 and Excerpts of 2012 Land Use & Rural Neighborhoods Preservation Element	2	0302-0317
Q	Ordinance No. 6622 and Excerpts of 2018 Land Use & Rural Neighborhoods Preservation Element	2	0318-0332
R	Ordinance No. 1582	2	0333-0339
S	Ordinance No. 4073 and Excerpt of the 1997 City of Las Vegas Zoning Code	2	0340-0341

Exhibit	Exhibit Description	Vol.	Bates No.
T	Ordinance No. 5353	2	0342-0361
U	Ordinance No. 6135 and Excerpts of City of Las Vegas Unified Development Code adopted March 16, 2011	2	0362-0364
V	Deeds transferring ownership of the Badlands Golf Course	2	0365-0377
W	Third Revised Justification Letter regarding the Major Modification to the 1990 Conceptual Peccole Ranch Master Plan	2	0378-0381
X	Parcel maps recorded by the Developer subdividing the Badlands Golf Course	3	0382-0410
Y	EHB Companies promotional materials	3	0411-0445
Z	General Plan Amendment (GPA-62387), Rezoning (ZON-62392) and Site Development Plan Review (SDR-62393) applications	3	0446-0466
AA	Staff Report regarding 17-Acre Applications	3	0467-0482
BB	Major Modification (MOD-63600), Rezoning (ZON-63601), General Plan Amendment (GPA-63599), and Development Agreement (DIR-63602) applications	3	0483-0582
CC	Letter requesting withdrawal of MOD-63600, GPA-63599, ZON-63601, DIR-63602 applications	4	0583
DD	Transcript of February 15, 2017 City Council meeting	4	0584-0597
EE	Judge Crockett's March 5, 2018 order granting Queensridge homeowners' petition for judicial review, Case No. A-17-752344-J	4	0598-0611
FF	Docket for NSC Case No. 75481	4	0612-0623
GG	Complaint filed by Fore Stars Ltd. and Seventy Acres LLC, Case No. A-18-773268-C	4	0624-0643
HH	General Plan Amendment (GPA-68385), Site Development Plan Review (SDR-68481), Tentative Map (TMP-68482), and Waiver (68480) applications	4	0644-0671
II	June 21, 2017 City Council meeting minutes and transcript excerpt regarding GPA-68385, SDR-68481, TMP-68482, and 68480.	4	0672-0679
JJ	Docket for Case No. A-17-758528-J	4	0680-0768
KK	Judge Williams' Findings of Fact and Conclusions of Law, Case No. A-17-758528-J	5	0769-0793
LL	Development Agreement (DIR-70539) application	5	0794-0879
MM	August 2, 2017 City Council minutes regarding DIR-70539	5	0880-0882

Exhibit	Exhibit Description	Vol.	Bates No.
NN	Judge Sturman's February 15, 2019 minute order granting City's motion to dismiss, Case No. A-18-775804-J	5	0883
OO	Excerpts of August 2, 2017 City Council meeting transcript	5	0884-0932
PP	Final maps for Amended Peccole West and Peccole West Lot 10	5	0933-0941
QQ	Excerpt of the 1983 Edition of the Las Vegas Municipal Code	5	0942-0951
RR	Ordinance No. 2185	5	0952-0956
SS	1990 aerial photograph identifying Phase I and Phase II boundaries, produced by the City's Planning & Development Department, Office of Geographic Information Systems (GIS)	5	0957
TT	1996 aerial photograph identifying Phase I and Phase II boundaries, produced by the City's Planning & Development Department, Office of Geographic Information Systems (GIS)	5	0958
UU	1998 aerial photograph identifying Phase I and Phase II boundaries, produced by the City's Planning & Development Department, Office of Geographic Information Systems (GIS)	5	0959
VV	2015 aerial photograph identifying Phase I and Phase II boundaries, retail development, hotel/casino, and Developer projects, produced by the City's Planning & Development Department, Office of Geographic Information Systems (GIS)	5	0960
WW	2015 aerial photograph identifying Phase I and Phase II boundaries, produced by the City's Planning & Development Department, Office of Geographic Information Systems (GIS)	5	0961
XX	2019 aerial photograph identifying Phase I and Phase II boundaries, and current assessor parcel numbers for the Badlands property, produced by the City's Planning & Development Department, Office of Geographic Information Systems (GIS)	5	0962
YY	2019 aerial photograph identifying Phase I and Phase II boundaries, and areas subject to inverse condemnation litigation, produced by the City's Planning & Development Department, Office of Geographic Information Systems (GIS)	5	0963
ZZ	2019 aerial photograph identifying areas subject to proposed development agreement (DIR-70539), produced by the City's Planning & Development	5	0964

Exhibit	Exhibit Description	Vol.	Bates No.
	Department, Office of Geographic Information Systems (GIS)		
AAA	Membership Interest Purchase and Sale Agreement	6	0965-0981
BBB	Transcript of May 16, 2018 City Council meeting	6	0982-0998
CCC	City of Las Vegas' Amicus Curiae Brief, <i>Seventy Acres, LLC v. Binion</i> , Nevada Supreme Court Case No. 75481	6	0999-1009
DDD	Nevada Supreme Court March 5, 2020 Order of Reversal, <i>Seventy Acres, LLC v. Binion</i> , Nevada Supreme Court Case No. 75481	6	1010-1016
EEE	Nevada Supreme Court August 24, 2020 Remittitur, <i>Seventy Acres, LLC v. Binion</i> , Nevada Supreme Court Case No. 75481	6	1017-1018
FFF	March 26, 2020 Letter from City of Las Vegas Office of the City Attorney to Counsel for the Developer Re: Entitlements on 17 Acres	6	1019-1020
GGG	September 1, 2020 Letter from City of Las Vegas Office of the City Attorney to Counsel for the Developer Re: Final Entitlements for 435-Unit Housing Development Project in Badlands	6	1021-1026
HHH	Complaint Pursuant to 42 U.S.C. § 1983, <i>180 Land Co. LLC et al. v. City of Las Vegas, et al.</i> , 18-cv-00547 (2018)	6	1027-1122
III	9th Circuit Order in <i>180 Land Co. LLC; et al v. City of Las Vegas, et al.</i> , 18-cv-0547 (Oct. 19, 2020)	6	1123-1127
JJJ	Plaintiff Landowners' Second Supplement to Initial Disclosures Pursuant to NRCP 16.1 in 65-Acre case	6	1128-1137
LLL	Bill No. 2019-48: Ordinance No. 6720	7	1138-1142
MMM	Bill No. 2019-51: Ordinance No. 6722	7	1143-1150
NNN	March 26, 2020 Letter from City of Las Vegas Office of the City Attorney to Counsel for the Developer Re: Entitlement Requests for 65 Acres	7	1151-1152
OOO	March 26, 2020 Letter from City of Las Vegas Office of the City Attorney to Counsel for the Developer Re: Entitlement Requests for 133 Acres	7	1153-1155

Exhibit	Exhibit Description	Vol.	Bates No.
PPP	April 15, 2020 Letter from City of Las Vegas Office of the City Attorney to Counsel for the Developer Re: Entitlement Requests for 35 Acres	7	1156-1157
QQQ	Valbridge Property Advisors, Lubawy & Associates Inc., Appraisal Report (Aug. 26, 2015)	7	1158-1247
RRR	Notice of Entry of Order Adopting the Order of the Nevada Supreme Court and Denying Petition for Judicial Review	7	1248-1281
SSS	Letters from City of Las Vegas Approval Letters for 17-Acre Property (Feb. 16, 2017)	8	1282-1287
TTT	Reply Brief of Appellants 180 Land Co. LLC, Fore Stars, LTD., Seventy Acres LLC, and Yohan Lowie in <i>180 Land Co LLC et al v. City of Las Vegas</i> , Court of Appeals for the Ninth Circuit Case No. 19-16114 (June 23, 2020)	8	1288-1294
UUU	Excerpt of Reporter's Transcript of Hearing on City of Las Vegas' Motion to Compel Discovery Responses, Documents and Damages Calculation and Related Documents on Order Shortening Time in <i>180 Land Co. LLC v. City of Las Vegas</i> , Eighth Judicial District Court Case No. A-17-758528-J (Nov. 17, 2020)	8	1295-1306
VVV	Plaintiff Landowners' Sixteenth Supplement to Initial Disclosures in <i>180 Land Co., LLC v. City of Las Vegas</i> , Eighth Judicial District Court Case No. A-17-758528-J (Nov. 10, 2020)	8	1307-1321
WWW	Excerpt of Transcript of Las Vegas City Council Meeting (Aug. 2, 2017)	8	1322-1371
XXX	Notice of Entry of Findings of Facts and Conclusions of Law on Petition for Judicial Review in <i>180 Land Co. LLC v. City of Las Vegas</i> , Eighth Judicial District Court Case No. A-17-758528-J (Nov. 26, 2018)	8	1372-1399
YYY	Notice of Entry of Order <i>Nunc Pro Tunc</i> Regarding Findings of Fact and Conclusion of Law Entered November 21, 2019 in <i>180 Land Co. LLC v. City of Las Vegas</i> , Eighth Judicial District Court Case No. A-17-758528 (Feb. 6, 2019)	8	1400-1405
ZZZ	City of Las Vegas Agenda Memo – Planning, for City Council Meeting June 21, 2017, Re: GPA-68385, WVR-68480, SDR-68481, and TMP-68482 [PRJ-67184]	8	1406-1432

Exhibit	Exhibit Description	Vol.	Bates No.
AAAA	Excerpts from the Land Use and Rural Neighborhoods Preservation Element of the City's 2020 Master Plan adopted by the City Council of the City on September 2, 2009	8	1433-1439
BBBB	Summons and Complaint for Declaratory Relief and Injunctive Relief, and Verified Claims in Inverse Condemnation in <i>180 Land Co. LLC v. City of Las Vegas</i> , Eighth Judicial District Court Case No.A-18-780184-C	8	1440-1477
CCCC	Notice of Entry of Findings of Fact and Conclusions of Law Granting City of Las Vegas' Motion for Summary Judgment in <i>180 Land Co. LLC v. City of Las Vegas</i> , Eighth Judicial District Court Case No.A-18-780184-C (Dec. 30, 2020)	8	1478-1515
DDDD	Peter Lowenstein Declaration	9	1516-1522
DDDD-1	Exhibit 1 to Peter Lowenstein Declaration: Diagram of Existing Access Points	9	1523-1526
DDDD-2	Exhibit 2 to Peter Lowenstein Declaration: July 5, 2017 Email from Mark Colloton	9	1527-1531
DDDD-3	Exhibit 3 to Peter Lowenstein Declaration: June 28, 2017 Permit application	9	1532-1533
DDDD-4	Exhibit 4 to Peter Lowenstein Declaration: June 29, 2017 Email from Mark Colloton re Rampart and Hualapai	9	1534-1536
DDDD-5	Exhibit 5 to Peter Lowenstein Declaration: August 24, 2017 Letter from City Department of Planning	9	1537
DDDD-6	Exhibit 6 to Peter Lowenstein Declaration: July 26, 2017 Email from Peter Lowenstein re Wall Fence	9	1538
DDDD-7	Exhibit 7 to Peter Lowenstein Declaration: August 10, 2017 Application for Walls, Fences, or Retaining Walls; related materials	9	1539-1546
DDDD-8	Exhibit 8 to Peter Lowenstein Declaration: August 24, 2017 Email from Steve Gebeke	9	1547-1553
DDDD-9	Exhibit 9 to Peter Lowenstein Declaration: Bill No. 2018-24	9	1554-1569
DDDD-10	Exhibit 10 to Peter Lowenstein Declaration: Las Vegas City Council Ordinance No. 6056 and excerpts from Land Use & Rural Neighborhoods Preservation Element	9	1570-1577

Exhibit	Exhibit Description	Vol.	Bates No.
DDDD-11	Exhibit 11 to Peter Lowenstein Declaration: documents submitted to Las Vegas Planning Commission by Jim Jimmerson at February 14, 2017 Planning Commission meeting	9	1578-1587
EEEE	GPA-72220 application form	9	1588-1590
FFFF	Chris Molina Declaration	9	1591-1605
FFFF-1	Fully Executed Copy of Membership Interest Purchase and Sale Agreement for Fore Stars Ltd.	9	1606-1622
FFFF-2	Summary of Communications between Developer and Peccole family regarding acquisition of Badlands Property	9	1623-1629
FFFF-3	Reference map of properties involved in transactions between Developer and Peccole family	9	1630
FFFF-4	Excerpt of appraisal for One Queensridge place dated October 13, 2005	9	1631-1632
FFFF-5	Site Plan Approval for One Queensridge Place (SDR-4206)	9	1633-1636
FFFF-6	Securities Redemption Agreement dated September 14, 2005	9	1637-1654
FFFF-7	Securities Purchase Agreement dated September 14, 2005	9	1655-1692
FFFF-8	Badlands Golf Course Clubhouse Improvement Agreement dated September 6, 2005	9	1693-1730
FFFF-9	Settlement Agreement and Mutual Release dated June 28, 2013	10	1731-1782
FFFF-10	June 12, 2014 emails and Letter of Intent regarding the Badlands Golf Course	10	1783-1786
FFFF-11	July 25, 2014 email and initial draft of Golf Course Purchase Agreement	10	1787-1813
FFFF-12	August 26, 2014 email from Todd Davis and revised purchase agreement	10	1814-1843
FFFF-13	August 27, 2014 email from Billy Bayne regarding purchase agreement	10	1844-1846
FFFF-14	September 15, 2014 email and draft letter to BGC Holdings LLC regarding right of first refusal	10	1847-1848

Exhibit	Exhibit Description	Vol.	Bates No.
FFFF-15	November 3, 2014 email regarding BGC Holdings LLC	10	1849-1851
FFFF-16	November 26, 2014 email and initial draft of stock purchase and sale agreement	10	1852-1870
FFFF-17	December 1, 2015 emails regarding stock purchase agreement	10	1871-1872
FFFF-18	December 1, 2015 email and fully executed signature page for stock purchase agreement	10	1873-1874
FFFF-19	December 23, 2014 emails regarding separation of Fore Stars Ltd. and WRL LLC acquisitions into separate agreements	10	1875-1876
FFFF-20	February 19, 2015 emails regarding notes and clarifications to purchase agreement	10	1877-1879
FFFF-21	February 26, 2015 email regarding revised purchase agreements for Fore Stars Ltd. and WRL LLC	10	1880
FFFF-22	February 27, 2015 emails regarding revised purchase agreements for Fore Stars Ltd. and WRL LLC	10	1881-1882
FFFF-23	Fully executed Membership Interest Purchase Agreement for WRL LLC	10	1883-1890
FFFF-24	June 12, 2015 email regarding clubhouse parcel and recorded parcel map	10	1891-1895
FFFF-25	Quitclaim deed for Clubhouse Parcel from Queensridge Towers LLC to Fore Stars Ltd.	10	1896-1900
FFFF-26	Record of Survey for Hualapai Commons Ltd.	10	1901
FFFF-27	Deed from Hualapai Commons Ltd. to EHC Hualapai LLC	10	1902-1914
FFFF-28	Purchase Agreement between Hualapai Commons Ltd. and EHC Hualapai LLC	10	1915-1931
FFFF-29	City of Las Vegas' First Set of Interrogatories to Plaintiff	10	1932-1945
FFFF-30	Plaintiff 180 Land Company LLC's Responses to City of Las Vegas' First Set of Interrogatories to Plaintiff, 3 rd Supplement	10	1946-1973
FFFF-31	City of Las Vegas' Second Set of Requests for Production of Documents to Plaintiff	11	1974-1981

Exhibit	Exhibit Description	Vol.	Bates No.
FFFF-32	Plaintiff 180 Land Company LLC's Response to Defendant City of Las Vegas' Second Set of Requests for Production of Documents to Plaintiff	11	1982-1989
FFFF-33	September 14, 2020 Letter to Plaintiff regarding Response to Second Set of Requests for Production of Documents	11	1990-1994
FFFF-34	First Supplement to Plaintiff Landowners Response to Defendant City of Las Vegas' Second Set of Requests for Production of Documents to Plaintiff	11	1995-2002
FFFF-35	Motion to Compel Discovery Responses, Documents and Damages Calculation, and Related Documents on Order Shortening Time	11	2003-2032
FFFF-36	Transcript of November 17, 2020 hearing regarding City's Motion to Compel Discovery Responses, Documents and Damages Calculation, and Related Documents on Order Shortening Time	11	2033-2109
FFFF-37	February 24, 2021 Order Granting in Part and denying in part City's Motion to Compel Discovery Responses, Documents and Damages Calculation, and Related Documents on Order Shortening Time	11	2110-2118
FFFF-38	April 1, 2021 Letter to Plaintiff regarding February 24, 2021 Order	11	2119-2120
FFFF-39	April 6, 2021 email from Elizabeth Ghanem Ham regarding letter dated April 1, 2021	11	2121-2123
FFFF-40	Hydrologic Criteria and Drainage Design Manual, Section 200	11	2124-2142
FFFF-41	Hydrologic Criteria and Drainage Design Manual, Standard Form 1	11	2143
FFFF-42	Hydrologic Criteria and Drainage Design Manual, Standard Form 2	11	2144-2148
FFFF-43	Email correspondence regarding minutes of August 13, 2018 meeting with GCW regarding Technical Drainage Study	11	2149-2152
FFFF-44	Excerpts from Peccole Ranch Master Plan Phase II regarding drainage and open space	11	2153-2159
FFFF-45	Aerial photos and demonstrative aids showing Badlands open space and drainage system	11	2160-2163
FFFF-46	August 16, 2016 letter from City Streets & Sanitation Manager regarding Badlands Golf Course Drainage Maintenance	11	2164-2166

Exhibit	Exhibit Description	Vol.	Bates No.
FFFF-47	Excerpt from EHB Companies promotional materials regarding security concerns and drainage culverts	11	2167
GGGG	Landowners' Reply in Support of Countermotion for Judicial Determination of Liability on the Landowners' Inverse Condemnation Claims Etc. in <i>180 Land Co., LLC v. City of Las Vegas</i> , Eighth Judicial District Court Case No. A-17-758528-J (March 21, 2019)	11	2168-2178
HHHH	June 28, 2016 Letter from Mark Colloton re: Reasons for Access Points Off Hualapai Way and Rampart Blvd.	12	2179-2184
IIII	Transcript of City Council Meeting (May 16, 2018)	12	2185-2260
JJJJ	Excerpt of April 8, 2021 Transcript of Hearing re Plaintiffs' Motion for a New Trial and to Amend (March 11, 2021), Case No. A-18-780184-C	12	2261-2266
KKKK	Affidavit of Donald Richards and accompanying photographs submitted by the Developer on April 15, 2021 in Case No. A-18-780184-C	13	2267-2428
LLLL	Supplemental Declaration of Seth T. Floyd	14	2429-2432
LLLL-1	1981 Peccole Property Land Use Plan	14	2433-
LLLL-2	1985 Las Vegas General Plan	14	2434-2515
LLLL-3	1975 General Plan	14	2516-2611
LLLL-4	Planning Commission meeting records regarding 1985 General Plan	15	2612-2839
LLLL-5	1986 Venetian Foothills Master Plan	15	2840
LLLL-6	1989 Peccole Ranch Master Plan	15	2841
LLLL-7	1990 Master Development Plan Amendment	15	2842
LLLL-8	Citizen's Advisory Committee records regarding 1992 General Plan	15	2843-2860
LLLL-9	1992 Las Vegas General Plan	16-17	2861-3310
LLLL-10	1992 Southwest Sector Map	18	3311
LLLL-11	Ordinance No. 5250 (Adopting 2020 Master Plan)	18	3312-3319

Exhibit	Exhibit Description	Vol.	Bates No.
LLLL-12	Las Vegas 2020 Master Plan	18	3320-3402
LLLL-13	Ordinance No. 5787 (Adopting 2005 Land Use Element)	18	3403-3469
LLLL-14	2005 Land Use Element	18	3470-3527
LLLL-15	Ordinance No. 6056 (Adopting 2009 Land Use and Rural Neighborhoods Preservation Element)	18	3528-3532
LLLL-16	2009 Land Use and Rural Neighborhoods Preservation Element	19	3533-3632
LLLL-17	Ordinance No. 6152 (Adopting revisions to 2009 Land Use and Rural Neighborhoods Preservation Element)	19	3633-3642
LLLL-18	Ordinance No. 6622 (Adopting 2018 Land Use and Rural Neighborhoods Preservation Element)	19	3643-3653
LLLL-19	2018 Land Use & Rural Neighborhoods Preservation Element	19	3654-3753
MMMM	State of Nevada State Board of Equalization Notice of Decision, <i>In the Matter of Fore Star Ltd., et al.</i> (Nov. 30, 2017)	20	3754-3758
NNNN	Clark County Real Property Tax Values	20	3759-3774
OOOO	Clark County Tax Assessor's Property Account Inquiry - Summary Screen	20	3775-3776
PPPP	February 22, 2017 Clark County Assessor Letter to 180 Land Co. LLC, re Assessor's Golf Course Assessment	20	3777
QQQQ	Petitioner's Opening Brief, <i>In the matter of 180 Land Co. LLC</i> (Aug. 29, 2017), State Board of Equalization	20	3778-3815
RRRR	September 21, 2017 Clark County Assessor Stipulation for the State Board of Equalization	20	3816
SSSS	Excerpt of Reporter's Transcript of Hearing in <i>180 Land Co. v. City of Las Vegas</i> , Eighth Judicial District Court Case No. A-17-758528-J (Feb. 16, 2021)	20	3817-3868
TTTT	June 28, 2016 Letter from Mark Colloton re: Reasons for Access Points Off Hualapai Way and Rampart Blvd.	20	3869-3874

Exhibit	Exhibit Description	Vol.	Bates No.
UUUU	Transcript of City Council Meeting (May 16, 2018)	20	3875-3950
VVVV	Supplemental declaration of Seth Floyd	21	3951-3953
VVVV-1	Southwest Sector Land Use Map (1992)	21	3954
VVVV-2	10/10/1991 Planning Commission Minutes	21	3955-3957
VVVV-3	10/22/1991 Planning Commission Minutes	21	3958-3962
VVVV-4	11/14/1991 Planning Commission Minutes	21	3963-3965
VVVV-5	11/26/1991 Planning Commission Minutes	21	3966-3968
VVVV-6	12/12/1991 Planning Commission Minutes	21	3969-3976
VVVV-7	12/12/1991 Planning Commission Resolution adopting 1992 General Plan	21	3977-3978
VVVV-8	2/5/1992 City Council Meeting Minutes	21	3979
VVVV-9	2/18/1992 Recommending Committee Meeting Minutes	21	3980-4000
VVVV-10	2/19/1992 City Council Meeting Minutes	21	4001-4002
VVVV-11	3/12/1992 Planning Commission Meeting Minutes	21	4003-4004
VVVV-12	3/16/1992 Recommending Committee Meeting Minute	21	4005
VVVV-13	4/1/1992 City Council Meeting Minutes	21	4006-4008
VVVV-14	Ordinance No. 3636 (adopting new general plan)	21	4009-4011

Exhibit	Exhibit Description	Vol.	Bates No.
VVVV-15	2/13/1992 Citizens Advisory Committee Meeting Minutes	21	4012-4015
VVVV-16	3/27/1991 Citizens Advisory Committee Mailout	21	4016-4025
WWWW	Excerpts of NRCP 30(b)(6) Designee of Peccole Nevada Corporation – William Bayne	21	4026-4039
XXXX	Findings of Facts, Conclusions of Law and Order Regarding Motion to Dismiss and Countermotion to Allow More Definite Statement if Necessary and Countermotion to Stay Litigation of Inverse Condemnation Claims Until Resolution of the Petition for Judicial Review and Countermotion for NRCP Rule 56(F) Continuance	21	4040-4051
YYYY	Declaration of Christopher Molina in Support of the City's Countermotion for Summary Judgment and Opposition to Motion to Determine Property Interest	21	4052-4053
ZZZZ	Declaration of Seth Floyd	21	4054-4055
ZZZZ -1	Master planned communities with R-PD zoning	21	4056-4061
ZZZZ -2	General Plan Maps for Master Planned Communities with R-PD zoning	21	4062-4067
AAAAA	Recorder's Amended Transcript of Pending Motions in <i>180 Land Company LLC, et al. vs. City of Las Vegas</i> , Eighth Judicial District Court Case No. A-18-775804 (September 17, 2021)	22	4068-4235
BBBBB	December 23, 2021 letter from Seth Floyd re Entitlements on 17-acre Property; Applications for development of other segments of former Badlands Golf Course	22	4236-4238
CCCCC	July 19, 2022 letter from Seth Floyd re Entitlements on 17-acre portion of Badlands	22	4239-4240
DDDDD	Appraisal of Real Property prepared by The DiFederico Group re the 17-Acre Property	23	4241-4394
EEEEEE	Affidavit of Donald Richards (Ex. 50 to Plaintiff Landowners' Reply in Support of Countermotion for Discovery Pursuant to NRCP 56(d) filed 7/7/2021)	23	4395-4396
FFFFF	Bill No. 2018-5 (Ordinance No. 6617)	23	4397-4405

Exhibit	Exhibit Description	Vol.	Bates No.
GGGGG	Appraisal Consulting Report prepared by Charles E. Jack of Integra Realty Resources	24	4406-4586
HHHHH	Supplemental Declaration Peter Lowenstein	24	4587-4600
HHHHH-1	Email from Steve Swanton re PMP – 58526 and PMP-58527 (Queensridge/Badlands Golf Course)	24	4601-4602
HHHHH-2	June 8, 2015 letter to Angie Scott from Steve Swanton re PMP-59572	24	4603
HHHHH-3	Email from Stephanie Allen to Peter Lowenstein re Development Agreement	24	4604-4605
HHHHH-4	Email from Lucien Paet re New Badlands Parcel Map	24	4606
HHHHH-5	Approved Site Plan for SDR-62393	24	4607
IIIII	Declaration of Kevin McOsker	25	4608-4609
JJJJJ	Videotaped Deposition of Tio Stephan DiFederico, MAI	25	4610-4711
KKKKK	Appellant's Opening Brief filed 11/6/18 in Nevada Supreme Court Case No. 75481	26	4712-4791
LLLLL	Appellant's Amended Reply Brief filed 5/1/19 in Nevada Supreme Court Case No. 75481	26	4792-4829
MMMMM	City of Las Vegas's Motion for Summary Judgment filed 11/9/20 in the 65-Acre Case (No. A-18-780184-C)	26	4830-4862
NNNNN	Plaintiff Landowners' Opposition to the City's Motion for Summary Judgment Etc. filed 11/23/20 in the 65-Acre Case (No. A-18-780184-C)	26	4863-4950
OOOOO	City of Las Vegas' Motion to Remand 133-Acre Applications to the Las Vegas City Council filed 8/9/2021 in the 133-Acre Case (No. A-18-775804-J)	27	4951-4961
PPPPP	Notice of Entry of Findings of Fact, Conclusions of Law Regarding (1) Motion to Remand 133-Acre Applications to Las Vegas City Council and (2) Motion to Dismiss Civil Complaint Improperly Joined with Petition for Judicial Review	27	4962-4973

Exhibit	Exhibit Description	Vol.	Bates No.
QQQQQ	Deposition Transcript of Charles E. Jack, June 16, 2022	28	4974-5168
RRRRR	Deposition Transcript of NRCP 30(b)(6) Designee of Peccole Nevada Corporation – William Bayne	29	5169-5411
SSSSS	Order Granting the City of Las Vegas' Motion to Compel and for an Order to Show Cause in the 35-Acre Case (No. A-17-758528-J)	30	5412-5416
TTTTT	Order Granting the City of Las Vegas' Objection to the Discovery Commissioner's Report and Recommendation in the 35-Acre Case (No. A-17-758528-J)	30	5417-5422
UUUUU	Appraisal of Real Property prepared by The DiFederico Group re the 35-Acre Property	30	5423-5558
VVVVV	Excerpts of Deposition Transcript of Yohan Lowie	31	5559-5566
WWWWW	Declaration of Philip R. Byrnes in Support of City's Reply in Support of City's Renewed Motion for Summary Judgment and City's Motion to Strike Developer's Countermotion for Approval of Entitlements and to End Take	32	5567-5568
WWWWW-1	Agenda Summary Page for Item 28 of the August 3, 2022 Las Vegas City Council meeting	32	5569-5570
WWWWW-2	Settlement Proposal	32	5571-5583
XXXXX	Order Granting Stay	33	5584-5588
YYYYY	Declaration of Oh-Sang Kwon	34	5589-5595
YYYYY-1	Technical Drainage Study for the Seventy 840-050 March 2016	34-35	5596-5982
YYYYY-2	Supplement to Technical Drainage Study for the Seventy 840-050 March 2016	35	5983-6024
YYYYY-3	March 24, 2016 City of Las Vegas Inter-Office Memorandum re Drainage Study for The Seventy	36	6025-6028
YYYYY-4	September 2017 Response to 1st CLV Comments on the Technical Drainage Study for the 435 (Formerly "The Seventy")	36	6029-6193
YYYYY-5	September 14, 2017 - Improvement Plans for the 435	37	6194-6210
YYYYY-6	March 24, 2016 City of Las Vegas Inter-Office Memorandum re Drainage Study for The Seventy	37	6211-6215
YYYYY-7	January 2018 Response to 2nd CLV Comments on the Technical Drainage Study for the 435 (Formerly "The Seventy")	37	6216-6292

Exhibit	Exhibit Description	Vol.	Bates No.
YYYYYY-8	January 10, 2018 - Improvement Plans for the 435	37	6293-6309
YYYYYY-9	February 1, 2018 City of Las Vegas Inter-Office Memorandum re Drainage Study for the 435 formerly the SEVENTY	37	6310-6314
YYYYYY-10	June 2018 Response to 3 rd CLV Comments on the Technical Drainage Study for the 435 (Formerly "The Seventy")	38	6315-6461
YYYYYY-11	Improvement Plans for the 435	39	6462-6483
YYYYYY-12	July 26, 2018 City of Las Vegas Inter-Office Memorandum re Drainage Study for the 435 formerly the Seventy	39	6484-6489
YYYYYY-13	August 13, 2016 GCW Engineers Meeting Minutes	39	6490-6495
YYYYYY-14	Email re The 435 TD5 Comments Review Meeting	39	6496-6499
ZZZZZ	Declaration of Michael Cunningham	39	6500
ZZZZZ-1	Administrative Code, 2019 Edition	39	6501-6507

Dated this 23rd day of November, 2022.

McDONALD CARANO LLP

By: /s/ George F. Ogilvie III

George F. Ogilvie III (NV Bar No. 3552)
Christopher Molina (NV Bar No. 14092)
2300 W. Sahara Avenue, Suite 1200
Las Vegas, Nevada 89102

LAS VEGAS CITY ATTORNEY'S OFFICE
Bryan K. Scott (NV Bar No. 4381)
Philip R. Byrnes (NV Bar No. 166)
Rebecca Wolfson (NV Bar No. 14132)
495 South Main Street, 6th Floor
Las Vegas, Nevada 89101

SHUTE, MIHALY & WEINBERGER, LLP
Andrew W. Schwartz (CA Bar No. 87699)
(Admitted *pro hac vice*)
Lauren M. Tarpey (CA Bar No. 321775)
(Admitted *pro hac vice*)
396 Hayes Street
San Francisco, California 94102

Attorneys for City of Las Vegas

1 **CERTIFICATE OF SERVICE**

2 I HEREBY CERTIFY that I am an employee of McDonald Carano LLP, and that on the 23rd
3 day of November, 2022, I caused a true and correct copy of the foregoing **FOURTH SUPPLEMENTAL**
4 **APPENDIX OF EXHIBITS IN SUPPORT OF CITY’S COUNTERMOTION FOR SUMMARY**
5 **JUDGMENT ON JUST COMPENSATION – VOLUME 37** to be electronically served with the
6 Clerk of the Court via the Clark County District Court Electronic Filing Program which will provide
7 copies to all counsel of record registered to receive such electronic notification.

8 /s/ Jelena Jovanovic

9 An employee of McDonald Carano LLP

EXHIBIT “YYYYYY-5”

APN: 138-32-301-005
APN: 138-32-301-007

BASIS OF BEARINGS
NORTH 89°40'30" EAST, BEING THE BEARING OF THE SOUTH LINE OF THE SOUTHEAST QUARTER (BE 1/4) OF SECTION 31, TOWNSHIP 20 SOUTH, RANGE 60 EAST, M.D.M., AS SHOWN IN FILE 120, PAGE 49 OF PARCEL MAPS ON FILE AT THE CLARK COUNTY, NEVADA RECORDER'S OFFICE.

CLV295640 6104

[illegible]

LEGEND	
-----	PROPOSED UTILITIES
-----	EXISTING UTILITIES
-----	FUTURE UTILITIES
-----	SECTION LINE
-----	RIGHT-OF-WAY LINE
-----	PROPERTY LINE
-----	EXISTING DRAINAGE DRAIN LINE
-----	PROPOSED DRAINAGE DRAIN LINE
-----	EXISTING STORM DRAIN
-----	PROPOSED STORM DRAIN
-----	NEW FENCE
-----	NEW ABANDONED PIPE
-----	RETAINING WALL
-----	EXISTING FLOOD WALLS
-----	FLOOD ZONE 1' W/ LIMITS
-----	LIMITS OF CONSTRUCTION
-----	LIMITS OF GRADED ACCESS WAY
-----	EXISTING DRAINAGE EASEMENT
-----	PROPOSED DRAINAGE EASEMENT
-----	EXISTING BEARING WALL

[illegible]


[illegible]











THE 435

1555 S. RAINBOW BLVD.
LAS VEGAS, NV 89146
T: 702.804.2000
F: 702.804.2299
gcbwengineering.com

TDS SUBMITTAL



TDS SUBMITTAL



DATE	DESCRIPTION
09/14/2017	DESIGN
	DATE
	DESCRIPTION
	DATE
	DESCRIPTION
	DATE
	DESCRIPTION

PROJECT NO.	840-050
DATE	09/14/2017
DESCRIPTION	DESIGN
DATE	09/14/2017
DESCRIPTION	DESIGN
DATE	09/14/2017
DESCRIPTION	DESIGN

PROJECT NO.	840-050
DATE	09/14/2017
DESCRIPTION	DESIGN
DATE	09/14/2017
DESCRIPTION	DESIGN
DATE	09/14/2017
DESCRIPTION	DESIGN

GCW ENGINEERS & SURVEYORS
 1555 S. RAINBOW BLVD.
 LAS VEGAS, NV 89146
 P: 702.804.2299
 F: 702.804.2299
 gowengineering.com

SEVENTY ACRES, LLC
 FORE STARS, LTD
 THE 435
 SECTIONS & DETAILS 2

C8.02
 DRAWING
 16 OF 17 SHEETS








TABLE OF DIMENSIONS

SIZE	W	D	H	W	D	H	W	D	H	W	D	H
18\"/>												

TABLE OF MATERIALS

ITEM	DESCRIPTION	QUANTITY	UNIT	PRICE
1	CONCRETE (C-15)	1.00	CU YD	1.00
2	CONCRETE (C-20)	1.00	CU YD	1.00
3	CONCRETE (C-25)	1.00	CU YD	1.00
4	CONCRETE (C-30)	1.00	CU YD	1.00
5	CONCRETE (C-35)	1.00	CU YD	1.00
6	CONCRETE (C-40)	1.00	CU YD	1.00
7	CONCRETE (C-45)	1.00	CU YD	1.00
8	CONCRETE (C-50)	1.00	CU YD	1.00
9	CONCRETE (C-55)	1.00	CU YD	1.00
10	CONCRETE (C-60)	1.00	CU YD	1.00
11	CONCRETE (C-65)	1.00	CU YD	1.00
12	CONCRETE (C-70)	1.00	CU YD	1.00
13	CONCRETE (C-75)	1.00	CU YD	1.00
14	CONCRETE (C-80)	1.00	CU YD	1.00
15	CONCRETE (C-85)	1.00	CU YD	1.00
16	CONCRETE (C-90)	1.00	CU YD	1.00
17	CONCRETE (C-95)	1.00	CU YD	1.00
18	CONCRETE (C-100)	1.00	CU YD	1.00
19	CONCRETE (C-105)	1.00	CU YD	1.00
20	CONCRETE (C-110)	1.00	CU YD	1.00
21	CONCRETE (C-115)	1.00	CU YD	1.00
22	CONCRETE (C-120)	1.00	CU YD	1.00
23	CONCRETE (C-125)	1.00	CU YD	1.00
24	CONCRETE (C-130)	1.00	CU YD	1.00
25	CONCRETE (C-135)	1.00	CU YD	1.00
26	CONCRETE (C-140)	1.00	CU YD	1.00
27	CONCRETE (C-145)	1.00	CU YD	1.00
28	CONCRETE (C-150)	1.00	CU YD	1.00
29	CONCRETE (C-155)	1.00	CU YD	1.00
30	CONCRETE (C-160)	1.00	CU YD	1.00
31	CONCRETE (C-165)	1.00	CU YD	1.00
32	CONCRETE (C-170)	1.00	CU YD	1.00
33	CONCRETE (C-175)	1.00	CU YD	1.00
34	CONCRETE (C-180)	1.00	CU YD	1.00
35	CONCRETE (C-185)	1.00	CU YD	1.00
36	CONCRETE (C-190)	1.00	CU YD	1.00
37	CONCRETE (C-195)	1.00	CU YD	1.00
38	CONCRETE (C-200)	1.00	CU YD	1.00
39	CONCRETE (C-205)	1.00	CU YD	1.00
40	CONCRETE (C-210)	1.00	CU YD	1.00
41	CONCRETE (C-215)	1.00	CU YD	1.00
42	CONCRETE (C-220)	1.00	CU YD	1.00
43	CONCRETE (C-225)	1.00	CU YD	1.00
44	CONCRETE (C-230)	1.00	CU YD	1.00
45	CONCRETE (C-235)	1.00	CU YD	1.00
46	CONCRETE (C-240)	1.00	CU YD	1.00
47	CONCRETE (C-245)	1.00	CU YD	1.00
48	CONCRETE (C-250)	1.00	CU YD	1.00
49	CONCRETE (C-255)	1.00	CU YD	1.00
50	CONCRETE (C-260)	1.00	CU YD	1.00
51	CONCRETE (C-265)	1.00	CU YD	1.00
52	CONCRETE (C-270)	1.00	CU YD	1.00
53	CONCRETE (C-275)	1.00	CU YD	1.00
54	CONCRETE (C-280)	1.00	CU YD	1.00
55	CONCRETE (C-285)	1.00	CU YD	1.00
56	CONCRETE (C-290)	1.00	CU YD	1.00
57	CONCRETE (C-295)	1.00	CU YD	1.00
58	CONCRETE (C-300)	1.00	CU YD	1.00
59	CONCRETE (C-305)	1.00	CU YD	1.00
60	CONCRETE (C-310)	1.00	CU YD	1.00
61	CONCRETE (C-315)	1.00	CU YD	1.00
62	CONCRETE (C-320)	1.00	CU YD	1.00
63	CONCRETE (C-325)	1.00	CU YD	1.00
64	CONCRETE (C-330)	1.00	CU YD	1.00
65	CONCRETE (C-335)	1.00	CU YD	1.00
66	CONCRETE (C-340)	1.00	CU YD	1.00
67	CONCRETE (C-345)	1.00	CU YD	1.00
68	CONCRETE (C-350)	1.00	CU YD	1.00
69	CONCRETE (C-355)	1.00	CU YD	1.00
70	CONCRETE (C-360)	1.00	CU YD	1.00
71	CONCRETE (C-365)	1.00	CU YD	1.00
72	CONCRETE (C-370)	1.00	CU YD	1.00
73	CONCRETE (C-375)	1.00	CU YD	1.00
74	CONCRETE (C-380)	1.00	CU YD	1.00
75	CONCRETE (C-385)	1.00	CU YD	1.00
76	CONCRETE (C-390)	1.00	CU YD	1.00
77	CONCRETE (C-395)	1.00	CU YD	1.00
78	CONCRETE (C-400)	1.00	CU YD	1.00
79	CONCRETE (C-405)	1.00	CU YD	1.00
80	CONCRETE (C-410)	1.00	CU YD	1.00
81	CONCRETE (C-415)	1.00	CU YD	1.00
82	CONCRETE (C-420)	1.00	CU YD	1.00
83	CONCRETE (C-425)	1.00	CU YD	1.00
84	CONCRETE (C-430)	1.00	CU YD	1.00
85	CONCRETE (C-435)	1.00	CU YD	1.00
86	CONCRETE (C-440)	1.00	CU YD	1.00
87	CONCRETE (C-445)	1.00	CU YD	1.00
88	CONCRETE (C-450)	1.00	CU YD	1.00
89	CONCRETE (C-455)	1.00	CU YD	1.00
90	CONCRETE (C-460)	1.00	CU YD	1.00
91	CONCRETE (C-465)	1.00	CU YD	1.00
92	CONCRETE (C-470)	1.00	CU YD	1.00
93	CONCRETE (C-475)	1.00	CU YD	1.00
94	CONCRETE (C-480)	1.00	CU YD	1.00
95	CONCRETE (C-485)	1.00	CU YD	1.00
96	CONCRETE (C-490)	1.00	CU YD	1.00
97	CONCRETE (C-495)	1.00	CU YD	1.00
98	CONCRETE (C-500)	1.00	CU YD	1.00
99	CONCRETE (C-505)	1.00	CU YD	1.00
100	CONCRETE (C-510)	1.00	CU YD	1.00
101	CONCRETE (C-515)	1.00	CU YD	1.00
102	CONCRETE (C-520)	1.00	CU YD	1.00
103	CONCRETE (C-525)	1.00	CU YD	1.00
104	CONCRETE (C-530)	1.00	CU YD	1.00
105	CONCRETE (C-535)	1.00	CU YD	1.00
106	CONCRETE (C-540)	1.00	CU YD	1.00
107	CONCRETE (C-545)	1.00	CU YD	1.00
108	CONCRETE (C-550)	1.00	CU YD	1.00
109	CONCRETE (C-555)	1.00	CU YD	1.00
110	CONCRETE (C-560)	1.00	CU YD	1.00
111	CONCRETE (C-565)	1.00	CU YD	1.00
112	CONCRETE (C-570)	1.00	CU YD	1.00
113	CONCRETE (C-575)	1.00	CU YD	1.00
114	CONCRETE (C-580)	1.00	CU YD	1.00
115	CONCRETE (C-585)	1.00	CU YD	1.00
116	CONCRETE (C-590)	1.00	CU YD	1.00
117	CONCRETE (C-595)	1.00	CU YD	1.00
118	CONCRETE (C-600)	1.00	CU YD	1.00
119	CONCRETE (C-605)	1.00	CU YD	1.00
120	CONCRETE (C-610)	1.00	CU YD	1.00
121	CONCRETE (C-615)	1.00	CU YD	1.00
122	CONCRETE (C-620)	1.00	CU YD	1.00
123	CONCRETE (C-625)	1.00	CU YD	1.00
124	CONCRETE (C-630)	1.00	CU YD	1.00
125	CONCRETE (C-635)	1.00	CU YD	1.00
126	CONCRETE (C-640)	1.00	CU YD	1.00
127	CONCRETE (C-645)	1.00	CU YD	1.00
128	CONCRETE (C-650)	1.00	CU YD	1.00
129	CONCRETE (C-655)	1.00	CU YD	1.00
130	CONCRETE (C-660)	1.00	CU YD	1.00
131	CONCRETE (C-665)	1.00	CU YD	1.00
132	CONCRETE (C-670)	1.00	CU YD	1.00
133	CONCRETE (C-675)	1.00	CU YD	1.00
134	CONCRETE (C-680)	1.00	CU YD	1.00
135	CONCRETE (C-685)	1.00	CU YD	1.00
136	CONCRETE (C-690)	1.00	CU YD	1.00
137	CONCRETE (C-695)	1.00	CU YD	1.00
138	CONCRETE (C-700)	1.00	CU YD	1.00
139	CONCRETE (C-705)	1.00	CU YD	1.00
140	CONCRETE (C-710)	1.00	CU YD	1.00
141	CONCRETE (C-715)	1.00	CU YD	1.00
142	CONCRETE (C-720)	1.00	CU YD	1.00
143	CONCRETE (C-725)	1.00	CU YD	1.00
144	CONCRETE (C-730)	1.00	CU YD	1.00
145	CONCRETE (C-735)	1.00	CU YD	1.00
146	CONCRETE (C-740)	1.00	CU YD	1.00
147	CONCRETE (C-745)	1.00	CU YD	1.00
148	CONCRETE (C-750)	1.00	CU YD	1.00
149	CONCRETE (C-755)	1.00	CU YD	1.00
150	CONCRETE (C-760)	1.00	CU YD	1.00
151	CONCRETE (C-765)	1.00	CU YD	1.00
152	CONCRETE (C-770)	1.00	CU YD	1.00
153	CONCRETE (C-775)	1.00	CU YD	1.00
154	CONCRETE (C-780)	1.00	CU YD	1.00
155	CONCRETE (C-785)	1.00	CU YD	1.00
156	CONCRETE (C-790)	1.00	CU YD	1.00
157	CONCRETE (C-795)	1.00	CU YD	1.00
158	CONCRETE (C-800)	1.00	CU YD	1.00
159	CONCRETE (C-805)	1.00	CU YD	1.00
160	CONCRETE (C-810)	1.00	CU YD	1.00
161	CONCRETE (C-815)	1.00	CU YD	1.00
162	CONCRETE (C-820)	1.00	CU YD	1.00
163	CONCRETE (C-825)	1.00	CU YD	1.00
164	CONCRETE (C-830)	1.00	CU YD	1.00
165	CONCRETE (C-835)	1.00	CU YD	1.00
166	CONCRETE (C-840)	1.00	CU YD	1.00
167	CONCRETE (C-845)	1.00	CU YD	1.00
168	CONCRETE (C-850)	1.00	CU YD	1.00
169	CONCRETE (C-855)	1.00	CU YD	1.00
170	CONCRETE (C-860)	1.00	CU YD	1.00
171	CONCRETE (C-865)	1.00	CU YD	1.00
172	CONCRETE (C-870)	1.00	CU YD	1.00
173	CONCRETE (C-875)	1.00	CU YD	1.00
174	CONCRETE (C-880)	1.00	CU YD	1.00
175	CONCRETE (C-885)	1.00	CU YD	1.00
176	CONCRETE (C-890)	1.00	CU YD	1.00
177	CONCRETE (C-895)	1.00	CU YD	1.00
178	CONCRETE (C-900)	1.00	CU YD	1.00
179	CONCRETE (C-905)	1.00	CU YD	1.00
180	CONCRETE (C-910)	1.00	CU YD	1.00
181	CONCRETE (C-915)	1.00	CU YD	1.00
182	CONCRETE (C-920)			

DRAWING
C8.03
17 OF 17 SHEETS




SEVENTY ACRES, LLC
FORE STARS, LTD.
THE 435
SECTIONS & DETAILS 3

GCW
ENGINEERS & SURVEYORS

1555 S. RAINBOW BLVD
LAS VEGAS, NV 89146
P: 702.804.2299
F: 702.804.2298
gcwengineering.com

PROJECT NO.
840-050

DATE	DESCRIPTION
09/14/2017	TDS SUBMITTAL



CONSTRUCTION NOTES
● INSTALL 8" INCH BYPASS LINDS (200 - 4")
● BURY FILLER TUBES

EXHIBIT “YYYYYY-6”

CITY OF LAS VEGAS INTER-OFFICE MEMORANDUM			DATE: November 9, 2017
TO: Land Development Services Department of Building & Safety			FROM: Albert Sung, P.E. Flood Control Project Engineer Department of Public Works
SUBJECT:	Drainage Study for: The 435 formerly The SEVENTY		COPIES TO: GCW Engineers
Cross Streets:	SWC of Rampart & Alta		Seventy Acres LLC
File Number:	F:\Depot\DSMemos\DS4787B.ZNA.doc		Bart Anderson, P.E., DevCo
Parcel Number:	138-32-301-005, 006, 210-008		CCRFCD
Zoning Action:	SDR-62393; GPA-62387; ZON-62392		
FEMA Flood Zone	YES	X NO	
Proposed Storm Drain	YES	X NO	

HISTORY	DATE RECEIVED	DATE REVIEWED	COMMENTS	REVIEW FEES	FEES PAID Payment Trn #
1 st Submittal	3/3/2016 & 3/9/2016	3/23/2016	See Comments Below	\$400.00	425231: \$400
2 nd Submittal	9/18/17	11/9/2017	See Comments Below	\$400.00	490193: \$400
			TOTAL FEES (LDDRS):	\$800.00	----

REMARKS: This site development is within a FEMA SPECIAL FLOOD HAZARD AREA, Zone A. No permits of any kind will be issued for this project until a Conditional Letter of Map Revision (CLOMR/CLOMR-F) is received from FEMA.

The Drainage Study for the subject project has been reviewed and:

	is approved subject to conformance to all City standards and the following conditions:
X	must be resubmitted or supplemented including the following:
	is conditionally approved subject to Clark County Regional Flood Control District concurrence.
	is conditionally approved subject to NDOT concurrence.

1. This site development is located within a FEMA SPECIAL FLOOD HAZARD AREA, Zone A. **No permits will be issued until a Conditional Letter of Map Revision (CLOMR/CLOMR-F) is received from FEMA. Permits may be issued upon the receipt of Conditional Letter of Map Revision (CLOMR or CLOMR-F) from FEMA.**
2. A Letter of Map Revision (LOMR/LOMR-F) must be obtained from FEMA after the completion of any project within a FEMA Special Flood Hazard Area, Flood Zone "A". The bonded improvements shall include a line item of **\$50,000.00** for the LOMR. The bonded improvements will not be released until the LOMR/LOMR-F is obtained from FEMA and filed with the City of Las Vegas.

3. Sites with a grade difference of 2 feet above or below existing are required to have approval from the *City Planning and Development Department*. The engineer must submit copies of the grading plans and detail sheet with a letter justifying the grade difference to the *City Planning Department* (229-6301). The submitted letter did not include the Planning Department approval. The engineer must provide Planning approval with the next submittal.
4. The site is located within the Flood Zone A and is adjacent to an existing or proposed *Clark County Regional Flood Control District* (CCRFC) master planned facility. Therefore, CCRFC concurrence is required prior to final approval of the drainage study.
5. Please obtain necessary 404 permits from US Army Corps of Engineers and provide a copy of the permit to City of Las Vegas Flood Control Section prior to issuance of the grading permit. Contact the St. George Field Office of the US Army Corps of Engineers for permit information.
6. The provided WSPG model shall be extended further downstream incorporating the FEMA approved analysis for the Village at Queensridge LOMR with your update and slightly higher flow rates. Revise the WSPG Exhibit to include extending the WSPG Stations shown on the plan to the downstream limits shown with the previous LOMR.
7. The provided WSPG analysis used a *n-values* of 0.013 and 0.015. Provide an additional WSPG analysis of the two main line RCB's using an appropriate *n-values* to reflect the rougher, tined bottom surface within the boxes in order to analyze the effects it will have on the HGLs and freeboard requirements. Any velocities above 35 feet per second with proposed mitigation measures may require additional mitigation measures to reduce the velocities and are subject to further comment by the City as well as CCRFC review and acceptance. Provide a summary table showing the different *n-values* used and the resulting velocities, HGLs and minimum freeboard elevations. Revise the plans to reflect the HGLs during the worst case scenario and provide supporting freeboard calculations.
8. Provide a HEC-RAS analysis that incorporates the interim channel and entry structure flows. Extend the analysis sufficiently upstream to model the existing natural channel sections. Extend the analysis sufficiently downstream to model the concrete channel structure and extend the channel into the RCB area to normalize the flows to match the WSPG analysis. The combined HEC-RAS & WSPG analysis needs to verify that the interim entry structure has adequate freeboard. Include an Exhibit showing new cross sections that incorporate the detailed grading plans for the inlet structures within the HEC-RAS analysis.
9. Provide complete *Plans and Project Specifications* for approval by the *City of Las Vegas*. The Structural Plans and Details shall be a part of the Civil Improvement Plan set. This project is considered as a *Capital Improvement Project* (CIP) with developer funding.
10. Structural plans for the proposed storm drain improvements and pertinent flood control facilities must be submitted for review. Provide a soils report, structural calculations and specifications, two wet stamped structural sets, and a grading plan to the *Building Department* for processing. The engineer must provide a copy of *Building Department* approval of the structures to Regional Flood prior to their concurrence and to *Flood Control* prior to final acceptance of the drainage study.
11. All proposed improvements associated with the Storm Drain facilities shall be bonded and inspected. This project shall require Special Inspection. Coordinate the requirements of and the Agreements needed for Special Inspection with the Building Department.
12. The proposed improvements show drainage facilities of a size that must be reviewed for access and maintenance concerns. The engineer must submit an extra set of improvement plans to the *City Streets & Sanitation Department* for their review and comments. *Streets & Sanitation Department's* approval must be secured prior to the conditional drainage study approval.

13. Provide plans and sections of the proposed interim open channel section. Include fall protection, access ladders, and a conceptual section to make this channel a future Box Structure.
14. The provided access roads shall be included within easements dedicated to the City and clearly labeled on the plans. Provide details and show any access gates (16-foot minimum gate width) as necessary to accommodate the 12-foot wide access roads.
15. Revise the access road detail to provide a minimum of 6" Type II. Show turnaround areas for dead end segments. In addition, provide an access road to the interim channel area to the west.
16. Storm Drain Construction Note 1 does not match Construction Note 4. Revise accordingly.
17. Construction Note 10 indicates a 2:1 maximum slope but a 1:1 slope is shown on the plans. Revise accordingly.
18. Provide a list of estimated quantities on the plans for both public and private drainage facilities.
19. Revise Drainage Construction Notes 1 and 2 to match the dimensions of additional concrete clearance indicated in Details 1 and 2 on Sheet C8.02.
20. Provide new public drainage easements for the area of the site impacted by the proposed MPU facility improvements. The easement shall note that the public drainage improvements (MPU facilities) are publicly maintained and all onsite storm drain and surface improvements are privately maintained and the easement must be dedicated and recorded by separate document prior to the final acceptance of the improvement plans. Provide legal description and an exhibit of the drainage easement to Flood Control and *Rae Heller* (702-229-2139) of *City of Las Vegas Right of Way Section* for the recordation process after the subject drainage study is conceptually approved. The existing drainage easements shall be vacated by separate action and the recording of the new easements shall be done consecutively.
21. Provide a detail of the proposed riprap areas that include the Type II and geotextile fabric in the detail section. Revise all pertinent plans and callouts accordingly.
22. Detail 9 on Sheet C8.01 shows a 2.0% slope while the plans and FlowMaster model reflect a 1.0% slope. Revise detail to match plan and hydraulic model. In addition, add dimensions, show rip rap, rip rap size and construction on Detail 9.
23. Provide a cross sectional detail of the rip rap channel just upstream of the weir to show the construction of the rip rap and provide detailed grading plans of the interim improvements that include sufficient spot grades to indicate extents of the rip rap.
24. Indicate the minimum Finished Floor Elevations on the plans of the rough graded pads adjacent to the storm drain facilities.
25. Technical drainage studies are required for each of the future development super pads. The technical drainage studies for the developments may not be submitted until the conditional approval of this pertinent infrastructure drainage study is obtained. Final approval for the infrastructure study must be obtained prior to conditional approval of the impacted development super pad drainage studies.
26. Complete the Construction Notes on the Grading Plan including pavement section and reference details for the call-outs of proposed improvements, i.e. RCB's, rip-rap, structure details, manholes, inlets, etc.

27. This project currently has no Proposed Buildings or Structures. Should the project propose changes to this design assumption, then the Engineer is to update the drainage study detailing the flood zone impacts and provide addresses for each building in a FEMA Flood Hazard Zone prior to obtaining a grading permit. This information is necessary to insure that the elevation certificates are provided for each address prior to completion of construction. This information is required until such time as a LOMR is approved that removes the development from the SFHA.

Flood Control understands that this overall project will be developed in Phases. The following comments are repeated to reflect items that shall be addressed in future study updates as the Phases develop.

28. Proposed storm drain laterals have been identified to collect flows from Peccole West Lot 9 and Queensridge Fairway Homes. Extend the storm drain system to collect the 100-year flows from these adjacent subdivisions.

29. Continue to coordinate the MPU facility changes that are proposed with this development.

30. Storm drain facilities are located on cut/fill slopes. Revise the slopes and/or the storm drain alignment to maintain 12-foot access roads. Provide a cross section detail of the maintenance access.

31. Provide a concrete pad and maintenance access to the inlet structures for the local storm drains. Show the needed drainage easements for these facilities.

32. The existing and proposed utility crossings of the storm drain must be shown on the storm drain plan and profiles sheets and on the lateral profiles. Indicate the type of pipe material for water and sewer lines. Review separation requirements between utilities and show all of the utility crossings of the storm drains.

NOTE: Please be advised that all land surface area disturbances over 1 acre or any area adjacent to a water way must submit to the *Nevada Division of Environmental Protection* a "Notice of Intent" to discharge that certifies a stormwater pollution prevention plan has been developed and is maintained on site; for inclusion in the Stormwater General Permit No. NVR100000. A phased construction unit in a contiguous subdivision is considered under construction until all stripped or disturbed surface areas have been covered by paving, building construction or planting. For more information, including forms and applications see <http://ndep.nv.gov/bwpc/storm01.htm> or call (775) 687-9429.

NOTE: The engineer must submit the drainage study to FEMA for a Conditional Letter of Map Revision (CLOMR). A favorable CLOMR must be obtained prior to the issuance of any permits. This site is located in a FEMA Zone A. Clark County Regional Flood Control District (CCRFCDD) review and approval is required prior to recordation of final map or issuance of building/grading permits. The Engineer must send a copy of the report to the CCRFCDD for review. The developer/engineer must also obtain a Letter of Map Revision (LOMR) using the approved drainage study as technical support to inform FEMA of the modifications within the flood zone. The approved LOMR must be submitted to the City of Las Vegas prior to the release of the bond. FEMA Elevation Certificates, showing as-built finish floor elevations, must be completed for each building in the FEMA A Zone. The certificate must be submitted to the City of Las Vegas Flood Control Section prior to scheduling a framing inspection.

END OF REMARKS
JKN/PBJ

T/R/S: T20S/R60E/12
AREA L-32

EXHIBIT “YYYYYY-7”

**RESPONSE TO 2ND CLV COMMENTS
ON THE
TECHNICAL DRAINAGE STUDY FOR THE 435
(FORMERLY "THE SEVENTY")**

840-050

January 2018

Prepared for:

**Seventy Acres LLC, Fore Stars LTD, and 180 Land Co LLC
9775 West Charleston Boulevard
Las Vegas, Nevada 89117
Phone: (702) 940-6930
Fax: (702) 940-6931**



CLV295847

6216

REPLY APP 1140

HYDROLOGIC CRITERIA AND DRAINAGE MANUAL
DRAINAGE STUDY INFORMATION FORM

Name of Development: The 435 (formerly known as The Seventy) Date: January 2018

Location of Development: a) Descriptive (Cross Streets) North/South: Hualapai Way

East/West: Rampart Boulevard

b) Section: 32 Township: 20S Range: 60E

c) APN : 138-32-301-005

Name of Owner: Seventy Acres LLC

Telephone No.: (702) 940-6930 Fax No.: (702) 940-6931 E-Mail Address: frank@EHBcompanies.com

Address: 9775 W. Charleston Blvd., Las Vegas, Nevada 89117

Contact Person-Name: Steve Jones, P.E. Telephone No.: (702) 804-2000

* E-Mail Address: SJones@gcwengineering.com Fax No.: (702) 804-2299

Firm: GCW, Inc.

Address: 1555 South Rainbow Blvd, Las Vegas, NV 89146

Type of Land Development/Land Disturbance Process:

☐	Rezoning	☐	Subdivision Map	☐	Clearing and Grading Only
☐	Parcel Map	☐	Planned Unit Development	☒	Other (Please specify below)
☐	Large Parcel Map	☐	Building Permit	☐	Conceptual Drianage, Rough Grade, SD

1. Total Owned Land Area: At Site: +/- 70.52 acres Being Developed/Disturbed: +/- 17.5 acres

2. Is a portion or all of the subject property located in a designated FEMA Flood Hazard Area? ☒ Yes** ☐ No

3. Is the property bordered or crossed by an existing or proposed Clark County Regional Flood Control District Master Planned Facility? ☒ Yes** ☐ No

4. Proposed type of development (Residential, Commercial, Etc.): Conceptual Drainage, Rough Grade, and Storm Drain Improvements

5. Approximate upstream land area which drains to the subject site: +/- 3.73 sq. mi.

6. Has the site drainage been evaluated in the past? ☒ YES ☐ NO If yes, please identify documentation: Peccole Ranch West Master Study, Queensridge LOMR, Queens Borough Culvert Study

7. If known, please briefly identify the proposed discharge point(s) of runoff from the site: Existing dual (2) - 12'X 12' RCB at northeast corner of site

8. Briefly describe your proposed schedule for the subject project: Phase 1 Infrastructure (This Study), Phase 1 Improvements (Future Study), Phase 2 - Remaining 52.1 acres (Future Studies)



Engineer's Seal

Submit this form as part of the required drainage study to the local entity which has jurisdiction over the subject property. This form may provide sufficient information to serve as the Conceptual Drainage Study.

***New Required Field**

****Review and concurrence of the Clark County Regional Flood Control District is required.**

Local Entity File No.	Revision	Date

REFERENCE:

STANDARD FORM 1

**RESPONSE TO 2ND CLV COMMENTS
ON THE
TECHNICAL DRAINAGE STUDY FOR THE 435
(FORMERLY "THE SEVENTY")**

840-050

January 2018

Prepared for:

Seventy Acres LLC, Fore Stars LTD, and 180 Land Co LLC
9775 West Charleston Boulevard
Las Vegas, Nevada 89117
Phone: (702) 940-6930
Fax: (702) 940-6931

Prepared By:

GCW, Inc.
1555 S. Rainbow Blvd.
Las Vegas, Nevada 89146
Phone: (702) 804-2000
Fax: (702) 804-2299

840-050

January 8, 2018

Albert Sung, PE
City of Las Vegas – Department of Public Works
333 N. Rancho Drive – 7th Floor
Las Vegas, NV 89106

**Re: 2nd Response to City of Las Vegas Comments on the
Technical Drainage Study for "The 435" (DS4787)**

Dear Mr. Sung:

This letter addresses City of Las Vegas (CLV) second review comments dated November 9, 2017, regarding the project in its entirety. The CLV comment letter has been included in Appendix A for reference. Below are individual responses to each comment included in the review letter.

Comment: "1. This site development is located within a FEMA SPECIAL FLOOD HAZARD AREA, Zone A. **No permits will be issued until a Conditional Letter of Map Revision (CLOMR/CLOMR-F) is received from FEMA. Permits may be issued upon the receipt of Conditional Letter of Map Revision (CLOMR or CLOMR-F) from FEMA.**"

Response: The requirement for FEMA coordination to receive permits is acknowledged.

Comment: "2. A Letter of Map Revision (LOMR/LOMR-F) must be obtained from FEMA after the completion of any project within a FEMA Special Flood Hazard Area, Flood Zone "A". The bonded improvements shall include a line item of **\$50,000.00** for the LOMR. The bonded improvements will not be released until the LOMR/LOMR-F is obtained from FEMA and filed with the City of Las Vegas."

Response: The requirement for an additional bond with regards to LOMR approval is acknowledged.

Comment: "3. Sites with a grade difference of 2 feet above or below existing are required to have approval from the *City Planning and Development Department*. The engineer must submit copies of the grading plans and detail sheet with a letter justifying the grade difference to the *City Planning Department* (229-6301). The submitted letter did not include the Planning Department approval. The engineer must provide Planning approval with the next submittal."

Response: Planning approval has been provided in Appendix D.

1555 South Rainbow Boulevard
Las Vegas, Nevada 89146



O 702.804.2000
F 702.804.2299



info@gcwengineering.com
gcwengineering.com

Comment: "4. The site is located within the Flood Zone A and is adjacent to an existing or proposed *Clark County Regional Flood Control District (CCRFCD)* master planned facility. Therefore, CCRFCD concurrence is required prior to final approval of the drainage study."

Response: The requirement of CCRFCD concurrence prior to final approval is acknowledged.

Comment: "5. Please obtain necessary 404 permits from US Army Corps of Engineers and provide a copy of the permit to City of Las Vegas Flood Control Section prior to issuance of the grading permit. Contact the St. George Field Office of the US Army Corps of Engineers for permit information."

Response: It is acknowledged that necessary 404 permits are required prior to issuance of the grading permit.

Comment: "6. The provided WSPG model shall be extended further downstream incorporating the FEMA approved analysis for the Village at Queensridge LOMR with your update and slightly higher flow rates. Revise the WSPG Exhibit to include extending the WSPG Stations shown on the plan to the downstream limits shown with the previous LOMR."

Response: The WSPG model and Figure 8R have been extended downstream and are included in the appendix. Note that per Response to Comment No. 7, only one WSPG model has been included that uses the most conservative n-values and extends through the Queensridge LOMR. Pertinent reference material from the Queensridge LOMR has been included in Appendix E. Figure 8R has been updated through Queensridge and shows that criteria is met in the summary table.

Comment: "7. The provided WSPG analysis used a *n-values* of 0.013 and 0.015. Provide an additional WSPG analysis of the two main line RCB's using an appropriate n-values to reflect the rougher, tined bottom surface within the boxes in order to analyze the effects it will have on the HGLs and freeboard requirements. Any velocities above 35 feet per second with proposed mitigation measures may require additional mitigation measures to reduce the velocities and are subject to further comment by the City as well as CCRFCD review and acceptance. Provide a summary table showing the different n-values used and the resulting velocities, HGLs and minimum freeboard elevations. Revise the plans to reflect the HGLs during the worst case scenario and provide supporting freeboard calculations."

Response: A WSPG analysis for Mainline 1 and Mainline 2 using n-values of 0.015 for sections of the RCB with 1-inch of sacrificial concrete and n-values of 0.020 for

sections of the RCB with 3-inches of sacrificial concrete and tined groove bottoms have been included in the appendix. The 0.020 coefficient was taken from the CCRFCD Manual since the 3-inch sacrificial concrete and tined grooves are representative of an unfinished surface. A summary table located on Figure 8R showing n-values, velocities, HGLs, FG elevations, and a HGL criteria check has been included in the appendix. The plans have been revised to reflect the worst case scenario HGLs. Note that locations of 1-inch and 3-inch sacrificial concrete have been revised based on the new models velocities. The velocities of the Mainline 1 and Mainline 2 models exceed 35 ft/s in 2 places. The first place is for approximately 20-feet between WSPG station 7710 and 7691 within the open box section in the Mainline 1 model. The second place is for less than 40-feet between WSPG stations 2775 and 2738 in the Mainline 2 model and at station 7536 in the Mainline 1 model. Both of these locations are located just upstream of the open box junction. Since the stretches where the model exceeds 35 ft/s are brief, only slightly exceed it by 3 ft/s in the worst location, and all the places where it exceeds 35 ft/s are located within sections that will have 3-inches of sacrificial concrete the design is considered adequate.

Comment: "8. Provide a HEC-RAS analysis that incorporates the interim channel and entry structure flows. Extend the analysis sufficiently upstream to model the existing natural channel sections. Extend the analysis sufficiently downstream to model the concrete channel structure and extend the channel into the RCB area to normalize the flows to match the WSPG analysis. The combined HEC-RAS & WSPG analysis needs to verify that the interim entry structure has adequate freeboard. Include an Exhibit showing new cross sections that incorporate the detailed grading plans for the inlet structures within the HEC-RAS analysis."

Response: A HEC-RAS analysis incorporating the interim channel, entry structure, and RCB along with Figure 14 showing the cross sections have been included in the appendix. A HEC-RAS summary table showing required freeboard has also been provided on Figure 14. Note that the water surface elevations in the HEC-RAS and WSPG model are approximately 0.96-feet different at HEC-RAS station 800 due to differences in methodology between the two programs. Since the flow is near the top of box and WSPG can accurately model pressurized flow, the HGL from the WSPG model has been chosen for design purposes. Note that in the HEC-RAS model flow still remains around the top of box with adequate cover to meet HGL criteria.

Note that the open channel entry structure has been revised to allow for flow to better transition into the RCB, by elongating the open portion and modifying the walls to gradually contain the flow. An embankment with access to the top has been proposed to direct the water into the entry structure. A Blow-up detail on how to construct the embankment has been included on the improvement plans with this submittal. Riprap has been proposed throughout the entry structure and

grading up to minimum the water surface elevation that has been determined by the HEC-RAS model. Access to the open channel portion of the improvements remains drive-able through the RCB.

Figure 8R shows WSPG data for the RCB storm drain and the new Figure 14 shows the hydraulics and the proposed flood zone delineation at the entry structure; therefore, for consolidation purposes, Figure 11R has not been re-included with this submittal.

Comment: "9. Provide complete *Plans and Project Specifications* for approval by the *City of Las Vegas*. The Structural Plans and Details shall be a part of the Civil Improvement Plan set. This project is considered as a *Capital Improvement Project (CIP)* with developer funding."

Response: Complete Plans and Project Specifications will be provided to the City of Las Vegas for approval after the approval of the technical drainage study. It is acknowledged that the structural plans and details will be part of the Civil Improvement Plan set and that the project is considered a CIP project.

Comment: "10. Structural plans for the proposed storm drain improvements and pertinent flood control facilities must be submitted for review. Provide a soils report, structural calculations and specifications, two wet stamped structural sets, and a grading plan to the *Building Department* for processing. The engineer must provide a copy of *Building Department* approval of the structures to Regional Flood prior to their concurrence and to *Flood Control* prior to final acceptance of the drainage study."

Response: Structural plans for the proposed storm drain improvements and pertinent flood control facilities will be submitted for review after the approval of the technical drainage study. A soils report, structural calculations and specifications, two wet stamped structural sets, and a grading plan will be provided to the *Building Department* for processing. It is acknowledged that Building Department approval must be provided to Regional Flood for concurrence and to Flood Control prior to final acceptance.

Comment: "11. All proposed improvements associated with the Storm Drain facilities shall be bonded and inspected. This project shall require Special Inspection. Coordinate the requirements of and the Agreements needed for Special Inspection with the Building Department."

Response: It is acknowledged that the storm drain facilities must be bonded and inspected and that the project will require special inspection. The requirements and agreements needed for special inspection will be coordinated with the building department.

- Comment:** "12. The proposed improvements show drainage facilities of a size that must be reviewed for access and maintenance concerns. The engineer must submit an extra set of improvement plans to the *City Streets & Sanitation Department* for their review and comments. *Streets & Sanitation Department's* approval must be secured prior to the conditional drainage study approval."
- Response:** Improvement plans were submitted to the City Streets and Sanitation Department for review and comments on November 20, 2017. Due to the changes with the entry structure, an updated copy of the improvement plans will be forwarded with this drainage study submittal for Maintenance review.
- Comment:** "13. Provide plans and sections of the proposed interim open channel section. Include fall protection, access ladders, and a conceptual section to make this channel a future Box Structure."
- Response:** Fall protection and access ladders have been added to the pertinent detail in the improvement plans. Locations of post and cable have been properly shown where applicable. Note that structural design will be provided with the improvement plans that shows the design of the open channel, including how the channel can be constructed as a RCB at a later date.
- Comment:** "14. The provided access roads shall be included within easements dedicated to the City and clearly labeled on the plans. Provide details and show any access gates (16-foot minimum gate width) as necessary to accommodate the 12-foot wide access roads."
- Response:** Easements dedicated to the City have been provided for all access roads and are labeled on the plans.
- Comment:** "15. Revise the access road detail to provide a minimum of 6" Type II. Show turnaround areas for dead end segments. In addition, provide an access road to the interim channel area to the west."
- Response:** The access road detail has been revised to show a minimum of 6" Type II. Turn around areas for dead end segments are now shown on plans.
- Comment:** "16. Storm Drain Construction Note 1 does not match Construction Note 4. Revise accordingly."
- Response:** Construction notes have been reviewed and cross-checked for accuracy.
- Comment:** "17. Construction Note 10 indicates a 2:1 maximum slope but a 1:1 slope is shown on the plans. Revise accordingly."

- Response:** The plans have been revised to show the maximum engineered slope as 2:1. Note that along the northern boundary of the site, retaining walls are now proposed to assist in making up the grade difference.
- Comment:** "18. Provide a list of estimated quantities on the plans for both public and private drainage facilities."
- Response:** A list of estimated quantities for public and private drainage facilities has been added to sheet C1.02
- Comment:** "19. Revise Drainage Construction Notes 1 and 2 to match the dimensions of additional concrete clearance indicated in Details 1 and 2 on Sheet C8.02."
- Response:** Notes 1 and 2 indicate the 1" and 3" clearance needed in addition to the 2" clearance required from the rebar as shown in the included NDOT RCB culvert standard drawing. Detail 1 and 2 on Sheet C8.02 show the total clearance from the rebar needed taking into consideration the 2" clearance and the additional either 1" or 3" clearance.
- Comment:** "20. Provide new public drainage easements for the area of the site impacted by the proposed MPU facility improvements. The easement shall note that the public drainage improvements (MPU facilities) are publicly maintained and all onsite storm drain and surface improvements are privately maintained and the easement must be dedicated and recorded by separate document prior to the final acceptance of the improvement plans. Provide legal description and an exhibit of the drainage easement to Flood Control and *Mary Wulff* (702-229-2139) of *City of Las Vegas Right of Way Section* for the recordation process after the subject drainage study is conceptually approved. The existing drainage easements shall be vacated by separate action and the recording of the new easements shall be done consecutively."
- Response:** New public drainage easements with the note that the MPU facilities are publically maintained and onsite storm drain and surface improvements are privately maintained have been provided. It is acknowledged that the easement must be dedicated and recorded prior to final acceptance of the improvement plans. A legal description and exhibit will be provided to Flood Control and Mary Wulff for the recordation process after conceptual approval. It is acknowledged that the existing drainage easements shall be vacated by separate action and the recording of new easement will be done consecutively.
- Comment:** "21. Provide a detail of the proposed riprap areas that include the Type II and geotextile fabric in the detail section. Revise all pertinent plans and callouts accordingly."

Response: Further detail regarding the installation of riprap including callout for the bedding under the riprap has been added to the applicable details on the plans.

Comment: "22. Detail 9 on Sheet C8.01 shows a 2.0% slope while the plans and FlowMaster model reflect a 1.0% slope. Revise detail to match plan and hydraulic model. In addition, add dimensions, show rip rap, rip rap size and construction on Detail 9."

Response: The slope shown on the detail has been corrected to 1.0%. Dimensions, riprap, and riprap size have been added..

Comment: "23. Provide a cross sectional detail of the rip rap channel just upstream of the weir to show the construction of the rip rap and provide detailed grading plans of the interim improvements that include sufficient spot grades to indicate extents of the rip rap."

Response: Further detail regarding the grading and the installation of the interim open channel entry structure has been included on the plans.

Comment: "24. Indicate the minimum Finished Floor Elevations on the plans of the rough graded pads adjacent to the storm drain facilities."

Response: Minimum finished floor elevations of the rough graded pads adjacent to storm drain facilities have been added to the plans

Comment: "25. Technical drainage studies are required for each of the future development super pads. The technical drainage studies for the developments may not be submitted until the conditional approval of this pertinent infrastructure drainage study is obtained. Final approval for the infrastructure study must be obtained prior to conditional approval of the impacted development super pad drainage studies."

Response: It is acknowledged that technical drainage studies are needed for future development of the super pads. It is also noted that conditional approval of this study is required before the submittal of the technical drainage studies for the future developments and that final approval of this study is required prior to conditional approval of the future development studies.

Comment: "26. Complete the Construction Notes on the Grading Plan including pavement section and reference details for the call-outs of proposed improvements, i.e. RCB's, rip-rap, structure details, manholes, inlets, etc."

Response: Construction notes on the grading plan have been completed.

Comment: "27. This project currently has no Proposed Buildings or Structures. Should the project propose changes to this design assumption, then the Engineer

is to update the drainage study detailing the flood zone impacts and provide addresses for each building in a FEMA Flood Hazard Zone prior to obtaining a grading permit. This information is necessary to insure that the elevation certificates are provided for each address prior to completion of construction. This information is required until such time as a LOMR is approved that removes the development from the SFHA."

Response: Comment acknowledged.

The following comments are deferred to future technical drainage studies and no response to comment has been completed as a part of this submittal.

Comment: "28. Proposed storm drain laterals have been identified to collect flows from Peccole West Lot 9 and Queensridge Fairway Homes. Extend the storm drain system to collect the 100-year flows from these adjacent subdivisions."

Comment: "29. Continue to coordinate the MPU facility changes that are proposed with this development."

Comment: "30. Storm drain facilities are located on cut/fill slopes. Revise the slopes and/or the storm drain alignment to maintain 12-foot access roads. Provide a cross section detail of the maintenance access."


Comment: "31. Provide a concrete pad and maintenance access to the inlet structures for the local storm drains. Show the needed drainage easements for these facilities."

Comment: "32. The existing and proposed utility crossings of the storm drain must be shown on the storm drain plan and profiles sheets and on the lateral profiles. Indicate the type of pipe material for water and sewer lines. Review separation requirements between utilities and show all of the utility crossings of the storm drains."

If you have any questions or require additional information, please do not hesitate to contact me at 804-2130.

Respectfully,

GCW, INC.



Nelson Baggs, E.I.
Flood Control Division

Enclosures

c: Tom Dyson, GCW
James Duddleston, GCW

**THE 435 – 2nd CLV Response to Comments
APPENDIX LAYOUT**

Appendix A. City of Las Vegas Comments

1. November 9, 2017 CLV Comments

Appendix B. Hydraulic Calculations

1. Extended WSPG Model
2. HEC-RAS Model

Appendix C. Drainage Exhibits

1. Figure 8R - WSPG Exhibit
2. Figure 14 - HEC-RAS Exhibit

Appendix D. Additional Documents and Reference Material

1. Planning Approval (grade difference)
2. Table 702 – Manning's Roughness Coefficients
3. NDOT RCB Culvert Standard Drawing
4. Queensridge Culvert Reference Material

Appendix E. Improvement Plans (Folded Separately)

APPENDIX A

City of Las Vegas Comments

CITY OF LAS VEGAS		DATE:
INTER-OFFICE MEMORANDUM		November 9, 2017
TO: Land Development Services Department of Building & Safety		FROM: Albert Sung, P.E. Flood Control Project Engineer Department of Public Works 
SUBJECT:	COPIES TO:	
Drainage Study for:	GCW Engineers	
The 435 formerly The SEVENTY	Seventy Acres LLC	
Cross Streets:	SWC of Rampart & Alta	
File Number:	F:\Depot\DSMemos\DS4787B.ZNA.doc	
Parcel Number:	138-32-301-005, 006, 210-008	
Zoning Action:	SDR-62393; GPA-62387; ZON-62392	
FEMA Flood Zone	YES ☒	NO ☐
Proposed Storm Drain	YES ☒	NO ☐
		CCRFC

HISTORY	DATE RECEIVED	DATE REVIEWED	COMMENTS	REVIEW FEES	FEES PAID Payment Trn #
1 st Submittal	3/3/2016 & 3/9/2016	3/23/2016	See Comments Below	\$400.00	425231: \$400
2 nd Submittal	9/18/17	11/9/2017	See Comments Below	\$400.00	490193: \$400
TOTAL FEES (LDDRS):				\$800.00	----

REMARKS: This site development is within a FEMA SPECIAL FLOOD HAZARD AREA, Zone A. No permits of any kind will be issued for this project until a Conditional Letter of Map Revision (CLOMR/CLOMR-F) is received from FEMA.

The Drainage Study for the subject project has been reviewed and:

	is approved subject to conformance to all City standards and the following conditions:
X	must be resubmitted or supplemented including the following:
	is conditionally approved subject to Clark County Regional Flood Control District concurrence.
	is conditionally approved subject to NDOT concurrence.

1. This site development is located within a FEMA SPECIAL FLOOD HAZARD AREA, Zone A. **No permits will be issued until a Conditional Letter of Map Revision (CLOMR/CLOMR-F) is received from FEMA.** Permits may be issued upon the receipt of Conditional Letter of Map Revision (CLOMR or CLOMR-F) from FEMA.
2. A Letter of Map Revision (LOMR/LOMR-F) must be obtained from FEMA after the completion of any project within a FEMA Special Flood Hazard Area, Flood Zone "A". The bonded improvements shall include a line item of **\$50,000.00** for the LOMR. The bonded improvements will not be released until the LOMR/LOMR-F is obtained from FEMA and filed with the City of Las Vegas.

3. Sites with a grade difference of 2 feet above or below existing are required to have approval from the *City Planning and Development Department*. The engineer must submit copies of the grading plans and detail sheet with a letter justifying the grade difference to the *City Planning Department* (229-6301). The submitted letter did not include the Planning Department approval. The engineer must provide Planning approval with the next submittal.
4. The site is located within the Flood Zone A and is adjacent to an existing or proposed *Clark County Regional Flood Control District* (CCRFCD) master planned facility. Therefore, CCRFCD concurrence is required prior to final approval of the drainage study.
5. Please obtain necessary 404 permits from US Army Corps of Engineers and provide a copy of the permit to City of Las Vegas Flood Control Section prior to issuance of the grading permit. Contact the St. George Field Office of the US Army Corps of Engineers for permit information.
6. The provided WSPG model shall be extended further downstream incorporating the FEMA approved analysis for the Village at Queensridge LOMR with your update and slightly higher flow rates. Revise the WSPG Exhibit to include extending the WSPG Stations shown on the plan to the downstream limits shown with the previous LOMR.
7. The provided WSPG analysis used a *n-values* of 0.013 and 0.015. Provide an additional WSPG analysis of the two main line RCB's using an appropriate *n-values* to reflect the rougher, tined bottom surface within the boxes in order to analyze the effects it will have on the HGLs and freeboard requirements. Any velocities above 35 feet per second with proposed mitigation measures may require additional mitigation measures to reduce the velocities and are subject to further comment by the City as well as CCRFCD review and acceptance. Provide a summary table showing the different *n-values* used and the resulting velocities, HGLs and minimum freeboard elevations. Revise the plans to reflect the HGLs during the worst case scenario and provide supporting freeboard calculations.
8. Provide a HEC-RAS analysis that incorporates the interim channel and entry structure flows. Extend the analysis sufficiently upstream to model the existing natural channel sections. Extend the analysis sufficiently downstream to model the concrete channel structure and extend the channel into the RCB area to normalize the flows to match the WSPG analysis. The combined HEC-RAS & WSPG analysis needs to verify that the interim entry structure has adequate freeboard. Include an Exhibit showing new cross sections that incorporate the detailed grading plans for the inlet structures within the HEC-RAS analysis.
9. Provide complete *Plans and Project Specifications* for approval by the *City of Las Vegas*. The Structural Plans and Details shall be a part of the Civil Improvement Plan set. This project is considered as a *Capital Improvement Project* (CIP) with developer funding.
10. Structural plans for the proposed storm drain improvements and pertinent flood control facilities must be submitted for review. Provide a soils report, structural calculations and specifications, two wet stamped structural sets, and a grading plan to the *Building Department* for processing. The engineer must provide a copy of *Building Department* approval of the structures to Regional Flood prior to their concurrence and to *Flood Control* prior to final acceptance of the drainage study.
11. All proposed improvements associated with the Storm Drain facilities shall be bonded and inspected. This project shall require Special Inspection. Coordinate the requirements of and the Agreements needed for Special Inspection with the Building Department.
12. The proposed improvements show drainage facilities of a size that must be reviewed for access and maintenance concerns. The engineer must submit an extra set of improvement plans to the *City Streets & Sanitation Department* for their review and comments. *Streets & Sanitation Department's* approval must be secured prior to the conditional drainage study approval.

13. Provide plans and sections of the proposed interim open channel section. Include fall protection, access ladders, and a conceptual section to make this channel a future Box Structure.
14. The provided access roads shall be included within easements dedicated to the City and clearly labeled on the plans. Provide details and show any access gates (16-foot minimum gate width) as necessary to accommodate the 12-foot wide access roads.
15. Revise the access road detail to provide a minimum of 6" Type II. Show turnaround areas for dead end segments. In addition, provide an access road to the interim channel area to the west.
16. Storm Drain Construction Note 1 does not match Construction Note 4. Revise accordingly.
17. Construction Note 10 indicates a 2:1 maximum slope but a 1:1 slope is shown on the plans. Revise accordingly.
18. Provide a list of estimated quantities on the plans for both public and private drainage facilities.
19. Revise Drainage Construction Notes 1 and 2 to match the dimensions of additional concrete clearance indicated in Details 1 and 2 on Sheet C8.02.
20. Provide new public drainage easements for the area of the site impacted by the proposed MPU facility improvements. The easement shall note that the public drainage improvements (MPU facilities) are publicly maintained and all onsite storm drain and surface improvements are privately maintained and the easement must be dedicated and recorded by separate document prior to the final acceptance of the improvement plans. Provide legal description and an exhibit of the drainage easement to Flood Control and *Mary Wulff* (702-229-2139) of *City of Las Vegas Right of Way Section* for the recordation process after the subject drainage study is conceptually approved. The existing drainage easements shall be vacated by separate action and the recording of the new easements shall be done consecutively.
21. Provide a detail of the proposed riprap areas that include the Type II and geotextile fabric in the detail section. Revise all pertinent plans and callouts accordingly.
22. Detail 9 on Sheet C8.01 shows a 2.0% slope while the plans and FlowMaster model reflect a 1.0% slope. Revise detail to match plan and hydraulic model. In addition, add dimensions, show rip rap, rip rap size and construction on Detail 9.
23. Provide a cross sectional detail of the rip rap channel just upstream of the weir to show the construction of the rip rap and provide detailed grading plans of the interim improvements that include sufficient spot grades to indicate extents of the rip rap.
24. Indicate the minimum Finished Floor Elevations on the plans of the rough graded pads adjacent to the storm drain facilities.
25. Technical drainage studies are required for each of the future development super pads. The technical drainage studies for the developments may not be submitted until the conditional approval of this pertinent infrastructure drainage study is obtained. Final approval for the infrastructure study must be obtained prior to conditional approval of the impacted development super pad drainage studies.
26. Complete the Construction Notes on the Grading Plan including pavement section and reference details for the call-outs of proposed improvements, i.e. RCB's, rip-rap, structure details, manholes, inlets, etc.

27. This project currently has no Proposed Buildings or Structures. Should the project propose changes to this design assumption, then the Engineer is to update the drainage study detailing the flood zone impacts and provide addresses for each building in a FEMA Flood Hazard Zone prior to obtaining a grading permit. This information is necessary to insure that the elevation certificates are provided for each address prior to completion of construction. This information is required until such time as a LOMR is approved that removes the development from the SFHA.

Flood Control understands that this overall project will be developed in Phases. The following comments are repeated to reflect items that shall be addressed in future study updates as the Phases develop.

28. Proposed storm drain laterals have been identified to collect flows from Peccole West Lot 9 and Queensridge Fairway Homes. Extend the storm drain system to collect the 100-year flows from these adjacent subdivisions.
29. Continue to coordinate the MPU facility changes that are proposed with this development.
30. Storm drain facilities are located on cut/fill slopes. Revise the slopes and/or the storm drain alignment to maintain 12-foot access roads. Provide a cross section detail of the maintenance access.
31. Provide a concrete pad and maintenance access to the inlet structures for the local storm drains. Show the needed drainage easements for these facilities.
32. The existing and proposed utility crossings of the storm drain must be shown on the storm drain plan and profiles sheets and on the lateral profiles. Indicate the type of pipe material for water and sewer lines. Review separation requirements between utilities and show all of the utility crossings of the storm drains.

NOTE: Please be advised that all land surface area disturbances over 1 acre or any area adjacent to a water way must submit to the *Nevada Division of Environmental Protection* a "Notice of Intent" to discharge that certifies a stormwater pollution prevention plan has been developed and is maintained on site; for inclusion in the Stormwater General Permit No. NVR100000. A phased construction unit in a contiguous subdivision is considered under construction until all stripped or disturbed surface areas have been covered by paving, building construction or planting. For more information, including forms and applications see <http://ndep.nv.gov/bwpc/storm01.htm> or call (775) 687-9429.

NOTE: The engineer must submit the drainage study to FEMA for a Conditional Letter of Map Revision (CLOMR). A favorable CLOMR must be obtained prior to the issuance of any permits. This site is located in a FEMA Zone A. Clark County Regional Flood Control District (CCRFGD) review and approval is required prior to recordation of final map or issuance of building/grading permits. The Engineer must send a copy of the report to the CCRFGD for review. The developer/engineer must also obtain a Letter of Map Revision (LOMR) using the approved drainage study as technical support to inform FEMA of the modifications within the flood zone. The approved LOMR must be submitted to the City of Las Vegas prior to the release of the bond. FEMA Elevation Certificates, showing as-built finish floor elevations, must be completed for each building in the FEMA A Zone. The certificate must be submitted to the City of Las Vegas Flood Control Section prior to scheduling a framing inspection.

END OF REMARKS
JKN/PBJ

T/R/S: T20S/R60E/12
AREA L-32

APPENDIX B

Hydraulic Calculations

T1 THE SEVENTY - THE 435 (PHASE 1), GCW JOB NO. 840-050 0

T2 2ND RESPONSE TO CLV COMMENTS

T3 MAIN1 FACILITY (CCRFCD 'APSO' MPU FACILITY)EXTENDED THROUGH QUEENSRIDGE LOMR

SO	-11897.2702621.300	14	.015		2623.822															
TS	-11872.4102621.650	15	.015				.000													
TS	-11862.4102621.810	10	.015				.000													
R	-11772.1002623.180	10	.015				.000													
R	-11769.7802623.000	10	.015				.000		.000	0										
R	-11699.1602625.000	10	.015				-40.463													
R	-11681.7502625.480	10	.015				.000													
R	-11596.4502627.860	10	.015				48.868													
R	-11452.9802631.860	10	.015				.000													
R	-10980.0902645.025	10	.015				13.909													
R	-10864.6802648.238	10	.015				-66.125													
R	-10746.4602651.530	10	.015				.000													
R	-10280.3202655.259	10	.015				.000		.000	0										
R	-10111.4602656.610	10	.015				90.000													
R	-9546.4602659.440	10	.015				.000		.000	0										
R	-9401.3002662.940	1	.015				.000		.000	0										
JX	-9391.3002663.130	1	6	.015	188.000		2663.420		-60.0		.000									
R	-9196.4602666.750	1	.015				.000		.000	0										
TS	-9166.4602668.540	2	.020				.000													
R	-9128.4302670.810	2	.020				.000		.000	0										
R	-9038.3502671.710	2	.015				34.408		.000	0										
R	-8662.5402675.470	2	.015				.000		.000	0										
R	-8553.1202676.560	2	.015				12.539		.000	0										
R	-8493.5002677.160	2	.015				.000		.000	0										
R	-8441.4702677.683	2	.015				-19.874		.000	0										
R	-7825.4502683.840	2	.015				.000		.000	0										
R	-7710.0002685.000	2	.020				-4.535		.000	0										
R	-7573.6402695.000	2	.020				-16.076		.000	0										
JX	-7536.9702697.680	4	3	.020	2008.000		2697.680		-15.0		.000									
R	-7441.1002704.768	4	.020				.000		.000	0										
R	-7361.1002710.680	4	.020				-17.196		.000	0										
R	-7235.1202715.420	4	.020				-12.318		.000	0										
R	-6922.5702727.190	4	.020				.000		.000	0										
R	-6751.4802729.550	4	.020				.000		.000	0										
JX	-6741.4802729.650	4	5	5.015	9.000		17.0002729.6502729.650		45.0-45.0		.000									
R	-6181.4602735.100	4	.015				.000		.000	0										
JX	-6171.4602735.200	4	6	6.015	51.000		28.0002735.1502735.150		45.0-45.0		.000									
R	-6138.2902735.531	4	.015				.000		.000	0										
R	-6058.1802735.820	4	.015				40.982		.000	0										
R	-5813.2102738.240	4	.015				.000		.000	0										
SH	-5813.2102738.240	4					.000													
CD	1 3 1	1.000	12.000	25.000	.000	.000	.00													
CD	2 3 0	.000	12.000	14.000	.000	.000	.00													
CD	3 3 0	.000	8.000	10.000	.000	.000	.00													
CD	4 3 0	.000	9.000	14.000	.000	.000	.00													
CD	5 4 1	.000	4.000	.000	.000	.000	.00													
CD	6 4 1	.000	6.000	.000	.000	.000	.00													
CD	10 3 1	1.000	12.000	25.000	.000	.000	.00													
CD	14 5 0	.000	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00
CD	15 5 0	.000	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00
PTS	14 8	.000	48.000	19.090	48.000	50.850	45.000111.110		21.000159.240		21.000									
PTS		159.240	21.000186.970	35.980248.780	40.000															
PTS	15 6	.000	49.000	11.030	48.000	54.930	38.000	84.460	22.000136.390		22.000									
PTS		173.210	40.000																	
Q		2384.000	.0																	

MAIN1_ExtendedModel.OUT
 FILE: MAIN1_ExtendedModel.WSW W S P G W - CIVILDESIGN Version 14.08 PAGE 1
 Program Package Serial Number: 3074
 WATER SURFACE PROFILE LISTING
 THE SEVENTY - THE 435 (PHASE 1), GCW JOB NO. 840-050 Date:12-18-2017 Time: 9:43:43
 2ND RESPONSE TO CLV COMMENTS
 MAIN1 FACILITY (CCRFGD 'APSO' MPU FACILITY)EXTENDED THROUGH QUEENSRIDG

Station	Invert Elev	Depth (FT)	Water Elev	Q (CFS)	Vel (FPS)	Vel Head	Energy Grd.El.	Super Elev	Critical Depth	Flow Top Width	Height/Dia.-FT	Base Wt/or I.D.	No Wth ZL	Prs/Pip
L/Elem	Ch Slope				SF Ave	HF	SE Dpth	Froude N	Norm Dp	"N"	X-Fall	ZR	Type Ch	
*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****
-11897.270	2621.300	2.589	2623.889	4685.00	33.65	17.58	2641.47	.00	6.04	59.42		14	0	.0
TRANS STR	.0141					.0409	1.02	2.59	3.87		.015			IR-OPEN
-11872.410	2621.650	2.388	2624.038	4685.00	34.68	18.67	2642.71	.00	5.85	61.22		15	0	.0
TRANS STR	.0160					.0337	.34	2.39	4.11		.015			IR-OPEN
-11862.410	2621.810	6.111	2627.921	4685.00	31.95	15.85	2643.77	.00	10.58	25.00	12.000	25.000	.00	1 1.0
90.311	.0152					.0248	2.24	6.11	2.32	7.24	.015	.00	.00	BOX
-11772.100	2623.180	5.915	2629.095	4685.00	33.00	16.91	2646.01	.00	10.58	25.00	12.000	25.000	.00	1 1.0
2.319	-.0776					.0262	.06	5.91	2.44	.00	.015	.00	.00	BOX
-11769.780	2623.000	5.864	2628.864	4685.00	33.29	17.21	2646.07	12.00	10.58	25.00	12.000	25.000	.00	1 1.0
70.620	.0283					.0263	1.86	12.00	2.47	5.72	.015	.00	.00	BOX
-11699.160	2625.000	5.893	2630.893	4685.00	33.12	17.04	2647.93	.00	10.58	25.00	12.000	25.000	.00	1 1.0
17.410	.0276					.0261	.45	5.89	2.45	5.78	.015	.00	.00	BOX
-11681.750	2625.480	5.899	2631.378	4685.00	33.09	17.01	2648.39	12.00	10.58	25.00	12.000	25.000	.00	1 1.0
85.300	.0279					.0259	2.21	12.00	2.45	5.75	.015	.00	.00	BOX
-11596.450	2627.860	5.935	2633.795	4685.00	32.89	16.80	2650.59	.00	10.58	25.00	12.000	25.000	.00	1 1.0
143.470	.0279					.0252	3.61	5.94	2.43	5.75	.015	.00	.00	BOX
-11452.980	2631.860	6.020	2637.880	4685.00	32.43	16.33	2654.21	.40	10.58	25.00	12.000	25.000	.00	1 1.0
204.530	.0278					.0237	4.84	6.42	2.38	5.76	.015	.00	.00	BOX

FILE: MAIN1_ExtendedModel.WSW W S P G W - CIVILDESIGN Version 14.08 PAGE 2
 Program Package Serial Number: 3074
 WATER SURFACE PROFILE LISTING
 THE SEVENTY - THE 435 (PHASE 1), GCW JOB NO. 840-050 Date:12-18-2017 Time: 9:43:43
 2ND RESPONSE TO CLV COMMENTS
 MAIN1 FACILITY (CCRFGD 'APSO' MPU FACILITY)EXTENDED THROUGH QUEENSRIDG

Station	Invert Elev	Depth (FT)	Water Elev	Q (CFS)	Vel (FPS)	Vel Head	Energy Grd.El.	Super Elev	Critical Depth	Flow Top Width	Height/Dia.-FT	Base Wt/or I.D.	No Wth ZL	Prs/Pip
L/Elem	Ch Slope				SF Ave	HF	SE Dpth	Froude N	Norm Dp	"N"	X-Fall	ZR	Type Ch	
*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****
-11248.450	2637.554	6.226	2643.780	4685.00	31.36	15.27	2659.05	.38	10.58	25.00	12.000	25.000	.00	1 1.0
164.674	.0278					.0213	3.50	6.60	2.26	5.76	.015	.00	.00	BOX
-11083.780	2642.138	6.530	2648.668	4685.00	29.90	13.88	2662.55	.34	10.58	25.00	12.000	25.000	.00	1 1.0
103.687	.0278					.0187	1.94	6.87	2.10	5.76	.015	.00	.00	BOX
-10980.090	2645.025	6.848	2651.873	4685.00	28.50	12.62	2664.49	12.00	10.58	25.00	12.000	25.000	.00	1 1.0
59.909	.0278					.0167	1.00	12.00	1.96	5.76	.015	.00	.00	BOX
-10920.180	2646.693	7.117	2653.810	4685.00	27.43	11.68	2665.49	12.00	10.58	25.00	12.000	25.000	.00	1 1.0
55.501	.0278					.0150	.83	12.00	1.85	5.76	.015	.00	.00	BOX
-10864.680	2648.238	7.464	2655.702	4685.00	26.15	10.62	2666.32	.00	10.58	25.00	12.000	25.000	.00	1 1.0
26.598	.0278					.0135	.36	7.46	1.72	5.76	.015	.00	.00	BOX
-10838.080	2648.979	7.685	2656.664	4685.00	25.40	10.02	2666.68	.00	10.58	25.00	12.000	25.000	.00	1 1.0
34.383	.0278					.0123	.42	7.68	1.65	5.76	.015	.00	.00	BOX
-10803.700	2649.936	8.060	2657.996	4685.00	24.22	9.11	2667.10	.00	10.58	25.00	12.000	25.000	.00	1 1.0
25.574	.0278					.0109	.28	8.06	1.53	5.76	.015	.00	.00	BOX

MAIN1_ExtendedModel.OUT

-10778.130	2650.648	8.453	2659.102	4685.00	23.09	8.28	2667.38	.00	10.58	25.00	12.000	25.000	.00	1	1.0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
18.651	.0278					.0096	.18	8.45	1.43	5.76	.015	.00	.00	BOX	
-10759.470	2651.168	8.866	2660.034	4685.00	22.02	7.53	2667.56	.00	10.58	25.00	12.000	25.000	.00	1	1.0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
13.014	.0278					.0085	.11	8.87	1.33	5.76	.015	.00	.00	BOX	

FILE: MAIN1_ExtendedModel.WSW W S P G W - CIVILDESIGN Version 14.08
 Program Package Serial Number: 3074
 WATER SURFACE PROFILE LISTING
 THE SEVENTY - THE 435 (PHASE 1), GCW JOB NO. 840-050
 2ND RESPONSE TO CLV COMMENTS
 MAIN1 FACILITY (CCRFGD 'APSO' MPU FACILITY)EXTENDED THROUGH QUEENSRIDG
 Date:12-18-2017 Time: 9:43:43
 PAGE 3

Station	Invert Elev	Depth (FT)	Water Elev	Q (CFS)	Vel (FPS)	Vel Head	Energy Grd.El.	Super Elev	Critical Depth	Flow Top Width	Height/Dia.-FT	Base Wt or I.D.	ZL	No Wth Prs/Pip
L/Elem	Ch Slope				SF Ave	HF	SE Dpth	Froude N	Norm Dp	"N"	X-Fall	ZR	Type Ch	
-10746.460	2651.530	9.299	2660.829	4685.00	20.99	6.84	2667.67	.00	10.58	25.00	12.000	25.000	.00	1 1.0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
17.447	.0080					.0080	.14	9.30	1.24	9.30	.015	.00	.00	BOX
-10729.010	2651.670	9.299	2660.968	4685.00	20.99	6.84	2667.81	.00	10.58	25.00	12.000	25.000	.00	1 1.0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
448.692	.0080					.0081	3.64	9.30	1.24	9.30	.015	.00	.00	BOX
-10280.320	2655.259	9.193	2664.452	4685.00	21.24	7.00	2671.45	12.00	10.58	25.00	12.000	25.000	.00	1 1.0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
168.860	.0080					.0084	1.41	12.00	1.26	9.30	.015	.00	.00	BOX
-10111.460	2656.610	9.082	2665.692	4685.00	21.49	7.17	2672.87	.00	10.58	25.00	12.000	25.000	.00	1 1.0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
64.780	.0050					.0090	.58	9.08	1.28	11.22	.015	.00	.00	BOX
-10046.680	2656.935	8.706	2665.641	4685.00	22.42	7.81	2673.45	.00	10.58	25.00	12.000	25.000	.00	1 1.0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
74.290	.0050					.0101	.75	8.71	1.37	11.22	.015	.00	.00	BOX
-9972.390	2657.307	8.301	2665.608	4685.00	23.52	8.59	2674.19	.00	10.58	25.00	12.000	25.000	.00	1 1.0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
74.278	.0050					.0114	.84	8.30	1.47	11.22	.015	.00	.00	BOX
-9898.111	2657.679	7.915	2665.593	4685.00	24.66	9.45	2675.04	.00	10.58	25.00	12.000	25.000	.00	1 1.0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
73.460	.0050					.0129	.94	7.91	1.58	11.22	.015	.00	.00	BOX
-9824.651	2658.047	7.546	2665.593	4685.00	25.87	10.39	2675.98	.00	10.58	25.00	12.000	25.000	.00	1 1.0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
72.150	.0050					.0145	1.05	7.55	1.69	11.22	.015	.00	.00	BOX
-9752.501	2658.408	7.195	2665.603	4685.00	27.13	11.43	2677.03	.00	10.58	25.00	12.000	25.000	.00	1 1.0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
70.532	.0050					.0165	1.16	7.20	1.82	11.22	.015	.00	.00	BOX

FILE: MAIN1_ExtendedModel.WSW W S P G W - CIVILDESIGN Version 14.08
 Program Package Serial Number: 3074
 WATER SURFACE PROFILE LISTING
 THE SEVENTY - THE 435 (PHASE 1), GCW JOB NO. 840-050
 2ND RESPONSE TO CLV COMMENTS
 MAIN1 FACILITY (CCRFGD 'APSO' MPU FACILITY)EXTENDED THROUGH QUEENSRIDG
 Date:12-18-2017 Time: 9:43:43
 PAGE 4

Station	Invert Elev	Depth (FT)	Water Elev	Q (CFS)	Vel (FPS)	Vel Head	Energy Grd.El.	Super Elev	Critical Depth	Flow Top Width	Height/Dia.-FT	Base Wt or I.D.	ZL	No Wth Prs/Pip
L/Elem	Ch Slope				SF Ave	HF	SE Dpth	Froude N	Norm Dp	"N"	X-Fall	ZR	Type Ch	
-9681.969	2658.761	6.860	2665.622	4685.00	28.45	12.57	2678.19	.00	10.58	25.00	12.000	25.000	.00	1 1.0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
68.721	.0050					.0187	1.28	6.86	1.95	11.22	.015	.00	.00	BOX
-9613.248	2659.105	6.541	2665.646	4685.00	29.84	13.83	2679.48	.00	10.58	25.00	12.000	25.000	.00	1 1.0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
66.788	.0050					.0212	1.41	6.54	2.10	11.22	.015	.00	.00	BOX
-9546.460	2659.440	6.237	2665.677	4685.00	31.30	15.21	2680.89	.00	10.58	25.00	12.000	25.000	.00	1 1.0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
145.160	.0241					.0221	3.21	6.24	2.25	6.08	.015	.00	.00	BOX
-9401.300	2662.940	6.312	2669.252	4685.00	30.93	14.85	2684.10	.00	10.58	25.00	12.000	25.000	.00	1 1.0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
JUNCT STR	.0190					.0239	.24	6.31	2.21		.015	.00	.00	BOX
-9391.300	2663.130	5.724	2668.854	4497.00	32.74	16.64	2685.49	.00	10.29	25.00	12.000	25.000	.00	1 1.0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
55.894	.0186					.0266	1.49	5.72	2.46	6.50	.015	.00	.00	BOX
-9335.406	2664.168	5.633	2669.802	4497.00	33.26	17.18	2686.98	.00	10.29	25.00	12.000	25.000	.00	1 1.0

MAIN1_ExtendedModel.OUT
138.946 .0186 .0291 4.04 5.63 2.52 6.50 .015 .00 .00 BOX
-9196.460 2666.750 5.371 2672.121 4497.00 34.89 18.90 2691.02 .00 10.29 25.00 12.000 25.000 .00 1 1.0
TRANS STR .0597 .0395 1.18 5.37 2.71 .020 .00 .00 BOX
-9166.459 2668.540 10.672 2679.212 4497.00 30.10 14.07 2693.28 .00 12.00 14.00 12.000 14.000 .00 0 .0
3.481 .0597 .0238 .08 10.67 1.62 7.50 .020 .00 .00 BOX
-9162.978 2668.748 10.750 2679.498 4497.00 29.88 13.86 2693.36 .00 12.00 14.00 12.000 14.000 .00 0 .0
19.645 .0597 .0222 .44 10.75 1.61 7.50 .020 .00 .00 BOX
FILE: MAIN1_ExtendedModel.WSW W S P G W - CIVILDESIGN Version 14.08 PAGE 5
Program Package Serial Number: 3074

WATER SURFACE PROFILE LISTING Date:12-18-2017 Time: 9:43:43
THE SEVENTY - THE 435 (PHASE 1), GCW JOB NO. 840-050
2ND RESPONSE TO CLV COMMENTS
MAIN1 FACILITY (CCRCD 'APSO' MPU FACILITY)EXTENDED THROUGH QUEENSRIDGE

Station Invert Depth Water Q Vel Vel Energy Super Critical Flow Top Height Base Wt No Wth
Elev (FT) Elev (CFS) (FPS) Head Grd.El. Elev Depth Width Dia.-FT or I.D. ZL Prs/Pip
L/Elem Ch Slope SF Ave HF SE Dpth Froude N Norm Dp "N" X-Fall ZR Type Ch

-9143.333 2669.920 11.275 2681.195 4497.00 28.49 12.60 2693.80 .00 12.00 14.00 12.000 14.000 .00 0 .0
14.903 .0597 .0197 .29 11.27 1.50 7.50 .020 .00 .00 BOX
----- WARNING - Flow depth near top of box conduit -----
-9128.430 2670.810 11.825 2682.635 4497.00 27.16 11.46 2694.09 12.00 12.00 14.00 12.000 14.000 .00 0 .0
90.080 .0100 .0105 .94 12.00 1.39 12.00 .015 .00 .00 BOX
----- WARNING - Flow depth near top of box conduit -----
-9038.350 2671.710 11.777 2683.487 4497.00 27.27 11.55 2695.04 .00 12.00 14.00 12.000 14.000 .00 0 .0
375.810 .0100 .0109 4.11 11.78 1.40 12.00 .015 .00 .00 BOX
----- WARNING - Flow depth near top of box conduit -----
-8662.540 2675.470 11.443 2686.913 4497.00 28.07 12.24 2699.15 .34 12.00 14.00 12.000 14.000 .00 0 .0
109.420 .0100 .0115 1.26 11.79 1.46 12.00 .015 .00 .00 BOX
----- WARNING - Flow depth near top of box conduit -----
-8553.120 2676.560 11.298 2687.858 4497.00 28.43 12.55 2700.41 .00 12.00 14.00 12.000 14.000 .00 0 .0
59.620 .0101 .0118 .70 11.30 1.49 12.00 .015 .00 .00 BOX
----- WARNING - Flow depth near top of box conduit -----
FILE: MAIN1_ExtendedModel.WSW W S P G W - CIVILDESIGN Version 14.08 PAGE 6
Program Package Serial Number: 3074

WATER SURFACE PROFILE LISTING Date:12-18-2017 Time: 9:43:43
THE SEVENTY - THE 435 (PHASE 1), GCW JOB NO. 840-050
2ND RESPONSE TO CLV COMMENTS
MAIN1 FACILITY (CCRCD 'APSO' MPU FACILITY)EXTENDED THROUGH QUEENSRIDGE

Station Invert Depth Water Q Vel Vel Energy Super Critical Flow Top Height Base Wt No Wth
Elev (FT) Elev (CFS) (FPS) Head Grd.El. Elev Depth Width Dia.-FT or I.D. ZL Prs/Pip
L/Elem Ch Slope SF Ave HF SE Dpth Froude N Norm Dp "N" X-Fall ZR Type Ch

-8493.500 2677.160 11.214 2688.374 4497.00 28.64 12.74 2701.11 12.00 12.00 14.00 12.000 14.000 .00 0 .0
52.030 .0101 .0120 .63 12.00 1.51 12.00 .015 .00 .00 BOX
----- WARNING - Flow depth near top of box conduit -----
-8441.471 2677.683 11.135 2688.818 4497.00 28.85 12.92 2701.74 .00 12.00 14.00 12.000 14.000 .00 0 .0
233.027 .0100 .0128 2.98 11.13 1.52 12.00 .015 .00 .00 BOX
----- WARNING - Flow depth near top of box conduit -----
-8208.443 2680.012 10.691 2690.703 4497.00 30.05 14.02 2704.72 .00 12.00 14.00 12.000 14.000 .00 0 .0
209.615 .0100 .0143 3.00 10.69 1.62 12.00 .015 .00 .00 BOX
-7998.828 2682.107 10.193 2692.300 4497.00 31.51 15.42 2707.72 .00 12.00 14.00 12.000 14.000 .00 0 .0
173.378 .0100 .0162 2.80 10.19 1.74 12.00 .015 .00 .00 BOX
-7825.450 2683.840 9.719 2693.559 4497.00 33.05 16.96 2710.52 .16 12.00 14.00 12.000 14.000 .00 0 .0
6.403 .0100 .0307 .20 9.88 1.87 12.00 .020 .00 .00 BOX
-7819.047 2683.905 9.666 2693.571 4497.00 33.23 17.15 2710.72 .16 12.00 14.00 12.000 14.000 .00 0 .0
55.361 .0100 .0329 1.82 9.83 1.88 12.00 .020 .00 .00 BOX

WATER SURFACE PROFILE LISTING
 THE SEVENTY - THE 435 (PHASE 1), GCW JOB NO. 840-050
 2ND RESPONSE TO CLV COMMENTS
 MAIN1 FACILITY (CCRFGD 'APSO' MPU FACILITY)EXTENDED THROUGH QUEENSRIDG

Date:12-18-2017 Time: 9:43:43

Station	Invert Elev	Depth (FT)	Water Elev	Q (CFS)	Vel (FPS)	Vel Head	Energy Grd.El.	Super Elev	Critical Depth	Flow Top Width	Height/Dia.-FT	Base Wt or I.D.	ZL	No Wth Prs/Pip
L/Elem	Ch Slope				SF Ave	HF	SE Dpth	Froude N	Norm Dp	"N"	X-Fall	ZR	Type Ch	
-7763.686	2684.461	9.216	2693.677	4497.00	34.85	18.86	2712.54	.18	12.00	14.00	12.000	14.000	.00	0 .0
53.686	.0100					.0372	2.00	9.40	2.02	12.00	.020	.00	.00	BOX
-7710.000	2685.000	8.788	2693.788	4497.00	36.55	20.75	2714.54	1.20	12.00	14.00	12.000	14.000	.00	0 .0
18.829	.0733					.0384	.72	9.98	2.17	6.94	.020	.00	.00	BOX
-7691.171	2686.381	8.971	2695.352	4497.00	35.81	19.91	2715.26	1.15	12.00	14.00	12.000	14.000	.00	0 .0
36.032	.0733					.0353	1.27	10.12	2.11	6.94	.020	.00	.00	BOX
-7655.139	2689.023	9.409	2698.432	4497.00	34.14	18.10	2716.53	1.04	12.00	14.00	12.000	14.000	.00	0 .0
28.146	.0733					.0312	.88	10.45	1.96	6.94	.020	.00	.00	BOX
-7626.993	2691.087	9.868	2700.956	4497.00	32.55	16.45	2717.41	.95	12.00	14.00	12.000	14.000	.00	0 .0
22.183	.0733					.0276	.61	10.82	1.83	6.94	.020	.00	.00	BOX
-7604.810	2692.714	10.350	2703.064	4497.00	31.04	14.96	2718.02	.86	12.00	14.00	12.000	14.000	.00	0 .0
17.490	.0733					.0245	.43	11.21	1.70	6.94	.020	.00	.00	BOX
-7587.319	2693.997	10.855	2704.852	4497.00	29.59	13.60	2718.45	.78	12.00	14.00	12.000	14.000	.00	0 .0
13.679	.0733					.0217	.30	11.64	1.58	6.94	.020	.00	.00	BOX
----- WARNING - Flow depth near top of box conduit -----														
-7573.640	2695.000	11.385	2706.385	4497.00	28.21	12.36	2718.75	.00	12.00	14.00	12.000	14.000	.00	0 .0
JUNCT STR	.0731					.0380	1.39	11.38	1.47	.020	.00	.00	.00	BOX
----- WARNING - Flow depth near top of box conduit -----														

WATER SURFACE PROFILE LISTING
 THE SEVENTY - THE 435 (PHASE 1), GCW JOB NO. 840-050
 2ND RESPONSE TO CLV COMMENTS
 MAIN1 FACILITY (CCRFGD 'APSO' MPU FACILITY)EXTENDED THROUGH QUEENSRIDG

Date:12-18-2017 Time: 9:43:43

Station	Invert Elev	Depth (FT)	Water Elev	Q (CFS)	Vel (FPS)	Vel Head	Energy Grd.El.	Super Elev	Critical Depth	Flow Top Width	Height/Dia.-FT	Base Wt or I.D.	ZL	No Wth Prs/Pip
L/Elem	Ch Slope				SF Ave	HF	SE Dpth	Froude N	Norm Dp	"N"	X-Fall	ZR	Type Ch	
-7536.970	2697.680	4.981	2702.661	2489.00	35.69	19.78	2722.44	.00	9.00	14.00	9.000	14.000	.00	0 .0
36.618	.0739					.0539	1.97	4.98	2.82	4.50	.020	.00	.00	BOX
-7500.352	2700.387	5.090	2705.478	2489.00	34.93	18.94	2724.42	.00	9.00	14.00	9.000	14.000	.00	0 .0
59.252	.0739					.0491	2.91	5.09	2.73	4.50	.020	.00	.00	BOX
-7441.100	2704.768	5.339	2710.107	2489.00	33.30	17.22	2727.33	1.81	9.00	14.00	9.000	14.000	.00	0 .0
10.289	.0739					.0452	.47	7.15	2.54	4.50	.020	.00	.00	BOX
-7430.811	2705.528	5.393	2710.922	2489.00	32.96	16.87	2727.79	1.77	9.00	14.00	9.000	14.000	.00	0 .0
39.631	.0739					.0418	1.66	7.17	2.50	4.50	.020	.00	.00	BOX
-7391.180	2708.457	5.657	2714.114	2489.00	31.43	15.34	2729.45	1.61	9.00	14.00	9.000	14.000	.00	0 .0
30.080	.0739					.0367	1.10	7.27	2.33	4.50	.020	.00	.00	BOX
-7361.100	2710.680	5.933	2716.613	2489.00	29.97	13.94	2730.56	.67	9.00	14.00	9.000	14.000	.00	0 .0
125.980	.0376					.0331	4.17	6.60	2.17	5.74	.020	.00	.00	BOX
-7235.121	2715.420	6.094	2721.514	2489.00	29.18	13.22	2734.73	.00	9.00	14.00	9.000	14.000	.00	0 .0
53.761	.0377					.0312	1.68	6.09	2.08	5.74	.020	.00	.00	BOX
-7181.360	2717.444	6.201	2723.646	2489.00	28.67	12.76	2736.41	.00	9.00	14.00	9.000	14.000	.00	0 .0

MAIN1_ExtendedModel.OUT														
94.790	.0377			.0286	2.71	6.20	2.03	5.74	.020	.00	.00	BOX	9	
FILE: MAIN1_ExtendedModel.WSW W S P G W - CIVILDESIGN Version 14.08														
Program Package Serial Number: 3074														
WATER SURFACE PROFILE LISTING														
Date:12-18-2017 Time: 9:43:43														
THE SEVENTY - THE 435 (PHASE 1), GCW JOB NO. 840-050														
2ND RESPONSE TO CLV COMMENTS														
MAIN1 FACILITY (CCRFGD 'APSO' MPU FACILITY)EXTENDED THROUGH QUEENSRIDG														

Station	Invert Elev	Depth (FT)	Water Elev	Q (CFS)	Vel (FPS)	Vel Head	Energy Grd.El.	Super Elev	Critical Depth	Flow Top Width	Height/Dia.-FT	Base Wt or I.D.	No Wth ZL	Prs/Pip
L/Elem	Ch Slope					SF Ave	HF	SE Dpth	Froude N	Norm Dp	"N"	X-Fall	ZR	Type Ch

-7086.570	2721.014	6.504	2727.518	2489.00	27.33	11.60	2739.12	.00	9.00	14.00	9.000	14.000	.00	0 .0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
59.026	.0377					.0252	1.49	6.50	1.89	5.74	.020	.00	.00	BOX
-7027.544	2723.237	6.821	2730.058	2489.00	26.06	10.55	2740.61	.00	9.00	14.00	9.000	14.000	.00	0 .0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
40.372	.0377					.0222	.89	6.82	1.76	5.74	.020	.00	.00	BOX
-6987.173	2724.757	7.154	2731.911	2489.00	24.85	9.59	2741.50	.00	9.00	14.00	9.000	14.000	.00	0 .0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
28.802	.0377					.0195	.56	7.15	1.64	5.74	.020	.00	.00	BOX
-6958.371	2725.842	7.504	2733.345	2489.00	23.69	8.72	2742.06	.00	9.00	14.00	9.000	14.000	.00	0 .0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
20.840	.0377					.0172	.36	7.50	1.52	5.74	.020	.00	.00	BOX
-6937.531	2726.626	7.870	2734.496	2489.00	22.59	7.92	2742.42	.00	9.00	14.00	9.000	14.000	.00	0 .0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
14.961	.0377					.0152	.23	7.87	1.42	5.74	.020	.00	.00	BOX
-6922.570	2727.190	8.254	2735.444	2489.00	21.54	7.20	2742.65	.00	9.00	14.00	9.000	14.000	.00	0 .0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
171.090	.0138					.0147	2.51	8.25	1.32	8.35	.020	.00	.00	BOX
----- WARNING - Flow depth near top of box conduit -----														
-6751.480	2729.550	8.068	2737.618	2489.00	22.04	7.54	2745.16	.00	9.00	14.00	9.000	14.000	.00	0 .0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
JUNCT STR	.0100					.0089	.09	8.07	1.37		.015	.00	.00	BOX
-6741.480	2729.650	7.748	2737.397	2463.00	22.71	8.01	2745.40	.00	9.00	14.00	9.000	14.000	.00	0 .0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
98.917	.0097					.0092	.91	7.75	1.44	7.60	.015	.00	.00	BOX
FILE: MAIN1_ExtendedModel.WSW W S P G W - CIVILDESIGN Version 14.08														
Program Package Serial Number: 3074														
WATER SURFACE PROFILE LISTING														
Date:12-18-2017 Time: 9:43:43														
THE SEVENTY - THE 435 (PHASE 1), GCW JOB NO. 840-050														
2ND RESPONSE TO CLV COMMENTS														
MAIN1 FACILITY (CCRFGD 'APSO' MPU FACILITY)EXTENDED THROUGH QUEENSRIDG														

Station	Invert Elev	Depth (FT)	Water Elev	Q (CFS)	Vel (FPS)	Vel Head	Energy Grd.El.	Super Elev	Critical Depth	Flow Top Width	Height/Dia.-FT	Base Wt or I.D.	No Wth ZL	Prs/Pip
L/Elem	Ch Slope					SF Ave	HF	SE Dpth	Froude N	Norm Dp	"N"	X-Fall	ZR	Type Ch

-6642.563	2730.613	7.800	2738.413	2463.00	22.55	7.90	2746.31	.00	9.00	14.00	9.000	14.000	.00	0 .0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
287.478	.0097					.0086	2.46	7.80	1.42	7.60	.015	.00	.00	BOX
-6355.085	2733.410	8.181	2741.591	2463.00	21.50	7.18	2748.77	.00	9.00	14.00	9.000	14.000	.00	0 .0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
116.480	.0097					.0076	.88	8.18	1.32	7.60	.015	.00	.00	BOX
----- WARNING - Flow depth near top of box conduit -----														
-6238.604	2734.544	8.580	2743.124	2463.00	20.50	6.53	2749.65	.00	9.00	14.00	9.000	14.000	.00	0 .0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
57.145	.0097					.0067	.38	8.58	1.23	7.60	.015	.00	.00	BOX
----- WARNING - Flow depth near top of box conduit -----														
-6181.460	2735.100	9.000	2744.100	2463.00	19.55	5.93	2750.03	.00	9.00	14.00	9.000	14.000	.00	0 .0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
JUNCT STR	.0100					.0095	.10	9.00	1.15		.015	.00	.00	BOX
----- WARNING - Flow depth near top of box conduit -----														
-6171.460	2735.200	9.707	2744.907	2384.00	18.92	5.56	2750.47	.00	9.00	14.00	9.000	14.000	.00	0 .0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
33.170	.0100					.0095	.32	9.71	1.11	7.35	.015	.00	.00	BOX
-6138.290	2735.531	9.692	2745.223	2384.00	18.92	5.56	2750.78	.00	9.00	14.00	9.000	14.000	.00	0 .0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
80.110	.0036					.0095	.76	.00	1.11	9.00	.015	.00	.00	BOX
FILE: MAIN1_ExtendedModel.WSW W S P G W - CIVILDESIGN Version 14.08														
Program Package Serial Number: 3074														
WATER SURFACE PROFILE LISTING														
Date:12-18-2017 Time: 9:43:43														
THE SEVENTY - THE 435 (PHASE 1), GCW JOB NO. 840-050														

2ND RESPONSE TO CLV COMMENTS

MAIN1 FACILITY (CCRFGD 'APSO' MPU FACILITY)EXTENDED THROUGH QUEENSRIDG

```

*****
Station | Invert | Depth | Water | Q | Vel | Vel | Energy | Super | Critical | Flow Top | Height | Base Wt | | No Wth
        | Elev   | (FT)  | Elev  | (CFS) | (FPS) | Head | Grd.El. | Elev  | Depth  | Width  | Dia.-FT | or I.D. | ZL | Prs/Pip
L/Elem | Ch Slope |
***** |
-6058.180 | 2735.820 | 10.916 | 2746.736 | 2384.00 | 18.92 | 5.56 | 2752.29 | .00 | 9.00 | 14.00 | 9.000 | 14.000 | .00 | 0 | .0
        | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
244.970 | .0099 |
-5813.210 | 2738.240 | 10.827 | 2749.067 | 2384.00 | 18.92 | 5.56 | 2754.63 | .00 | 9.00 | 14.00 | 9.000 | 14.000 | .00 | 0 | .0
        | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
*****

```

↑

FILE: MAIN1_ExtendedModel.WSW MAIN1_ExtendedModel.EDT Date:12-18-2017 Time: 9:43:39
 W S P G W - EDIT LISTING - Version 14.10
 WATER SURFACE PROFILE - CHANNEL DEFINITION LISTING PAGE 1

CARD CODE	SECT NO	CHN TYPE	NO OF PIER/PIP WIDTH	AVE PIER WIDTH	HEIGHT 1 DIAMETER	BASE 1 WIDTH	ZL	ZR	INV DROP	Y(1)	Y(2)	Y(3)	Y(4)	Y(5)	Y(6)	Y(7)	Y(8)	Y(9)	Y(10)
CD	1	3	1	1.000	12.000	25.000	.000	.000	.00										
CD	2	3	0	.000	12.000	14.000	.000	.000	.00										
CD	3	3	0	.000	8.000	10.000	.000	.000	.00										
CD	4	3	0	.000	9.000	14.000	.000	.000	.00										
CD	5	4	1		4.000														
CD	6	4	1		6.000														
CD	10	3	1	1.000	12.000	25.000	.000	.000	.00										
CD	14	5	0		.000														
CD	15	5	0		.000														

FILE: W S P G W - EDIT LISTING - Version 14.10 Date:12-18-2017 Time: 9:43:39
 WATER SURFACE PROFILE - CROSS SECTION POINT LISTING PAGE 2

CARD CODE	SECT NO	NO OF POINTS	X(1), Y(1) X(8), Y(8)	X(2), Y(2) X(9), Y(9)	X(3), Y(3) X(10), Y(10)	X(4), Y(4) X(11), Y(11)	X(5), Y(5) X(N), Y(N)	X(6), Y(6) X(N+1), Y(N+1)	X(7), Y(7) X(35), Y(35)
PTS	14	8	.000 48.000	19.090 48.000	50.850 45.000	111.110 21.000	159.240 21.000	159.240 21.000	186.970 35.980
PTS			248.780 40.000						
PTS	15	6	.000 49.000	11.030 48.000	54.930 38.000	84.460 22.000	136.390 22.000	173.210 40.000	

W S P G W PAGE NO 1
 WATER SURFACE PROFILE - TITLE CARD LISTING

HEADING LINE NO 1 IS - THE SEVENTY - THE 435 (PHASE 1), GCW JOB NO. 840-050
 HEADING LINE NO 2 IS - 2ND RESPONSE TO CLV COMMENTS
 HEADING LINE NO 3 IS - MAIN1 FACILITY (CCRFGD 'APSO' MPU FACILITY)EXTENDED THROUGH QUEENSRIDGE LO

W S P G W PAGE NO 2
 WATER SURFACE PROFILE - ELEMENT CARD LISTING

ELEMENT NO	IS	A	SYSTEM OUTLET	STATION	INVERT	SECT	W S ELEV	RADIUS	ANGLE	ANG PT	MAN H
ELEMENT NO	1	IS	A	SYSTEM OUTLET							
				U/S DATA							
				-11897.270	2621.300	14	2623.822				
ELEMENT NO	2	IS	A	TRANSITION							
				U/S DATA							
				-11872.410	2621.650	15					
ELEMENT NO	3	IS	A	TRANSITION							
				U/S DATA							
				-11862.410	2621.810	10					
ELEMENT NO	4	IS	A	REACH							
				U/S DATA							
				-11772.100	2623.180	10					
ELEMENT NO	5	IS	A	REACH							
				U/S DATA							
				-11769.780	2623.000	10					
THE ABOVE ELEMENT CONTAINED AN INVERT ELEV WHICH WAS NOT GREATER THAN THE PREVIOUS INVERT ELEV -WARNING											
ELEMENT NO	6	IS	A	REACH							
				U/S DATA							
				-11699.160	2625.000	10					
ELEMENT NO	7	IS	A	REACH							
				U/S DATA							
				-11681.750	2625.480	10					
ELEMENT NO	8	IS	A	REACH							
				U/S DATA							
				-11596.450	2627.860	10					
ELEMENT NO	9	IS	A	REACH							
				U/S DATA							
				-11452.980	2631.860	10					
ELEMENT NO	10	IS	A	REACH							
				U/S DATA							
				-10980.090	2645.025	10					
ELEMENT NO	11	IS	A	REACH							
				U/S DATA							
				-10864.680	2648.238	10					
ELEMENT NO	12	IS	A	REACH							
				U/S DATA							
				-10746.460	2651.530	10					
ELEMENT NO	13	IS	A	REACH							
				U/S DATA							
				-10280.320	2655.259	10					

W S P G W PAGE NO 3
 WATER SURFACE PROFILE - ELEMENT CARD LISTING

ELEMENT NO	IS	A	REACH	STATION	INVERT	SECT	RADIUS	ANGLE	ANG PT	MAN H
ELEMENT NO	14	IS	A	REACH						
				U/S DATA						
				-10111.460	2656.610	10				
ELEMENT NO	15	IS	A	REACH						
				U/S DATA						
				-9546.460	2659.440	10				

WARNING - ADJACENT SECTIONS ARE NOT IDENTICAL - SEE SECTION NUMBERS AND CHANNEL DEFINITIONS

ELEMENT NO	IS	A	REACH	STATION	INVERT	SECT	RADIUS	ANGLE	ANG PT	MAN H
ELEMENT NO	16	IS	A	REACH						
				U/S DATA						
				-9401.300	2662.940	1				
ELEMENT NO	17	IS	A	JUNCTION						
				U/S DATA						
				-9391.300	2663.130	1				

W S P G W PAGE NO 3
 WATER SURFACE PROFILE - ELEMENT CARD LISTING

ELEMENT NO	IS	A	REACH	STATION	INVERT	SECT	RADIUS	ANGLE	ANG PT	MAN H
ELEMENT NO	14	IS	A	REACH						
				U/S DATA						
				-10111.460	2656.610	10				
ELEMENT NO	15	IS	A	REACH						
				U/S DATA						
				-9546.460	2659.440	10				

WARNING - ADJACENT SECTIONS ARE NOT IDENTICAL - SEE SECTION NUMBERS AND CHANNEL DEFINITIONS

ELEMENT NO	IS	A	REACH	STATION	INVERT	SECT	RADIUS	ANGLE	ANG PT	MAN H
ELEMENT NO	16	IS	A	REACH						
				U/S DATA						
				-9401.300	2662.940	1				
ELEMENT NO	17	IS	A	JUNCTION						
				U/S DATA						
				-9391.300	2663.130	1				

W S P G W PAGE NO 3
 WATER SURFACE PROFILE - ELEMENT CARD LISTING

ELEMENT NO	IS	A	REACH	STATION	INVERT	SECT	RADIUS	ANGLE	ANG PT	MAN H
ELEMENT NO	14	IS	A	REACH						
				U/S DATA						
				-10111.460	2656.610	10				
ELEMENT NO	15	IS	A	REACH						
				U/S DATA						
				-9546.460	2659.440	10				

WARNING - ADJACENT SECTIONS ARE NOT IDENTICAL - SEE SECTION NUMBERS AND CHANNEL DEFINITIONS

ELEMENT NO	IS	A	REACH	STATION	INVERT	SECT	RADIUS	ANGLE	ANG PT	MAN H
ELEMENT NO	16	IS	A	REACH						
				U/S DATA						
				-9401.300	2662.940	1				
ELEMENT NO	17	IS	A	JUNCTION						
				U/S DATA						
				-9391.300	2663.130	1				

W S P G W PAGE NO 3
 WATER SURFACE PROFILE - ELEMENT CARD LISTING

ELEMENT NO	IS	A	REACH	STATION	INVERT	SECT	RADIUS	ANGLE	ANG PT	MAN H
ELEMENT NO	14	IS	A	REACH						
				U/S DATA						
				-10111.460	2656.610	10				
ELEMENT NO	15	IS	A	REACH						
				U/S DATA						
				-9546.460	2659.440	10				

WARNING - ADJACENT SECTIONS ARE NOT IDENTICAL - SEE SECTION NUMBERS AND CHANNEL DEFINITIONS

ELEMENT NO	IS	A	REACH	STATION	INVERT	SECT	RADIUS	ANGLE	ANG PT	MAN H
ELEMENT NO	16	IS	A	REACH						
				U/S DATA						
				-9401.300	2662.940	1				
ELEMENT NO	17	IS	A	JUNCTION						
				U/S DATA						
				-9391.300	2663.130	1				

W S P G W PAGE NO 3
 WATER SURFACE PROFILE - ELEMENT CARD LISTING

ELEMENT NO	IS	A	REACH	STATION	INVERT	SECT	RADIUS	ANGLE	ANG PT	MAN H
ELEMENT NO	14	IS	A	REACH						
				U/S DATA						
				-10111.460	2656.610	10				
ELEMENT NO	15	IS	A	REACH						
				U/S DATA						
				-9546.460	2659.440	10				

WARNING - ADJACENT SECTIONS ARE NOT IDENTICAL - SEE SECTION NUMBERS AND CHANNEL DEFINITIONS

ELEMENT NO	IS	A	REACH	STATION	INVERT	SECT	RADIUS	ANGLE	ANG PT	MAN H
ELEMENT NO	16	IS	A	REACH						
				U/S DATA						
				-9401.300	2662.940	1				
ELEMENT NO	17	IS	A	JUNCTION						
				U/S DATA						
				-9391.300	2663.130	1				

W S P G W PAGE NO 3
 WATER SURFACE PROFILE - ELEMENT CARD LISTING

ELEMENT NO	IS	A	REACH	STATION	INVERT	SECT	RADIUS	ANGLE	ANG PT	MAN H
ELEMENT NO	14	IS	A	REACH						
				U/S DATA						
				-10111.460	2656.610	10				
ELEMENT NO	15	IS	A	REACH						
				U/S DATA						
				-9546.460	2659.440	10				

WARNING - ADJACENT SECTIONS ARE NOT IDENTICAL - SEE SECTION NUMBERS AND CHANNEL DEFINITIONS

ELEMENT NO	IS	A	REACH	STATION	INVERT	SECT	RADIUS	ANGLE	ANG PT	MAN H
ELEMENT NO	16	IS	A	REACH						
				U/S DATA						
				-9401.300	2662.940	1				
ELEMENT NO	17	IS	A	JUNCTION						
				U/S DATA						
				-9391.300	2663.130	1				

W S P G W PAGE NO 3
 WATER SURFACE PROFILE - ELEMENT CARD LISTING

ELEMENT NO	IS	A	REACH	STATION	INVERT	SECT	RADIUS	ANGLE	ANG PT	MAN H
ELEMENT NO	14	IS	A	REACH						
				U/S DATA						
				-10111.460	2656.610	10				
ELEMENT NO	15	IS	A	REACH						
				U/S DATA						
				-9546.460	2659.440	10				

WARNING - ADJACENT SECTIONS ARE NOT IDENTICAL - SEE SECTION NUMBERS AND CHANNEL DEFINITIONS

ELEMENT NO	IS	A	REACH	STATION	INVERT	SECT	RADIUS	ANGLE	ANG PT	MAN H
ELEMENT NO	16	IS	A	REACH						
				U/S DATA						
				-9401.300	2662.940	1				
ELEMENT NO	17	IS	A	JUNCTION						
				U/S DATA						
				-9391.300	2663.130	1				

W S P G W PAGE NO 3
 WATER SURFACE PROFILE - ELEMENT CARD LISTING

ELEMENT NO	IS	A	REACH	STATION	INVERT	SECT	RADIUS	ANGLE	ANG PT	MAN H
ELEMENT NO	14	IS	A	REACH						

ELEMENT NO	18	IS A REACH	STATION	INVERT	SECT	N	RADIUS	ANGLE	ANG PT	MAN H
		U/S DATA	-9196.460	2666.750	1	.015	.000	.000	.000	0
ELEMENT NO	19	IS A TRANSITION	STATION	INVERT	SECT	N	RADIUS	ANGLE		
		U/S DATA	-9166.460	2668.540	2	.020	.000	.000		
ELEMENT NO	20	IS A REACH	STATION	INVERT	SECT	N	RADIUS	ANGLE	ANG PT	MAN H
		U/S DATA	-9128.430	2670.810	2	.020	.000	.000	.000	0
ELEMENT NO	21	IS A REACH	STATION	INVERT	SECT	N	RADIUS	ANGLE	ANG PT	MAN H
		U/S DATA	-9038.350	2671.710	2	.015	150.000	34.408	.000	0
ELEMENT NO	22	IS A REACH	STATION	INVERT	SECT	N	RADIUS	ANGLE	ANG PT	MAN H
		U/S DATA	-8662.540	2675.470	2	.015	.000	.000	.000	0
ELEMENT NO	23	IS A REACH	STATION	INVERT	SECT	N	RADIUS	ANGLE	ANG PT	MAN H
		U/S DATA	-8553.120	2676.560	2	.015	499.984	12.539	.000	0
ELEMENT NO	24	IS A REACH	STATION	INVERT	SECT	N	RADIUS	ANGLE	ANG PT	MAN H
		U/S DATA	-8493.500	2677.160	2	.015	.000	.000	.000	0

ELEMENT NO	25	IS	A	REACH	STATION	INVERT	SECT					RADIUS	ANGLE	ANG PT	MAN H			
				U/S DATA	-8441.470	2677.683	2					150.001	-19.874	.000	0			
ELEMENT NO	26	IS	A	REACH	STATION	INVERT	SECT					RADIUS	ANGLE	ANG PT	MAN H			
				U/S DATA	-7825.450	2683.840	2					.000	.000	.000	0			
ELEMENT NO	27	IS	A	REACH	STATION	INVERT	SECT					RADIUS	ANGLE	ANG PT	MAN H			
				U/S DATA	-7710.000	2685.000	2					1458.613	-4.535	.000	0			
ELEMENT NO	28	IS	A	REACH	STATION	INVERT	SECT					RADIUS	ANGLE	ANG PT	MAN H			
				U/S DATA	-7573.640	2695.000	2					485.994	-16.076	.000	0			
ELEMENT NO	29	IS	A	JUNCTION	STATION	INVERT	SECT	4	1	LAT-2	N	Q3	Q4	INVERT-3	INVERT-4	PHI 3	PHI 4	
				U/S DATA	-7536.970	2697.680	2				0	.020	2008.000	.000	2697.680	.000	-15.000	.000

ELEMENT NO	30	IS A REACH	STATION	INVERT	SECT	N	RADIUS	ANGLE	ANG PT	MAN H
		U/S DATA	-7441.100	2704.768	4	.020	.000	.000	.000	0
ELEMENT NO	31	IS A REACH	STATION	INVERT	SECT	N	RADIUS	ANGLE	ANG PT	MAN H
		U/S DATA	-7361.100	2710.680	4	.020	266.554	-17.196	.000	0
ELEMENT NO	32	IS A REACH	STATION	INVERT	SECT	N	RADIUS	ANGLE	ANG PT	MAN H
		U/S DATA	-7235.120	2715.420	4	.020	585.982	-12.318	.000	0
ELEMENT NO	33	IS A REACH	STATION	INVERT	SECT	N	RADIUS	ANGLE	ANG PT	MAN H
		U/S DATA	-6922.570	2727.190	4	.020	.000	.000	.000	0
ELEMENT NO	34	IS A REACH	STATION	INVERT	SECT	N	RADIUS	ANGLE	ANG PT	MAN H
		U/S DATA	-6751.480	2729.550	4	.020	.000	.000	.000	0
ELEMENT NO	35	IS A JUNCTION	STATION	INVERT	SECT	N	INVERT-3	INVERT-4	PHI 3	PHI 4
		U/S DATA	-6741.480	2729.650	4	.015	2729.650	2729.650	45.000	-45.000
							RADIUS	ANGLE		
							.000	.000		

ELEMENT NO	36	IS A	REACH	STATION	INVERT	SECT					RADIUS	ANGLE	ANG PT	MAN H	
			U/S DATA	-6181.460	2735.100	4			N		.015	.000	.000	0	
ELEMENT NO	37	IS A	JUNCTION	STATION	INVERT	SECT	LAT-1	LAT-2	N	Q3	Q4	INVERT-3	INVERT-4	PHI 3	PHI 4
			U/S DATA	-6171.460	2735.200	4	*	*	.015	51.000	28.000	2735.150	2735.150	45.000	-45.000
												RADIUS	ANGLE		
												.000	.000		
ELEMENT NO	38	IS A	REACH	STATION	INVERT	SECT			N			RADIUS	ANGLE	ANG PT	MAN H
			U/S DATA	-6138.290	2735.531	4			.015			.000	.000	.000	0
ELEMENT NO	39	IS A	REACH	STATION	INVERT	SECT			N			RADIUS	ANGLE	ANG PT	MAN H
			U/S DATA	-6058.180	2735.820	4			.015			111.999	40.982	.000	0
ELEMENT NO	40	IS A	REACH	STATION	INVERT	SECT			N			RADIUS	ANGLE	ANG PT	MAN H
			U/S DATA	-5813.210	2738.240	4			.015			.000	.000	.000	0
ELEMENT NO	41	IS A	SYSTEM HEADWORKS	STATION	INVERT	SECT				*		W S ELEV			
			U/S DATA	-5813.210	2738.240	4						.000			

MAIN2-020.WSW									
T1 THE SEVENTY - THE 435 (PHASE 1), GCW JOB NO. 840-050									
T2 1ST RESPONSE TO CLV COMMENTS									
T3 MAIN2 FACILITY (CCRFGD 'APP2' MPU FACILITY)									
SO	-2775.6102697.680	1						2702.661	
R	-2648.9802712.970	1	.020					64.780	.000 0
R	-2556.6802716.660	1	.020					.000	.000 0
R	-2435.6102721.500	1	.020					-61.936	.000 0
R	-2218.9802726.000	1	.020					.000	.000 0
R	-2160.3602727.220	1	.015					29.988	.000 0
R	-1847.1002733.740	1	.015					.000	.000 0
R	-1764.2102734.560	1	.015					-42.404	.000 0
R	-1468.1802740.500	1	.015					.000	.000 0
SH	-1468.1802740.500	1						.000	
CD	1 3 0	.000	8.000	10.000	.000	.000	.00		
Q		2004.000	.0						

Station	Invert Elev	Depth (FT)	Water Elev	Q (CFS)	Vel (FPS)	Vel Head	Energy Grd.El.	Super Elev	Critical Depth	Flow Top Width	Height/Dia.-FT	Base Wt or I.D.	ZL	No Wth Prs/Pip
L/Elem	Ch Slope				SF Ave	HF	SE Dpth	Froude N	Norm Dp	"N"	X-Fall	ZR	Type Ch	
*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****
-2775.610	2697.680	5.269	2702.949	2004.00	38.04	22.46	2725.41	8.00	8.00	10.00	8.000	10.000	.00	0 .0
2.885	.1207					.0743	.21	8.00	2.92	4.40	.020	.00	.00	BOX
-2772.726	2698.028	5.286	2703.315	2004.00	37.91	22.31	2725.63	8.00	8.00	10.00	8.000	10.000	.00	0 .0
34.610	.1207					.0696	2.41	8.00	2.91	4.40	.020	.00	.00	BOX
-2738.115	2702.207	5.544	2707.752	2004.00	36.14	20.29	2728.04	8.00	8.00	10.00	8.000	10.000	.00	0 .0
26.507	.1207					.0614	1.63	8.00	2.71	4.40	.020	.00	.00	BOX
-2711.608	2705.408	5.815	2711.223	2004.00	34.46	18.44	2729.66	8.00	8.00	10.00	8.000	10.000	.00	0 .0
20.924	.1207					.0542	1.13	8.00	2.52	4.40	.020	.00	.00	BOX
-2690.684	2707.934	6.099	2714.033	2004.00	32.86	16.77	2730.80	8.00	8.00	10.00	8.000	10.000	.00	0 .0
16.829	.1207					.0479	.81	8.00	2.34	4.40	.020	.00	.00	BOX
-2673.856	2709.966	6.397	2716.363	2004.00	31.33	15.24	2731.60	8.00	8.00	10.00	8.000	10.000	.00	0 .0
13.686	.1207					.0423	.58	8.00	2.18	4.40	.020	.00	.00	BOX
-2660.170	2711.619	6.709	2718.328	2004.00	29.87	13.86	2732.18	8.00	8.00	10.00	8.000	10.000	.00	0 .0
11.190	.1207					.0374	.42	8.00	2.03	4.40	.020	.00	.00	BOX
-2648.980	2712.970	7.036	2720.006	2004.00	28.48	12.60	2732.60	.00	8.00	10.00	8.000	10.000	.00	0 .0
92.300	.0400					.0337	3.11	7.04	1.89	6.69	.020	.00	.00	BOX
-2556.680	2716.660	7.276	2723.936	2004.00	27.54	11.78	2735.71	8.00	8.00	10.00	8.000	10.000	.00	0 .0
74.553	.0400					.0305	2.27	8.00	1.80	6.69	.020	.00	.00	BOX

----- WARNING - Flow depth near top of box conduit -----

Station	Invert Elev	Depth (FT)	Water Elev	Q (CFS)	Vel (FPS)	Vel Head	Energy Grd.El.	Super Elev	Critical Depth	Flow Top Width	Height/Dia.-FT	Base Wt or I.D.	ZL	No Wth Prs/Pip
L/Elem	Ch Slope				SF Ave	HF	SE Dpth	Froude N	Norm Dp	"N"	X-Fall	ZR	Type Ch	
*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****
-2482.127	2719.640	7.627	2727.267	2004.00	26.28	10.72	2737.99	8.00	8.00	10.00	8.000	10.000	.00	0 .0
46.517	.0400					.0339	1.58	8.00	1.68	6.69	.020	.00	.00	BOX
----- WARNING - Flow depth near top of box conduit -----														
-2435.610	2721.500	8.000	2729.500	2004.00	25.05	9.74	2739.24	.00	8.00	10.00	8.000	10.000	.00	0 .0
216.630	.0208					.0392	8.49	8.00	1.56	8.00	.020	.00	.00	BOX
-2218.980	2726.000	11.991	2737.991	2004.00	25.05	9.74	2747.74	.00	8.00	10.00	8.000	10.000	.00	0 .0
58.620	.0208					.0220	1.29	.00	1.56	6.90	.015	.00	.00	BOX
-2160.360	2727.220	13.189	2740.409	2004.00	25.05	9.74	2750.15	.00	8.00	10.00	8.000	10.000	.00	0 .0
313.260	.0208					.0220	6.91	13.19	1.56	6.90	.015	.00	.00	BOX
-1847.100	2733.740	13.576	2747.316	2004.00	25.05	9.74	2757.06	.00	8.00	10.00	8.000	10.000	.00	0 .0
82.890	.0099					.0220	1.83	.00	1.56	8.00	.015	.00	.00	BOX
-1764.210	2734.560	15.921	2750.481	2004.00	25.05	9.74	2760.22	.00	8.00	10.00	8.000	10.000	.00	0 .0
296.030	.0201					.0220	6.53	15.92	1.56	7.00	.015	.00	.00	BOX
-1468.180	2740.500	16.508	2757.008	2004.00	25.05	9.74	2766.75	.00	8.00	10.00	8.000	10.000	.00	0 .0




FILE: MAIN2-020.WSW
 W S P G W - EDIT LISTING - Version 14.10
 WATER SURFACE PROFILE - CHANNEL DEFINITION LISTING
 Date:12-21-2017 Time: 8:30:16
 PAGE 1
 CARD SECT CHN NO OF AVE PIER HEIGHT 1 BASE ZL ZR INV Y(1) Y(2) Y(3) Y(4) Y(5) Y(6) Y(7) Y(8) Y(9) Y(10)
 CODE NO TYPE PIER/PIP WIDTH DIAMETER WIDTH DROP
 CD 1 3 0 .000 8.000 10.000 .000 .000 .00
 W S P G W
 WATER SURFACE PROFILE - TITLE CARD LISTING
 PAGE NO 1


HEADING LINE NO 1 IS -
 THE SEVENTY - THE 435 (PHASE 1), GCW JOB NO. 840-050
 HEADING LINE NO 2 IS -
 1ST RESPONSE TO CLV COMMENTS
 HEADING LINE NO 3 IS -
 MAIN2 FACILITY (CCRFGD 'APP2' MPU FACILITY)


W S P G W
 WATER SURFACE PROFILE - ELEMENT CARD LISTING
 PAGE NO 2
 ELEMENT NO 1 IS A SYSTEM OUTLET * * *
 U/S DATA STATION INVERT SECT
 -2775.610 2697.680 1
 W S ELEV
 2702.661
 ELEMENT NO 2 IS A REACH * * *
 U/S DATA STATION INVERT SECT N
 -2648.980 2712.970 1 .020 RADIUS ANGLE ANG PT MAN H
 112.000 64.780 .000 0
 ELEMENT NO 3 IS A REACH * * *
 U/S DATA STATION INVERT SECT N
 -2556.680 2716.660 1 .020 RADIUS ANGLE ANG PT MAN H
 .000 .000 .000 0
 ELEMENT NO 4 IS A REACH * * *
 U/S DATA STATION INVERT SECT N
 -2435.610 2721.500 1 .020 RADIUS ANGLE ANG PT MAN H
 111.999 -61.936 .000 0
 ELEMENT NO 5 IS A REACH * * *
 U/S DATA STATION INVERT SECT N
 -2218.980 2726.000 1 .020 RADIUS ANGLE ANG PT MAN H
 .000 .000 .000 0
 ELEMENT NO 6 IS A REACH * * *
 U/S DATA STATION INVERT SECT N
 -2160.360 2727.220 1 .015 RADIUS ANGLE ANG PT MAN H
 112.001 29.988 .000 0
 ELEMENT NO 7 IS A REACH * * *
 U/S DATA STATION INVERT SECT N
 -1847.100 2733.740 1 .015 RADIUS ANGLE ANG PT MAN H
 .000 .000 .000 0
 ELEMENT NO 8 IS A REACH * * *
 U/S DATA STATION INVERT SECT N
 -1764.210 2734.560 1 .015 RADIUS ANGLE ANG PT MAN H
 112.000 -42.404 .000 0
 ELEMENT NO 9 IS A REACH * * *
 U/S DATA STATION INVERT SECT N
 -1468.180 2740.500 1 .015 RADIUS ANGLE ANG PT MAN H
 .000 .000 .000 0
 ELEMENT NO 10 IS A SYSTEM HEADWORKS *
 U/S DATA STATION INVERT SECT
 -1468.180 2740.500 1
 W S ELEV
 .000


HEC-RAS Plan: PLAN02 Rwr: FEMA Wash Reach: MAUN1 Profile: PF 1


Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Max Ch Dpth (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Vel Left (ft/s)	Vel Right (ft/s)	Flow Area (sq ft)	Top Width (ft)	Froude # Chl
MAIN1	1400	PF 1	2489.00	2702.00	2713.89	11.89	2713.89	2716.96	0.016165	14.07			176.93	28.94	1.00
MAIN1	1383.33*	PF 1	2489.00	2701.33	2707.42	6.09	2710.11	2715.32	0.048728	22.53			110.46	21.74	1.76
MAIN1	1366.67*	PF 1	2489.00	2700.67	2705.20	4.53	2707.62	2712.94	0.055747	22.31			111.55	28.20	1.98
MAIN1	1350.00*	PF 1	2489.00	2700.00	2709.80	9.80	2705.86	2710.47	0.002108	6.52			381.64	54.41	0.43
MAIN1	1333.33*	PF 1	2489.00	2699.33	2709.97	10.64		2710.31	0.000911	4.68			531.90	69.15	0.30
MAIN1	1316.67*	PF 1	2489.00	2698.67	2710.04	11.37		2710.24	0.000453	3.56			699.93	83.39	0.22
MAIN1	1300	PF 1	2489.00	2698.00	2710.08	12.08		2710.20	0.000247	2.81			887.13	96.89	0.16
MAIN1	1299	PF 1	2489.00	2698.00	2710.08	12.08		2710.20	0.000276	2.81			887.13	96.89	0.16
MAIN1	1199.50*	PF 1	2489.00	2697.65	2710.07	12.42		2710.19	0.000264	2.77			897.95	96.58	0.16
MAIN1	1100	PF 1	2489.00	2697.30	2710.07	12.76		2710.18	0.000254	2.74			908.05	96.28	0.16
MAIN1	1099	PF 1	4497.00	2691.81	2705.87	14.06	2705.87	2709.77	0.003504	17.70	6.05	5.96	365.25	51.95	0.83
MAIN1	1098	PF 1	4497.00	2688.22	2701.60	13.38	2703.89	2709.15	0.008650	22.65	6.04	6.04	229.55	32.39	1.09
MAIN1	1000	PF 1	4497.00	2685.00	2696.89	11.89	2699.71	2708.23	0.018310	27.02			166.44	14.00	1.38
MAIN1	966.67*	PF 1	4497.00	2684.61	2696.78	12.17	2699.32	2707.61	0.014006	26.40			170.31	14.00	1.33
MAIN1	933.33*	PF 1	4497.00	2684.23	2696.57	12.33	2698.94	2707.10	0.012070	26.04			172.69	14.00	1.31
MAIN1	900	PF 1	4497.00	2683.84	2696.20	12.36	2698.55	2706.70	0.009354	25.99			173.01	14.00	1.30
MAIN1	892.31*	PF 1	4497.00	2683.37	2695.69	12.32	2698.08	2706.26	0.009426	26.07			172.47	14.00	1.31
MAIN1	884.62*	PF 1	4497.00	2682.89	2695.16	12.27	2697.60	2705.81	0.009520	26.18			171.78	14.00	1.32
MAIN1	876.92*	PF 1	4497.00	2682.42	2694.66	12.24	2697.13	2705.36	0.009571	26.23			171.42	14.00	1.32
MAIN1	869.23*	PF 1	4497.00	2681.94	2694.15	12.21	2696.65	2704.91	0.009641	26.31			170.91	14.00	1.33
MAIN1	861.54*	PF 1	4497.00	2681.47	2693.66	12.19	2696.18	2704.45	0.009675	26.35			170.67	14.00	1.33
MAIN1	853.85*	PF 1	4497.00	2681.00	2693.18	12.17	2695.71	2703.99	0.009707	26.38			170.44	14.00	1.33
MAIN1	846.15*	PF 1	4497.00	2680.52	2692.67	12.15	2695.23	2703.53	0.009759	26.44			170.08	14.00	1.34
MAIN1	838.46*	PF 1	4497.00	2680.05	2692.19	12.14	2694.76	2703.07	0.009779	26.46			169.94	14.00	1.34
MAIN1	830.77*	PF 1	4497.00	2679.58	2691.71	12.13	2694.29	2702.61	0.009794	26.48			169.84	14.00	1.34
MAIN1	823.08*	PF 1	4497.00	2679.10	2691.21	12.11	2693.81	2702.14	0.009836	26.52			169.55	14.00	1.34
MAIN1	815.38*	PF 1	4497.00	2678.63	2690.75	12.12	2693.34	2701.67	0.009825	26.51			169.62	14.00	1.34
MAIN1	807.69*	PF 1	4497.00	2678.15	2690.25	12.10	2692.86	2701.20	0.009861	26.55			169.37	14.00	1.35
MAIN1	800	PF 1	4497.00	2677.68	2689.78	12.10	2692.39	2700.73	0.009854	26.54			169.42	14.00	1.35























HEC-RAS HEC-RAS 5.0.3 September 2016
 U.S. Army Corps of Engineers
 Hydrologic Engineering Center
 609 Second Street
 Davis, California

```

X   X   XXXXXX   XXXX   XXXX   XX   XXXX
X   X   X       X   X       X   X   X   X   X
X   X   X       X   X       X   X   X   X   X
XXXXXXXX XXXX   X   XXX XXXX XXXXXX XXXX
X   X   X       X   X       X   X   X   X   X
X   X   X       X   X       X   X   X   X   X
X   X   XXXXXX   XXXX   X   X   X   X   XXXX

```

PROJECT DATA

Project Title: Interim Collector
 Project File : InterimCollector.prj
 Run Date and Time: 12/20/2017 05:45:17 PM

Project in English units

PLAN DATA

Plan Title: Official
 Plan File : f:\Projects\800\840-050\Division\Fctl\Calcs\RTC2\HECRAS\InterimCollector.p02

Geometry Title: Official
 Geometry File : f:\Projects\800\840-050\Division\Fctl\Calcs\RTC2\HECRAS\InterimCollector.g02

Flow Title : Official
 Flow File : f:\Projects\800\840-050\Division\Fctl\Calcs\RTC2\HECRAS\InterimCollector.f01

Plan Summary Information:

Number of:	Cross Sections = 29	Multiple Openings = 0
	Culverts = 0	Inline Structures = 0
	Bridges = 0	Lateral Structures = 0

Computational Information

Water surface calculation tolerance	= 0.01
Critical depth calculation tolerance	= 0.01
Maximum number of iterations	= 20
Maximum difference tolerance	= 0.3
Flow tolerance factor	= 0.001

Computation Options

Critical depth computed only where necessary
 Conveyance Calculation Method: At breaks in n values only
 Friction Slope Method: Average Conveyance
 Computational Flow Regime: Mixed Flow

FLOW DATA

Flow Title: Official
 Flow File : f:\Projects\800\840-050\Division\Fctl\Calcs\RTC2\HECRAS\InterimCollector.f01

Flow Data (cfs)

River	Reach	RS	PF 1
FEMA Wash	MAIN1	1400	2489
FEMA Wash	MAIN1	1099	4497

Boundary Conditions

River	Reach	Profile	Upstream	Downstream
FEMA Wash	MAIN1	PF 1	Normal S = 0.015	Normal S = 0.01

GEOMETRY DATA

Geometry Title: Official
 Geometry File : f:\Projects\800\840-050\Division\Fctl\Calcs\RTC2\HECRAS\InterimCollector.g02

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1

RS: 1400

INPUT

Description: Existing Wash - Upstream Analysis Limits

Station Elevation Data		num= 24							
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	2720	6.86	2719	11.59	2718	21.44	2715	25.17	2713
30.02	2710	30.88	2709	31.6	2708	33	2706	33.73	2705
34.42	2704	41.24	2702.26	42.26	2702	45.17	2702	45.29	2704
45.32	2705	45.5	2708	45.52	2709	45.55	2710	46.41	2711
48.5	2712	50.57	2713	52.69	2714	55.15	2715		

Manning's n Values		num= 3			
Sta	n Val	Sta	n Val	Sta	n Val
0	.035	0	.035	55.15	.035

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
0	55.15	47.29	44.84	43.76	.1	.3	

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2716.96	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.08	Wt. n-Val.		0.035	
W.S. Elev (ft)	2713.89	Reach Len. (ft)	47.29	44.84	43.76
Crit W.S. (ft)	2713.89	Flow Area (sq ft)		176.93	
E.G. Slope (ft/ft)	0.016165	Area (sq ft)		176.93	
Q Total (cfs)	2489.00	Flow (cfs)		2489.00	
Top Width (ft)	28.94	Top Width (ft)		28.94	
Vel Total (ft/s)	14.07	Avg. Vel. (ft/s)		14.07	
Max Chl Dpth (ft)	11.89	Hydr. Depth (ft)		6.11	
Conv. Total (cfs)	19576.8	Conv. (cfs)		19576.8	
Length Wtd. (ft)	44.84	Wetted Per. (ft)		42.05	
Min Ch El (ft)	2702.00	Shear (lb/sq ft)		4.25	
Alpha	1.00	Stream Power (lb/ft s)		59.73	
Frctn Loss (ft)	1.17	Cum Volume (acre-ft)	0.11	7.46	0.12
C & E Loss (ft)	0.48	Cum SA (acres)	0.03	0.78	0.03

Warning: Slope too shallow for slope area to converge during supercritical flow calculations (normal depth is above critical depth). Water surface set to critical depth.

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1

RS: 1383.33*

INPUT

Description:

Station Elevation Data		num= 24							
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	2719.17	6.58	2717.87	11.12	2716.72	20.57	2713.56	24.15	2711.65
28.81	2708.82	29.63	2707.93	30.32	2707.05	31.66	2705.29	32.37	2704.41
33.03	2703.53	39.57	2701.62	40.55	2701.33	51.31	2701.33	51.46	2703.03
51.5	2703.87	51.74	2706.41	51.76	2707.25	51.8	2708.09	52.92	2709.12
55.64	2710.45	58.33	2711.76	61.09	2713.09	64.29	2714.5		

Manning's n Values		num= 2			
Sta	n Val	Sta	n Val	Sta	n Val
0	.035	64.29	.035		

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
0	64.29	47.29	44.84	43.76	.1	.3	

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2715.32	Element	Left OB	Channel	Right OB
Vel Head (ft)	7.89	Wt. n-Val.		0.035	
W.S. Elev (ft)	2707.42	Reach Len. (ft)	47.29	44.84	43.76
Crit W.S. (ft)	2710.11	Flow Area (sq ft)		110.46	
E.G. Slope (ft/ft)	0.048728	Area (sq ft)		110.46	
Q Total (cfs)	2489.00	Flow (cfs)		2489.00	
Top Width (ft)	21.74	Top Width (ft)		21.74	
Vel Total (ft/s)	22.53	Avg. Vel. (ft/s)		22.53	
Max Chl Dpth (ft)	6.09	Hydr. Depth (ft)		5.08	
Conv. Total (cfs)	11275.5	Conv. (cfs)		11275.5	
Length Wtd. (ft)	44.84	Wetted Per. (ft)		29.63	
Min Ch El (ft)	2701.33	Shear (lb/sq ft)		11.34	
Alpha	1.00	Stream Power (lb/ft s)		255.58	
Frctn Loss (ft)	2.33	Cum Volume (acre-ft)	0.11	7.31	0.12
C & E Loss (ft)	0.05	Cum SA (acres)	0.03	0.75	0.03

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.

Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate

the need for additional cross sections.

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1

RS: 1366.67*

INPUT

Description:

Station	Elevation	Data	num=	24	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	2718.33	6.3	2716.75	10.65	2715.45	19.7	2712.12	23.13	2710.29			
27.59	2707.64	28.38	2706.86	29.04	2706.1	30.33	2704.57	31	2703.81			
31.63	2703.05	37.9	2700.98	38.84	2700.67	57.45	2700.67	57.64	2702.06			
57.69	2702.74	57.98	2704.82	58.01	2705.5	58.06	2706.18	59.43	2707.25			
62.78	2708.89	66.1	2710.53	69.49	2712.18	73.43	2714					

Manning's n Values

num= 2

Sta	n Val	Sta	n Val
0	.035	73.43	.035

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
0	73.43	47.29	44.84	43.76	.1	.3	

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2712.94	Element	Left OB	Channel	Right OB
Vel Head (ft)	7.74	Wt. n-Val.		0.035	
W.S. Elev (ft)	2705.20	Reach Len. (ft)	47.29	44.84	43.76
Crit W.S. (ft)	2707.62	Flow Area (sq ft)		111.55	
E.G. Slope (ft/ft)	0.055747	Area (sq ft)		111.55	
Q Total (cfs)	2489.00	Flow (cfs)		2489.00	
Top Width (ft)	28.20	Top Width (ft)		28.20	
Vel Total (ft/s)	22.31	Avg. Vel. (ft/s)		22.31	
Max Chl Dpth (ft)	4.53	Hydr. Depth (ft)		3.96	
Conv. Total (cfs)	10541.8	Conv. (cfs)		10541.8	
Length Wtd. (ft)	44.84	Wetted Per. (ft)		33.59	
Min Ch El (ft)	2700.67	Shear (lb/sq ft)		11.56	
Alpha	1.00	Stream Power (lb/ft s)		257.92	
Frctn Loss (ft)	0.15	Cum Volume (acre-ft)	0.11	7.20	0.12
C & E Loss (ft)	0.29	Cum SA (acres)	0.03	0.73	0.03

Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1

RS: 1350.00*

INPUT

Description:

Station	Elevation	Data	num=	24	Sta	Elev	Sta	Elev	Sta	Elev
0	2717.5	6.03	2715.62	10.18	2714.17	18.84	2710.69	22.11	2708.94	
26.38	2706.46	27.13	2705.79	27.76	2705.14	28.99	2703.86	29.64	2703.22	
30.24	2702.58	36.23	2700.34	37.13	2700	63.58	2700	63.81	2701.08	
63.87	2701.61	64.21	2703.23	64.25	2703.75	64.31	2704.27	65.94	2705.37	
69.92	2707.34	73.86	2709.29	77.89	2711.27	82.57	2713.5			

Manning's n Values

num= 2

Sta	n Val	Sta	n Val
0	.035	82.57	.035

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
0	82.57	47.29	44.84	43.76	.1	.3	

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2710.47	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.66	Wt. n-Val.		0.035	
W.S. Elev (ft)	2709.80	Reach Len. (ft)	47.29	44.84	43.76
Crit W.S. (ft)	2705.86	Flow Area (sq ft)		381.64	
E.G. Slope (ft/ft)	0.002108	Area (sq ft)		381.64	
Q Total (cfs)	2489.00	Flow (cfs)		2489.00	
Top Width (ft)	54.41	Top Width (ft)		54.41	
Vel Total (ft/s)	6.52	Avg. Vel. (ft/s)		6.52	
Max Chl Dpth (ft)	9.80	Hydr. Depth (ft)		7.01	
Conv. Total (cfs)	54209.1	Conv. (cfs)		54209.1	
Length Wtd. (ft)	44.84	Wetted Per. (ft)		62.36	
Min Ch El (ft)	2700.00	Shear (lb/sq ft)		0.81	
Alpha	1.00	Stream Power (lb/ft s)		5.25	
Frctn Loss (ft)	0.06	Cum Volume (acre-ft)	0.11	6.94	0.12
C & E Loss (ft)	0.10	Cum SA (acres)	0.03	0.69	0.03

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.

Note: Hydraulic jump has occurred between this cross section and the previous upstream section.

CROSS SECTION

RIVER: FEMA Wash

REACH: MAIN1 RS: 1333.33*

INPUT

Description:

Station	Elevation	Data	num=	24	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	2716.67	5.75	2714.49	9.71	2712.89	17.97	2709.25	21.1	2707.58			
25.16	2705.28	25.88	2704.72	26.49	2704.19	27.66	2703.15	28.27	2702.62			
28.85	2702.1	34.57	2699.69	35.42	2699.33	69.72	2699.33	69.99	2700.11			
70.05	2700.47	70.45	2701.64	70.49	2701.99	70.56	2702.36	72.46	2703.49			
77.06	2705.78	81.62	2708.05	86.3	2710.37	91.72	2713					

Manning's n Values num= 2

Sta	n Val	Sta	n Val
0	.035	91.72	.035

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
0	91.72	47.29	44.84	43.76	.1	.3	

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2710.31	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.34	Wt. n-Val.		0.035	
W.S. Elev (ft)	2709.97	Reach Len. (ft)	47.29	44.84	43.76
Crit W.S. (ft)		Flow Area (sq ft)		531.90	
E.G. Slope (ft/ft)	0.000911	Area (sq ft)		531.90	
Q Total (cfs)	2489.00	Flow (cfs)		2489.00	
Top Width (ft)	69.15	Top Width (ft)		69.15	
Vel Total (ft/s)	4.68	Avg. Vel. (ft/s)		4.68	
Max Chl Dpth (ft)	10.64	Hydr. Depth (ft)		7.69	
Conv. Total (cfs)	82466.0	Conv. (cfs)		82466.0	
Length Wtd. (ft)	44.84	Wetted Per. (ft)		76.22	
Min Ch El (ft)	2699.33	Shear (lb/sq ft)		0.40	
Alpha	1.00	Stream Power (lb/ft s)		1.86	
Frctn Loss (ft)	0.03	Cum Volume (acre-ft)	0.11	6.47	0.12
C & E Loss (ft)	0.04	Cum SA (acres)	0.03	0.62	0.03

CROSS SECTION

RIVER: FEMA Wash

REACH: MAIN1 RS: 1316.67*

INPUT

Description:

Station	Elevation	Data	num=	24	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	2715.83	5.47	2713.37	9.25	2711.61	17.1	2707.81	20.08	2706.23			
23.95	2704.1	24.63	2703.65	25.21	2703.24	26.32	2702.44	26.91	2702.03			
27.46	2701.63	32.9	2699.05	33.71	2698.67	75.86	2698.67	76.16	2699.14			
76.24	2699.34	76.69	2700.05	76.74	2700.24	76.81	2700.44	78.97	2701.62			
84.2	2704.23	89.39	2706.81	94.7	2709.46	100.86	2712.5					

Manning's n Values num= 2

Sta	n Val	Sta	n Val
0	.035	100.86	.035

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
0	100.86	47.29	44.84	43.76	.1	.3	

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2710.24	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.20	Wt. n-Val.		0.035	
W.S. Elev (ft)	2710.04	Reach Len. (ft)	47.29	44.84	43.76
Crit W.S. (ft)		Flow Area (sq ft)		699.93	
E.G. Slope (ft/ft)	0.000453	Area (sq ft)		699.93	
Q Total (cfs)	2489.00	Flow (cfs)		2489.00	
Top Width (ft)	83.39	Top Width (ft)		83.39	
Vel Total (ft/s)	3.56	Avg. Vel. (ft/s)		3.56	
Max Chl Dpth (ft)	11.37	Hydr. Depth (ft)		8.39	
Conv. Total (cfs)	116953.4	Conv. (cfs)		116953.4	
Length Wtd. (ft)	44.84	Wetted Per. (ft)		89.64	
Min Ch El (ft)	2698.67	Shear (lb/sq ft)		0.22	
Alpha	1.00	Stream Power (lb/ft s)		0.79	
Frctn Loss (ft)	0.01	Cum Volume (acre-ft)	0.11	5.84	0.12
C & E Loss (ft)	0.02	Cum SA (acres)	0.03	0.54	0.03

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1 RS: 1300

INPUT

Description:

Station	Elevation	Data	num=	4			
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	2715	32	2698	82	2698	110	2712

Manning's n Values		num=	3
Sta	n Val	Sta	n Val
0	.035	0	.035
110	.035		

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	0	110		.1	.1		.1	.3

CROSS SECTION OUTPUT Profile #PF 1

	E.G. Elev (ft)	2710.20	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.12		Wt. n-Val.		0.035	
W.S. Elev (ft)	2710.08		Reach Len. (ft)	0.10	0.10	0.10
Crit W.S. (ft)			Flow Area (sq ft)		887.13	
E.G. Slope (ft/ft)	0.000247		Area (sq ft)		887.13	
Q Total (cfs)	2489.00		Flow (cfs)		2489.00	
Top Width (ft)	96.89		Top Width (ft)		96.89	
Vel Total (ft/s)	2.81		Avg. Vel. (ft/s)		2.81	
Max Chl Dpth (ft)	12.08		Hydr. Depth (ft)		9.16	
Conv. Total (cfs)	158505.3		Conv. (cfs)		158505.3	
Length Wtd. (ft)	0.10		Wetted Per. (ft)		102.75	
Min Ch El (ft)	2698.00		Shear (lb/sq ft)		0.13	
Alpha	1.00		Stream Power (lb/ft s)		0.37	
Frctn Loss (ft)	0.00		Cum Volume (acre-ft)	0.11	5.02	0.12
C & E Loss (ft)	0.00		Cum SA (acres)	0.03	0.45	0.03

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1 RS: 1299

INPUT

Description:

Station	Elevation	Data	num=	4			
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	2715	32	2698	82	2698	110	2712

Manning's n Values		num=	3
Sta	n Val	Sta	n Val
0	.037	0	.037
110	.037		

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	0	110		49.33	33.5		.1	.3

CROSS SECTION OUTPUT Profile #PF 1

	E.G. Elev (ft)	2710.20	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.12		Wt. n-Val.		0.037	
W.S. Elev (ft)	2710.08		Reach Len. (ft)	49.33	33.50	28.05
Crit W.S. (ft)			Flow Area (sq ft)		887.13	
E.G. Slope (ft/ft)	0.000276		Area (sq ft)		887.13	
Q Total (cfs)	2489.00		Flow (cfs)		2489.00	
Top Width (ft)	96.89		Top Width (ft)		96.89	
Vel Total (ft/s)	2.81		Avg. Vel. (ft/s)		2.81	
Max Chl Dpth (ft)	12.08		Hydr. Depth (ft)		9.16	
Conv. Total (cfs)	149937.5		Conv. (cfs)		149937.5	
Length Wtd. (ft)	33.50		Wetted Per. (ft)		102.75	
Min Ch El (ft)	2698.00		Shear (lb/sq ft)		0.15	
Alpha	1.00		Stream Power (lb/ft s)		0.42	
Frctn Loss (ft)	0.01		Cum Volume (acre-ft)	0.11	5.02	0.12
C & E Loss (ft)	0.00		Cum SA (acres)	0.03	0.45	0.03

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1 RS: 1199.50*

INPUT

Description:

Station	Elevation	Data	num=	4			
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	2715	34	2697.65	82	2697.65	110	2712

Manning's n Values		num=	2
Sta	n Val	Sta	n Val

0 .037 110 .037

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	0	110		49.33 33.5	28.05		.1	.3

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2710.19	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.12	Wt. n-Val.		0.037	
W.S. Elev (ft)	2710.07	Reach Len. (ft)	49.33	33.50	28.05
Crit W.S. (ft)		Flow Area (sq ft)		897.95	
E.G. Slope (ft/ft)	0.000264	Area (sq ft)		897.95	
Q Total (cfs)	2489.00	Flow (cfs)		2489.00	
Top Width (ft)	96.58	Top Width (ft)		96.58	
Vel Total (ft/s)	2.77	Avg. Vel. (ft/s)		2.77	
Max Chl Dpth (ft)	12.42	Hydr. Depth (ft)		9.30	
Conv. Total (cfs)	153187.6	Conv. (cfs)		153187.6	
Length Wtd. (ft)	33.50	Wetted Per. (ft)		102.56	
Min Ch El (ft)	2697.65	Shear (lb/sq ft)		0.14	
Alpha	1.00	Stream Power (lb/ft s)		0.40	
Frctn Loss (ft)	0.01	Cum Volume (acre-ft)	0.11	4.33	0.12
C & E Loss (ft)	0.00	Cum SA (acres)	0.03	0.38	0.03

CROSS SECTION

RIVER: FEMA Wash
 REACH: MAIN1 RS: 1100

INPUT

Description:

Station	Elevation	Data	num=	4
Sta	Elev	Sta	Elev	Sta
0	2715	36	2697.3	82 2697.3 110 2712

Manning's n Values	num=	3
Sta	n Val	Sta
0	.037	0

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	0	110		38.24 30	60		.1	.3

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2710.18	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.12	Wt. n-Val.		0.037	
W.S. Elev (ft)	2710.07	Reach Len. (ft)	38.24	30.00	60.00
Crit W.S. (ft)		Flow Area (sq ft)		908.05	
E.G. Slope (ft/ft)	0.000254	Area (sq ft)		908.05	
Q Total (cfs)	2489.00	Flow (cfs)		2489.00	
Top Width (ft)	96.28	Top Width (ft)		96.28	
Vel Total (ft/s)	2.74	Avg. Vel. (ft/s)		2.74	
Max Chl Dpth (ft)	12.76	Hydr. Depth (ft)		9.43	
Conv. Total (cfs)	156243.5	Conv. (cfs)		156243.5	
Length Wtd. (ft)	32.65	Wetted Per. (ft)		102.39	
Min Ch El (ft)	2697.30	Shear (lb/sq ft)		0.14	
Alpha	1.00	Stream Power (lb/ft s)		0.39	
Frctn Loss (ft)	0.03	Cum Volume (acre-ft)	0.11	3.64	0.12
C & E Loss (ft)	0.38	Cum SA (acres)	0.03	0.30	0.03

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: FEMA Wash
 REACH: MAIN1 RS: 1099

INPUT

Description:

Station	Elevation	Data	num=	6
Sta	Elev	Sta	Elev	Sta
0	2715	41	2697	41 2691.81 55 2691.81 55 2697
91	2715			

Manning's n Values	num=	3
Sta	n Val	Sta
0	.037	41

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	41	55		49 49	49		.1	.3

CROSS SECTION OUTPUT Profile #PF 1

InterimCollector.rep					
		Element	Left OB	Channel	Right OB
E.G. Elev (ft)	2709.77	Wt. n-Val.	0.037	0.020	0.037
Vel Head (ft)	3.90	Reach Len. (ft)	49.00	49.00	49.00
W.S. Elev (ft)	2705.87	Flow Area (sq ft)	89.66	196.88	78.72
Crit W.S. (ft)	2705.87	Area (sq ft)	89.66	196.88	78.72
E.G. Slope (ft/ft)	0.003504	Flow (cfs)	542.64	3485.28	469.08
Q Total (cfs)	4497.00	Top Width (ft)	20.21	14.00	17.75
Top Width (ft)	51.95	Avg. Vel. (ft/s)	6.05	17.70	5.96
Vel Total (ft/s)	12.31	Hydr. Depth (ft)	4.44	14.06	4.44
Max Chl Dpth (ft)	14.06	Conv. (cfs)	9166.5	58874.7	7923.8
Conv. Total (cfs)	75965.0	Wetted Per. (ft)	22.07	24.38	19.84
Length Wtd. (ft)	49.00	Shear (lb/sq ft)	0.89	1.77	0.87
Min Ch El (ft)	2691.81	Stream Power (lb/ft s)	5.38	31.28	5.17
Alpha	1.66	Cum Volume (acre-ft)	0.07	3.26	0.07
Frctn Loss (ft)	0.26	Cum SA (acres)	0.02	0.26	0.02
C & E Loss (ft)	0.37				

Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.

Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1 RS: 1098

INPUT

Description:

Station	Elevation	Data	num=	6	Sta	Elev	Sta	Elev	Sta	Elev
0	2715	36	2697	36	2688.22	50	2688.22	50	2697	
86	2715									

Manning's n	Values	num=	3	Sta	n Val	Sta	n Val
0	.037	36	.02	50	.037		

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
36	50	44	44	44	.1	.3	

CROSS SECTION OUTPUT Profile #PF 1

		Element	Left OB	Channel	Right OB
E.G. Elev (ft)	2709.15	Wt. n-Val.	0.037	0.020	0.037
Vel Head (ft)	7.55	Reach Len. (ft)	44.00	44.00	44.00
W.S. Elev (ft)	2701.60	Flow Area (sq ft)	21.13	187.28	21.13
Crit W.S. (ft)	2703.89	Area (sq ft)	21.13	187.28	21.13
E.G. Slope (ft/ft)	0.008650	Flow (cfs)	127.63	4241.74	127.63
Q Total (cfs)	4497.00	Top Width (ft)	9.19	14.00	9.19
Top Width (ft)	32.39	Avg. Vel. (ft/s)	6.04	22.65	6.04
Vel Total (ft/s)	19.59	Hydr. Depth (ft)	2.30	13.38	2.30
Max Chl Dpth (ft)	13.38	Conv. (cfs)	1372.3	45606.7	1372.3
Conv. Total (cfs)	48351.3	Wetted Per. (ft)	10.28	31.56	10.28
Length Wtd. (ft)	44.00	Shear (lb/sq ft)	1.11	3.20	1.11
Min Ch El (ft)	2688.22	Stream Power (lb/ft s)	6.71	72.58	6.71
Alpha	1.27	Cum Volume (acre-ft)	0.01	3.04	0.01
Frctn Loss (ft)	0.53	Cum SA (acres)	0.00	0.25	0.00
C & E Loss (ft)	0.38				

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.

Note: Program found supercritical flow starting at this cross section.

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1 RS: 1000

INPUT

Description:

Station	Elevation	Data	num=	4	Sta	Elev	Sta	Elev
0	2697	0	2685	14	2685	14	2697	

Manning's n	Values	num=	3	Sta	n Val	Sta	n Val
0	.02	0	.02	14	.02		

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.

InterimCollector.rep
0 14 38.48 38.48 38.48 .01 .03

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2708.23	Element	Left OB	Channel	Right OB
Vel Head (ft)	11.34	Wt. n-Val.		0.020	
W.S. Elev (ft)	2696.89	Reach Len. (ft)	38.48	38.48	38.48
Crit W.S. (ft)	2699.71	Flow Area (sq ft)		166.44	
E.G. Slope (ft/ft)	0.018310	Area (sq ft)		166.44	
Q Total (cfs)	4497.00	Flow (cfs)		4497.00	
Top Width (ft)	14.00	Top Width (ft)		14.00	
Vel Total (ft/s)	27.02	Avg. Vel. (ft/s)		27.02	
Max Chl Dpth (ft)	11.89	Hydr. Depth (ft)		11.89	
Conv. Total (cfs)	33233.8	Conv. (cfs)		33233.8	
Length Wtd. (ft)	38.48	Wetted Per. (ft)		37.78	
Min Ch El (ft)	2685.00	Shear (lb/sq ft)		5.04	
Alpha	1.00	Stream Power (lb/ft s)		136.07	
Frctn Loss (ft)	0.61	Cum Volume (acre-ft)		2.87	
C & E Loss (ft)	0.02	Cum SA (acres)		0.24	

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1 RS: 966.67*

INPUT

Description:

Station Elevation Data	num=	4
Sta Elev Sta Elev Sta Elev		
0 2696.61 0 2684.61 14 2684.61 14 2696.61		

Manning's n Values	num=	2
Sta n Val Sta n Val		
0 .018 14 .018		

Bank Sta: Left Right	Lengths: Left Channel Right	Coeff Contr.	Expan.
0 14	38.48 38.48 38.48	.01	.03

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2707.61	Element	Left OB	Channel	Right OB
Vel Head (ft)	10.83	Wt. n-Val.		0.018	
W.S. Elev (ft)	2696.78	Reach Len. (ft)	38.48	38.48	38.48
Crit W.S. (ft)	2699.32	Flow Area (sq ft)		170.31	
E.G. Slope (ft/ft)	0.014006	Area (sq ft)		170.31	
Q Total (cfs)	4497.00	Flow (cfs)		4497.00	
Top Width (ft)	14.00	Top Width (ft)		14.00	
Vel Total (ft/s)	26.40	Avg. Vel. (ft/s)		26.40	
Max Chl Dpth (ft)	12.17	Hydr. Depth (ft)		12.17	
Conv. Total (cfs)	37998.4	Conv. (cfs)		37998.4	
Length Wtd. (ft)	38.48	Wetted Per. (ft)		38.33	
Min Ch El (ft)	2684.61	Shear (lb/sq ft)		3.89	
Alpha	1.00	Stream Power (lb/ft s)		102.59	
Frctn Loss (ft)	0.50	Cum Volume (acre-ft)		2.72	
C & E Loss (ft)	0.01	Cum SA (acres)		0.22	

Warning: The cross-section end points had to be extended vertically for the computed water surface.

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1 RS: 933.33*

INPUT

Description:

Station Elevation Data	num=	4
Sta Elev Sta Elev Sta Elev		
0 2696.23 0 2684.23 14 2684.23 14 2696.23		

Manning's n Values	num=	2
Sta n Val Sta n Val		
0 .017 14 .017		

Bank Sta: Left Right	Lengths: Left Channel Right	Coeff Contr.	Expan.
0 14	38.48 38.48 38.48	.01	.03

CROSS SECTION OUTPUT Profile #PF 1

			InterimCollector.rep		
		Element	Left OB	Channel	Right OB
E.G. Elev (ft)	2707.10	Wt. n-Val.		0.017	
Vel Head (ft)	10.54	Reach Len. (ft)	38.48	38.48	38.48
W.S. Elev (ft)	2696.57	Flow Area (sq ft)		172.69	
Crit W.S. (ft)	2698.94	Area (sq ft)		172.69	
E.G. Slope (ft/ft)	0.012070	Flow (cfs)		4497.00	
Q Total (cfs)	4497.00	Top Width (ft)		14.00	
Top Width (ft)	14.00	Avg. Vel. (ft/s)		26.04	
Vel Total (ft/s)	26.04	Hydr. Depth (ft)		12.33	
Max Chl Dpth (ft)	12.33	Conv. (cfs)		40933.0	
Conv. Total (cfs)	40933.0	Wetted Per. (ft)		38.67	
Length Wtd. (ft)	38.48	Shear (lb/sq ft)		3.36	
Min Ch El (ft)	2684.23	Stream Power (lb/ft s)		87.63	
Alpha	1.00	Cum Volume (acre-ft)		2.56	
Frctn Loss (ft)	0.41	Cum SA (acres)		0.21	
C & E Loss (ft)	0.00				

Warning: The cross-section end points had to be extended vertically for the computed water surface.

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1 RS: 900

INPUT

Description:

Station Elevation Data	num=	4		
Sta Elev	Sta Elev	Sta Elev	Sta Elev	
0 2695.84	0 2683.84	14 2683.84	14 2695.84	

Manning's n Values	num=	3		
Sta n Val	Sta n Val	Sta n Val		
0 .015	0 .015	14 .015		

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
0	14	47.39	47.39	.01	.03

CROSS SECTION OUTPUT Profile #PF 1

		Element	Left OB	Channel	Right OB
E.G. Elev (ft)	2706.70	Wt. n-Val.		0.015	
Vel Head (ft)	10.50	Reach Len. (ft)	47.39	47.39	47.39
W.S. Elev (ft)	2696.20	Flow Area (sq ft)		173.01	
Crit W.S. (ft)	2698.55	Area (sq ft)		173.01	
E.G. Slope (ft/ft)	0.009354	Flow (cfs)		4497.00	
Q Total (cfs)	4497.00	Top Width (ft)		14.00	
Top Width (ft)	14.00	Avg. Vel. (ft/s)		25.99	
Vel Total (ft/s)	25.99	Hydr. Depth (ft)		12.36	
Max Chl Dpth (ft)	12.36	Conv. (cfs)		46496.8	
Conv. Total (cfs)	46496.8	Wetted Per. (ft)		38.72	
Length Wtd. (ft)	47.39	Shear (lb/sq ft)		2.61	
Min Ch El (ft)	2683.84	Stream Power (lb/ft s)		67.83	
Alpha	1.00	Cum Volume (acre-ft)		2.41	
Frctn Loss (ft)	0.44	Cum SA (acres)		0.20	
C & E Loss (ft)	0.00				

Warning: The cross-section end points had to be extended vertically for the computed water surface.

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1 RS: 892.31*

INPUT

Description:

Station Elevation Data	num=	4		
Sta Elev	Sta Elev	Sta Elev	Sta Elev	
0 2695.37	0 2683.37	14 2683.37	14 2695.37	

Manning's n Values	num=	2		
Sta n Val	Sta n Val			
0 .015	14 .015			

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
0	14	47.39	47.39	.01	.03

CROSS SECTION OUTPUT Profile #PF 1

		Element	Left OB	Channel	Right OB
E.G. Elev (ft)	2706.26	Wt. n-Val.		0.015	
Vel Head (ft)	10.56	Reach Len. (ft)	47.39	47.39	47.39
W.S. Elev (ft)	2695.69	Flow Area (sq ft)		172.47	
Crit W.S. (ft)	2698.08	Area (sq ft)		172.47	
E.G. Slope (ft/ft)	0.009426	Flow (cfs)		4497.00	
Q Total (cfs)	4497.00	Top Width (ft)		14.00	
Top Width (ft)	14.00	Avg. Vel. (ft/s)		26.07	
Vel Total (ft/s)	26.07	Hydr. Depth (ft)		12.32	
Max Chl Dpth (ft)	12.32				

Conv. Total (cfs)	46319.0	Conv. (cfs)	46319.0
Length Wtd. (ft)	47.39	Wetted Per. (ft)	38.64
Min Ch El (ft)	2683.37	Shear (lb/sq ft)	2.63
Alpha	1.00	Stream Power (lb/ft s)	68.49
Frctn Loss (ft)	0.45	Cum Volume (acre-ft)	2.22
C & E Loss (ft)	0.00	Cum SA (acres)	0.18

Warning: The cross-section end points had to be extended vertically for the computed water surface.

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1 RS: 884.62*

INPUT

Description:

Station	Elevation	Data	num=	4
Sta	Elev	Sta	Elev	Sta
0	2694.89	0	2682.89	14
				14
				2694.89

Manning's n Values	num=	2
Sta	n Val	Sta
0	.015	14
		.015

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	0	14		47.39	47.39	47.39		.01	.03

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2705.81	Element	Left OB	Channel	Right OB
Vel Head (ft)	10.65	Wt. n-Val.		0.015	
W.S. Elev (ft)	2695.16	Reach Len. (ft)	47.39	47.39	47.39
Crit W.S. (ft)	2697.60	Flow Area (sq ft)		171.78	
E.G. Slope (ft/ft)	0.009520	Area (sq ft)		171.78	
Q Total (cfs)	4497.00	Flow (cfs)		4497.00	
Top Width (ft)	14.00	Top Width (ft)		14.00	
Vel Total (ft/s)	26.18	Avg. Vel. (ft/s)		26.18	
Max Chl Dpth (ft)	12.27	Hydr. Depth (ft)		12.27	
Conv. Total (cfs)	46088.8	Conv. (cfs)		46088.8	
Length Wtd. (ft)	47.39	Wetted Per. (ft)		38.54	
Min Ch El (ft)	2682.89	Shear (lb/sq ft)		2.65	
Alpha	1.00	Stream Power (lb/ft s)		69.35	
Frctn Loss (ft)	0.45	Cum Volume (acre-ft)		2.04	
C & E Loss (ft)	0.00	Cum SA (acres)		0.17	

Warning: The cross-section end points had to be extended vertically for the computed water surface.

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1 RS: 876.92*

INPUT

Description:

Station	Elevation	Data	num=	4
Sta	Elev	Sta	Elev	Sta
0	2694.42	0	2682.42	14
				14
				2694.42

Manning's n Values	num=	2
Sta	n Val	Sta
0	.015	14
		.015

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	0	14		47.39	47.39	47.39		.01	.03

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2705.36	Element	Left OB	Channel	Right OB
Vel Head (ft)	10.70	Wt. n-Val.		0.015	
W.S. Elev (ft)	2694.66	Reach Len. (ft)	47.39	47.39	47.39
Crit W.S. (ft)	2697.13	Flow Area (sq ft)		171.42	
E.G. Slope (ft/ft)	0.009571	Area (sq ft)		171.42	
Q Total (cfs)	4497.00	Flow (cfs)		4497.00	
Top Width (ft)	14.00	Top Width (ft)		14.00	
Vel Total (ft/s)	26.23	Avg. Vel. (ft/s)		26.23	
Max Chl Dpth (ft)	12.24	Hydr. Depth (ft)		12.24	
Conv. Total (cfs)	45967.0	Conv. (cfs)		45967.0	
Length Wtd. (ft)	47.39	Wetted Per. (ft)		38.49	
Min Ch El (ft)	2682.42	Shear (lb/sq ft)		2.66	
Alpha	1.00	Stream Power (lb/ft s)		69.81	
Frctn Loss (ft)	0.46	Cum Volume (acre-ft)		1.85	
C & E Loss (ft)	0.00	Cum SA (acres)		0.15	

Warning: The cross-section end points had to be extended vertically for the computed water surface.

CROSS SECTION

RIVER: FEMA Wash
 REACH: MAIN1

RS: 869.23*

INPUT

Description:

Station Elevation Data		num=	4
Sta	Elev	Sta	Elev
0	2693.94	0	2681.94
14	2681.94	14	2693.94

Manning's n Values		num=	2
Sta	n Val	Sta	n Val
0	.015	14	.015

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	0	14		47.39	47.39	.01	.03

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2704.91	Element	Left OB	Channel	Right OB
Vel Head (ft)	10.76	Wt. n-Val.		0.015	
W.S. Elev (ft)	2694.15	Reach Len. (ft)	47.39	47.39	47.39
Crit W.S. (ft)	2696.65	Flow Area (sq ft)		170.91	
E.G. Slope (ft/ft)	0.009641	Area (sq ft)		170.91	
Q Total (cfs)	4497.00	Flow (cfs)		4497.00	
Top Width (ft)	14.00	Top Width (ft)		14.00	
Vel Total (ft/s)	26.31	Avg. Vel. (ft/s)		26.31	
Max Chl Dpth (ft)	12.21	Hydr. Depth (ft)		12.21	
Conv. Total (cfs)	45798.4	Conv. (cfs)		45798.4	
Length Wtd. (ft)	47.39	Wetted Per. (ft)		38.42	
Min Ch El (ft)	2681.94	Shear (lb/sq ft)		2.68	
Alpha	1.00	Stream Power (lb/ft s)		70.46	
Frctn Loss (ft)	0.46	Cum Volume (acre-ft)		1.66	
C & E Loss (ft)	0.00	Cum SA (acres)		0.14	

Warning: The cross-section end points had to be extended vertically for the computed water surface.

CROSS SECTION

RIVER: FEMA Wash
 REACH: MAIN1

RS: 861.54*

INPUT

Description:

Station Elevation Data		num=	4
Sta	Elev	Sta	Elev
0	2693.47	0	2681.47
14	2681.47	14	2693.47

Manning's n Values		num=	2
Sta	n Val	Sta	n Val
0	.015	14	.015

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	0	14		47.39	47.39	.01	.03

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2704.45	Element	Left OB	Channel	Right OB
Vel Head (ft)	10.79	Wt. n-Val.		0.015	
W.S. Elev (ft)	2693.66	Reach Len. (ft)	47.39	47.39	47.39
Crit W.S. (ft)	2696.18	Flow Area (sq ft)		170.67	
E.G. Slope (ft/ft)	0.009675	Area (sq ft)		170.67	
Q Total (cfs)	4497.00	Flow (cfs)		4497.00	
Top Width (ft)	14.00	Top Width (ft)		14.00	
Vel Total (ft/s)	26.35	Avg. Vel. (ft/s)		26.35	
Max Chl Dpth (ft)	12.19	Hydr. Depth (ft)		12.19	
Conv. Total (cfs)	45718.8	Conv. (cfs)		45718.8	
Length Wtd. (ft)	47.39	Wetted Per. (ft)		38.38	
Min Ch El (ft)	2681.47	Shear (lb/sq ft)		2.69	
Alpha	1.00	Stream Power (lb/ft s)		70.77	
Frctn Loss (ft)	0.46	Cum Volume (acre-ft)		1.48	
C & E Loss (ft)	0.00	Cum SA (acres)		0.12	

Warning: The cross-section end points had to be extended vertically for the computed water surface.

CROSS SECTION

RIVER: FEMA Wash
 REACH: MAIN1

RS: 853.85*

INPUT

Description:

Station	Elevation	Data	num=	4				
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	
0	2693	0	2681	14	2681	14	2693	

Manning's n	Values	num=	2
Sta	n Val	Sta	n Val
0	.015	14	.015

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	0	14		47.39	47.39		.01	.03

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2703.99	Element	Left OB	Channel	Right OB
Vel Head (ft)	10.82	Wt. n-Val.		0.015	
W.S. Elev (ft)	2693.18	Reach Len. (ft)	47.39	47.39	47.39
Crit W.S. (ft)	2695.71	Flow Area (sq ft)		170.44	
E.G. Slope (ft/ft)	0.009707	Area (sq ft)		170.44	
Q Total (cfs)	4497.00	Flow (cfs)		4497.00	
Top Width (ft)	14.00	Top Width (ft)		14.00	
Vel Total (ft/s)	26.38	Avg. Vel. (ft/s)		26.38	
Max Chl Dpth (ft)	12.17	Hydr. Depth (ft)		12.17	
Conv. Total (cfs)	45642.5	Conv. (cfs)		45642.5	
Length Wtd. (ft)	47.39	Wetted Per. (ft)		38.35	
Min Ch El (ft)	2681.00	Shear (lb/sq ft)		2.69	
Alpha	1.00	Stream Power (lb/ft s)		71.07	
Frctn Loss (ft)	0.46	Cum Volume (acre-ft)		1.29	
C & E Loss (ft)	0.00	Cum SA (acres)		0.11	

Warning: The cross-section end points had to be extended vertically for the computed water surface.

CROSS SECTION

RIVER: FEMA Wash
 REACH: MAIN1 RS: 846.15*

INPUT

Description:

Station	Elevation	Data	num=	4				
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	
0	2692.52	0	2680.52	14	2680.52	14	2692.52	

Manning's n	Values	num=	2
Sta	n Val	Sta	n Val
0	.015	14	.015

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	0	14		47.39	47.39		.01	.03

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2703.53	Element	Left OB	Channel	Right OB
Vel Head (ft)	10.86	Wt. n-Val.		0.015	
W.S. Elev (ft)	2692.67	Reach Len. (ft)	47.39	47.39	47.39
Crit W.S. (ft)	2695.23	Flow Area (sq ft)		170.08	
E.G. Slope (ft/ft)	0.009759	Area (sq ft)		170.08	
Q Total (cfs)	4497.00	Flow (cfs)		4497.00	
Top Width (ft)	14.00	Top Width (ft)		14.00	
Vel Total (ft/s)	26.44	Avg. Vel. (ft/s)		26.44	
Max Chl Dpth (ft)	12.15	Hydr. Depth (ft)		12.15	
Conv. Total (cfs)	45520.8	Conv. (cfs)		45520.8	
Length Wtd. (ft)	47.39	Wetted Per. (ft)		38.30	
Min Ch El (ft)	2680.52	Shear (lb/sq ft)		2.71	
Alpha	1.00	Stream Power (lb/ft s)		71.55	
Frctn Loss (ft)	0.46	Cum Volume (acre-ft)		1.11	
C & E Loss (ft)	0.00	Cum SA (acres)		0.09	

Warning: The cross-section end points had to be extended vertically for the computed water surface.

CROSS SECTION

RIVER: FEMA Wash
 REACH: MAIN1 RS: 838.46*

INPUT

Description:

Station	Elevation	Data	num=	4				
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	
0	2692.05	0	2680.05	14	2680.05	14	2692.05	

Manning's n	Values	num=	2
Sta	n Val	Sta	n Val
0	.015	14	.015

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.

InterimCollector.rep
.01 .03

0 14 47.39 47.39 47.39

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2703.07	Element	Left OB	Channel	Right OB
Vel Head (ft)	10.88	Wt. n-Val.		0.015	
W.S. Elev (ft)	2692.19	Reach Len. (ft)	47.39	47.39	47.39
Crit W.S. (ft)	2694.76	Flow Area (sq ft)		169.94	
E.G. Slope (ft/ft)	0.009779	Area (sq ft)		169.94	
Q Total (cfs)	4497.00	Flow (cfs)		4497.00	
Top Width (ft)	14.00	Top Width (ft)		14.00	
Vel Total (ft/s)	26.46	Avg. Vel. (ft/s)		26.46	
Max Chl Dpth (ft)	12.14	Hydr. Depth (ft)		12.14	
Conv. Total (cfs)	45476.4	Conv. (cfs)		45476.4	
Length Wtd. (ft)	47.39	Wetted Per. (ft)		38.28	
Min Ch El (ft)	2680.05	Shear (lb/sq ft)		2.71	
Alpha	1.00	Stream Power (lb/ft s)		71.72	
Frctn Loss (ft)	0.46	Cum Volume (acre-ft)		0.92	
C & E Loss (ft)	0.00	Cum SA (acres)		0.08	

Warning: The cross-section end points had to be extended vertically for the computed water surface.

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1 RS: 830.77*

INPUT
Description:
Station Elevation Data num= 4

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	2691.58	0	2679.58	14	2679.58	14	2691.58

Manning's n Values num= 2

Sta	n Val	Sta	n Val
0	.015	14	.015

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
0 14 47.39 47.39 47.39 .01 .03

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2702.61	Element	Left OB	Channel	Right OB
Vel Head (ft)	10.90	Wt. n-Val.		0.015	
W.S. Elev (ft)	2691.71	Reach Len. (ft)	47.39	47.39	47.39
Crit W.S. (ft)	2694.29	Flow Area (sq ft)		169.84	
E.G. Slope (ft/ft)	0.009794	Area (sq ft)		169.84	
Q Total (cfs)	4497.00	Flow (cfs)		4497.00	
Top Width (ft)	14.00	Top Width (ft)		14.00	
Vel Total (ft/s)	26.48	Avg. Vel. (ft/s)		26.48	
Max Chl Dpth (ft)	12.13	Hydr. Depth (ft)		12.13	
Conv. Total (cfs)	45440.0	Conv. (cfs)		45440.0	
Length Wtd. (ft)	47.39	Wetted Per. (ft)		38.26	
Min Ch El (ft)	2679.58	Shear (lb/sq ft)		2.71	
Alpha	1.00	Stream Power (lb/ft s)		71.86	
Frctn Loss (ft)	0.47	Cum Volume (acre-ft)		0.74	
C & E Loss (ft)	0.00	Cum SA (acres)		0.06	

Warning: The cross-section end points had to be extended vertically for the computed water surface.

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1 RS: 823.08*

INPUT
Description:
Station Elevation Data num= 4

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	2691.1	0	2679.1	14	2679.1	14	2691.1

Manning's n Values num= 2

Sta	n Val	Sta	n Val
0	.015	14	.015

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
0 14 47.39 47.39 47.39 .01 .03

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2702.14	Element	Left OB	Channel	Right OB
Vel Head (ft)	10.93	Wt. n-Val.		0.015	
W.S. Elev (ft)	2691.21	Reach Len. (ft)	47.39	47.39	47.39
Crit W.S. (ft)	2693.81	Flow Area (sq ft)		169.55	
E.G. Slope (ft/ft)	0.009836	Area (sq ft)		169.55	

Page 13

				InterimCollector.rep			
Q Total (cfs)	4497.00	Flow (cfs)		4497.00			
Top Width (ft)	14.00	Top Width (ft)		14.00			
Vel Total (ft/s)	26.52	Avg. Vel. (ft/s)		26.52			
Max Chl Dpth (ft)	12.11	Hydr. Depth (ft)		12.11			
Conv. Total (cfs)	45344.4	Conv. (cfs)		45344.4			
Length Wtd. (ft)	47.39	Wetted Per. (ft)		38.22			
Min Ch El (ft)	2679.10	Shear (lb/sq ft)		2.72			
Alpha	1.00	Stream Power (lb/ft s)		72.25			
Frctn Loss (ft)	0.47	Cum Volume (acre-ft)		0.55			
C & E Loss (ft)	0.00	Cum SA (acres)		0.05			

Warning: The cross-section end points had to be extended vertically for the computed water surface.

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1 RS: 815.38*

INPUT

Description:

Station	Elevation	Data	num=	4			
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	2690.63	0	2678.63	14	2678.63	14	2690.63

Manning's n Values	num=	2
Sta	n Val	Sta
0	.015	14

Bank Sta: Left	Right	Lengths: Left	Channel	Right	Coeff	Contr.	Expan.
0	14	47.39	47.39	47.39	.01	.03	

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2701.67	Element	Left OB	Channel	Right OB
Vel Head (ft)	10.92	Wt. n-Val.		0.015	
W.S. Elev (ft)	2690.75	Reach Len. (ft)	47.39	47.39	47.39
Crit W.S. (ft)	2693.34	Flow Area (sq ft)		169.62	
E.G. Slope (ft/ft)	0.009825	Area (sq ft)		169.62	
Q Total (cfs)	4497.00	Flow (cfs)		4497.00	
Top Width (ft)	14.00	Top Width (ft)		14.00	
Vel Total (ft/s)	26.51	Avg. Vel. (ft/s)		26.51	
Max Chl Dpth (ft)	12.12	Hydr. Depth (ft)		12.12	
Conv. Total (cfs)	45368.3	Conv. (cfs)		45368.3	
Length Wtd. (ft)	47.39	Wetted Per. (ft)		38.23	
Min Ch El (ft)	2678.63	Shear (lb/sq ft)		2.72	
Alpha	1.00	Stream Power (lb/ft s)		72.15	
Frctn Loss (ft)	0.47	Cum Volume (acre-ft)		0.37	
C & E Loss (ft)	0.00	Cum SA (acres)		0.03	

Warning: The cross-section end points had to be extended vertically for the computed water surface.

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1 RS: 807.69*

INPUT

Description:

Station	Elevation	Data	num=	4			
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	2690.15	0	2678.15	14	2678.15	14	2690.15

Manning's n Values	num=	2
Sta	n Val	Sta
0	.015	14

Bank Sta: Left	Right	Lengths: Left	Channel	Right	Coeff	Contr.	Expan.
0	14	47.39	47.39	47.39	.01	.03	

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2701.20	Element	Left OB	Channel	Right OB
Vel Head (ft)	10.96	Wt. n-Val.		0.015	
W.S. Elev (ft)	2690.25	Reach Len. (ft)	47.39	47.39	47.39
Crit W.S. (ft)	2692.86	Flow Area (sq ft)		169.37	
E.G. Slope (ft/ft)	0.009861	Area (sq ft)		169.37	
Q Total (cfs)	4497.00	Flow (cfs)		4497.00	
Top Width (ft)	14.00	Top Width (ft)		14.00	
Vel Total (ft/s)	26.55	Avg. Vel. (ft/s)		26.55	
Max Chl Dpth (ft)	12.10	Hydr. Depth (ft)		12.10	
Conv. Total (cfs)	45285.3	Conv. (cfs)		45285.3	
Length Wtd. (ft)	47.39	Wetted Per. (ft)		38.20	
Min Ch El (ft)	2678.15	Shear (lb/sq ft)		2.73	
Alpha	1.00	Stream Power (lb/ft s)		72.48	
Frctn Loss (ft)	0.47	Cum Volume (acre-ft)		0.18	

Page 14

C & E Loss (ft) 0.00 Cum SA (acres) InterimCollector.rep 0.02

Warning: The cross-section end points had to be extended vertically for the computed water surface.

CROSS SECTION

RIVER: FEMA Wash
REACH: MAIN1 RS: 800

INPUT

Description:

Station	Elevation	Data	num=	4			
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	2689.68	0	2677.68	14	2677.68	14	2689.68

Manning's n Values		num=	3		
Sta	n Val	Sta	n Val	Sta	n Val
0	.015	0	.015	14	.015

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	0	14		0	0		.01	.03

CROSS SECTION OUTPUT Profile #PF 1

E.G. Elev (ft)	2700.73	Element	Left OB	Channel	Right OB
Vel Head (ft)	10.95	Wt. n-Val.		0.015	
W.S. Elev (ft)	2689.78	Reach Len. (ft)			
Crit W.S. (ft)	2692.39	Flow Area (sq ft)		169.42	
E.G. Slope (ft/ft)	0.009854	Area (sq ft)		169.42	
Q Total (cfs)	4497.00	Flow (cfs)		4497.00	
Top Width (ft)	14.00	Top Width (ft)		14.00	
Vel Total (ft/s)	26.54	Avg. Vel. (ft/s)		26.54	
Max Chl Dpth (ft)	12.10	Hydr. Depth (ft)		12.10	
Conv. Total (cfs)	45301.2	Conv. (cfs)		45301.2	
Length Wtd. (ft)		Wetted Per. (ft)		38.20	
Min Ch El (ft)	2677.68	Shear (lb/sq ft)		2.73	
Alpha	1.00	Stream Power (lb/ft s)		72.42	
Frctn Loss (ft)		Cum Volume (acre-ft)			
C & E Loss (ft)		Cum SA (acres)			

Warning: The cross-section end points had to be extended vertically for the computed water surface.

SUMMARY OF MANNING'S N VALUES

River:FEMA Wash

Reach	River Sta.	n1	n2	n3
MAIN1	1400	.035	.035	.035
MAIN1	1383.33*	.035	.035	
MAIN1	1366.67*	.035	.035	
MAIN1	1350.00*	.035	.035	
MAIN1	1333.33*	.035	.035	
MAIN1	1316.67*	.035	.035	
MAIN1	1300	.035	.035	.035
MAIN1	1299	.037	.037	.037
MAIN1	1199.50*	.037	.037	
MAIN1	1100	.037	.037	.037
MAIN1	1099	.037	.02	.037
MAIN1	1098	.037	.02	.037
MAIN1	1000	.02	.02	.02
MAIN1	966.67*	.018	.018	
MAIN1	933.33*	.017	.017	
MAIN1	900	.015	.015	.015
MAIN1	892.31*	.015	.015	
MAIN1	884.62*	.015	.015	
MAIN1	876.92*	.015	.015	
MAIN1	869.23*	.015	.015	
MAIN1	861.54*	.015	.015	
MAIN1	853.85*	.015	.015	
MAIN1	846.15*	.015	.015	
MAIN1	838.46*	.015	.015	
MAIN1	830.77*	.015	.015	
MAIN1	823.08*	.015	.015	
MAIN1	815.38*	.015	.015	
MAIN1	807.69*	.015	.015	
MAIN1	800	.015	.015	.015

SUMMARY OF REACH LENGTHS

River: FEMA Wash

Reach	River Sta.	Left	Channel	Right
MAIN1	1400	47.29	44.84	43.76
MAIN1	1383.33*	47.29	44.84	43.76
MAIN1	1366.67*	47.29	44.84	43.76
MAIN1	1350.00*	47.29	44.84	43.76
MAIN1	1333.33*	47.29	44.84	43.76
MAIN1	1316.67*	47.29	44.84	43.76
MAIN1	1300	.1	.1	.1
MAIN1	1299	49.33	33.5	28.05
MAIN1	1199.50*	49.33	33.5	28.05
MAIN1	1100	38.24	30	60
MAIN1	1099	49	49	49
MAIN1	1098	44	44	44
MAIN1	1000	38.48	38.48	38.48
MAIN1	966.67*	38.48	38.48	38.48
MAIN1	933.33*	38.48	38.48	38.48
MAIN1	900	47.39	47.39	47.39
MAIN1	892.31*	47.39	47.39	47.39
MAIN1	884.62*	47.39	47.39	47.39
MAIN1	876.92*	47.39	47.39	47.39
MAIN1	869.23*	47.39	47.39	47.39
MAIN1	861.54*	47.39	47.39	47.39
MAIN1	853.85*	47.39	47.39	47.39
MAIN1	846.15*	47.39	47.39	47.39
MAIN1	838.46*	47.39	47.39	47.39
MAIN1	830.77*	47.39	47.39	47.39
MAIN1	823.08*	47.39	47.39	47.39
MAIN1	815.38*	47.39	47.39	47.39
MAIN1	807.69*	47.39	47.39	47.39
MAIN1	800	0	0	0

SUMMARY OF CONTRACTION AND EXPANSION COEFFICIENTS
River: FEMA Wash

Reach	River Sta.	Contr.	Expan.
MAIN1	1400	.1	.3
MAIN1	1383.33*	.1	.3
MAIN1	1366.67*	.1	.3
MAIN1	1350.00*	.1	.3
MAIN1	1333.33*	.1	.3
MAIN1	1316.67*	.1	.3
MAIN1	1300	.1	.3
MAIN1	1299	.1	.3
MAIN1	1199.50*	.1	.3
MAIN1	1100	.1	.3
MAIN1	1099	.1	.3
MAIN1	1098	.1	.3
MAIN1	1000	.01	.03
MAIN1	966.67*	.01	.03
MAIN1	933.33*	.01	.03
MAIN1	900	.01	.03
MAIN1	892.31*	.01	.03
MAIN1	884.62*	.01	.03
MAIN1	876.92*	.01	.03
MAIN1	869.23*	.01	.03
MAIN1	861.54*	.01	.03
MAIN1	853.85*	.01	.03
MAIN1	846.15*	.01	.03
MAIN1	838.46*	.01	.03
MAIN1	830.77*	.01	.03
MAIN1	823.08*	.01	.03
MAIN1	815.38*	.01	.03
MAIN1	807.69*	.01	.03
MAIN1	800	.01	.03

ERRORS WARNINGS AND NOTES

Errors Warnings and Notes for Plan : PLAN02

River: FEMA Wash Reach: MAIN1 RS: 1400 Profile: PF 1

Warning:Slope too shallow for slope area to converge during supercritical flow calculations (normal depth is above critical depth). Water surface set to critical depth.

River: FEMA Wash Reach: MAIN1 RS: 1383.33* Profile: PF 1

Warning:The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections. Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

Warning:The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.

River: FEMA Wash Reach: MAIN1 RS: 1366.67* Profile: PF 1

Warning:The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate

the need for additional cross sections.

River: FEMA Wash Reach: MAIN1 RS: 1350.00* Profile: PF 1
 Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.
 This may indicate the need for additional cross sections.
 Note: Hydraulic jump has occurred between this cross section and the previous upstream section.

River: FEMA Wash Reach: MAIN1 RS: 1100 Profile: PF 1
 Warning:The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
 Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.
 This may indicate the need for additional cross sections.

River: FEMA Wash Reach: MAIN1 RS: 1099 Profile: PF 1
 Warning:The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.
 Warning:The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
 Warning:The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.
 Warning:During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

River: FEMA Wash Reach: MAIN1 RS: 1098 Profile: PF 1
 Warning:The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
 Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.
 This may indicate the need for additional cross sections.
 Note: Program found supercritical flow starting at this cross section.

River: FEMA Wash Reach: MAIN1 RS: 1000 Profile: PF 1
 Warning:The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
 Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.
 This may indicate the need for additional cross sections.

River: FEMA Wash Reach: MAIN1 RS: 966.67* Profile: PF 1
 Warning:The cross-section end points had to be extended vertically for the computed water surface.
 Warning:The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

River: FEMA Wash Reach: MAIN1 RS: 933.33* Profile: PF 1
 Warning:The cross-section end points had to be extended vertically for the computed water surface.

River: FEMA Wash Reach: MAIN1 RS: 900 Profile: PF 1
 Warning:The cross-section end points had to be extended vertically for the computed water surface.

River: FEMA Wash Reach: MAIN1 RS: 892.31* Profile: PF 1
 Warning:The cross-section end points had to be extended vertically for the computed water surface.

River: FEMA Wash Reach: MAIN1 RS: 884.62* Profile: PF 1
 Warning:The cross-section end points had to be extended vertically for the computed water surface.

River: FEMA Wash Reach: MAIN1 RS: 876.92* Profile: PF 1
 Warning:The cross-section end points had to be extended vertically for the computed water surface.

River: FEMA Wash Reach: MAIN1 RS: 869.23* Profile: PF 1
 Warning:The cross-section end points had to be extended vertically for the computed water surface.

River: FEMA Wash Reach: MAIN1 RS: 861.54* Profile: PF 1
 Warning:The cross-section end points had to be extended vertically for the computed water surface.

River: FEMA Wash Reach: MAIN1 RS: 853.85* Profile: PF 1
 Warning:The cross-section end points had to be extended vertically for the computed water surface.

River: FEMA Wash Reach: MAIN1 RS: 846.15* Profile: PF 1
 Warning:The cross-section end points had to be extended vertically for the computed water surface.

River: FEMA Wash Reach: MAIN1 RS: 838.46* Profile: PF 1
 Warning:The cross-section end points had to be extended vertically for the computed water surface.

River: FEMA Wash Reach: MAIN1 RS: 830.77* Profile: PF 1
 Warning:The cross-section end points had to be extended vertically for the computed water surface.

River: FEMA Wash Reach: MAIN1 RS: 823.08* Profile: PF 1
 Warning:The cross-section end points had to be extended vertically for the computed water surface.


River: FEMA Wash Reach: MAIN1 RS: 815.38* Profile: PF 1
 Warning:The cross-section end points had to be extended vertically for the computed water surface.

River: FEMA Wash Reach: MAIN1 RS: 807.69* Profile: PF 1
 Warning:The cross-section end points had to be extended vertically for the computed water surface.

River: FEMA Wash Reach: MAIN1 RS: 800 Profile: PF 1
 Warning:The cross-section end points had to be extended vertically for the computed water surface.

APPENDIX C

Drainage Exhibits



APPENDIX D

Additional Documents and Reference Material

December 28, 2017



Mr. John Alabado and Ms. Linda Maynard
City Planning and Development
City of Las Vegas
333 North Rancho Drive
Las Vegas, NV 89106

RE: 17.49-Acre Parcel (APNs 138-32-301-005 and a portion of 138-32-301-007))
GCW Project # 840-050

Dear Mr. Alabado and Ms. Maynard:

GCW, Inc. is currently preparing mass grading plans and flood control facilities (storm drain boxes and pipe) for the 17.49-acre parcel zoned for 435 condominium units adjacent to Alta Drive and Rampart Boulevard. We have submitted and received comments to the Technical Drainage Study (DS4787A.ZNA.doc); Comment #3 to the Technical Drainage Study referenced the need for an approval of the grade differential relative to our site and the properties adjacent to the perimeter of the 70-acre proposed mass grading site.

The project is bounded by existing and proposed multi-family development (PD) to the north; Alta Drive to the northeast; Rampart Boulevard and C-1 commercial development to the south and east; and an undeveloped portion of the old golf course with an R-PD7 use, owned by Seventy Acres LLC, to the southwest. The site is presently developed as a golf course with washes and gentle to steep ridges throughout the site. The elevation differential from the west limit of the mass grading area to the low point of the project near the intersection of Alta Drive and Rampart Boulevard is in excess of 45 feet.

Our grading plan has been developed to match the existing conditions of the surrounding properties, and to keep future finish floor elevations below grade of adjacent properties. We have worked very hard to minimize the impact of our project and would ask for your support and approval of our grading plan, included with this package.

Thank you for your consideration.

Cordially,
GCW, Inc.



Thomas P. Dyson, PE
Senior Project Manager

**PLANS APPROVED
PLANNING**
Building & Safety Dept.
City of Las Vegas, Nevada
**2 FT GRADE DIFFERENCE
ONLY**
LHM JAN 10 2018
Conforms to the minimum requirements of
LVMC Title 19, applicable Master Plan
development standards and/or Conditions of
Approval. Make No Change Without Approval.
Plan is Not a Permit to Violate Any Ordinance.

1555 South Rainbow Boulevard
Las Vegas, Nevada 89146



O 702.804.2000
F 702.804.2299



info@gcwengineering.com
gcwengineering.com

F:\Projects\800\840-050\Admin\Letters\GradeDiffLtr-170913.docx

6279
CLV295910

REPLY APP 1203

HYDROLOGIC CRITERIA AND DRAINAGE DESIGN MANUAL

MANNING'S ROUGHNESS COEFFICIENTS FOR CHANNEL LINING TYPES

Channel Material	Roughness Coefficient (n)	
	Normal	Maximum
Corrugated Metal	0.025	0.030
Concrete**		
1) Trowel finish	0.013	0.015
2) Float finish	0.015	0.016
3) Unfinished	0.017	0.020
4) Shotcrete, Good section	0.019	0.023
5) Shotcrete, wavy section	0.122	0.025
Asphalt (use maximum value when cars are present)	0.016	0.020
Soil-Cement	0.020	0.025
Constructed channels with earth or sand bottom, sides of		
1) Clean earth; straight	0.022	0.025
2) Earth with grass and weeds	0.025	0.030
3) Earth with trees and shrubs	0.032	0.040
4) Shotcrete	0.022	0.025
5) Soil-cement	0.025	0.028
6) Concrete	0.020	0.024
7) Dry rubble or riprap	0.033	0.036
Natural channels with sand bottom, sides of		
1) Trees and shrubs	0.035	0.045
2) Rock	0.032	0.040
Natural channel with rock bottom	0.060	0.090
Overbank floodplains		
1) Desert brush, normal density	0.060	0.080
2) Dense vegetation	0.100	0.160

• Adapted from Chow (1959) and Aldridge and Garrett (1973).

** Manning's Coefficients for Clear Water Only

— City of Tucson Standards Manual for Drainage Design

Revision	Date

REFERENCE:

TABLE 702

**SUPPLEMENT NO. 1 TO THE
2nd UPDATE TO THE
TECHNICAL DRAINAGE STUDY
FOR
QUEENS BOROUGH CULVERT**

619.295

MARCH 2006

Prepared for:

**JMA Architecture Studios
10150 Covington Cross Drive
Las Vegas, Nevada 89144
Phone: (702) 731- 2033
Fax: (702) 731- 2039**



619.295

RECEIVED

APR 26 2006

CITY OF LAS VEGAS INTER-OFFICE MEMORANDUM		DATE: April 21, 2006
TO: Land Development Services Department of Public Works		FROM: Albert Sung, P.E. Flood Control Project Engineer Department of Public Works
SUBJECT: Technical Drainage Study for:		COPIES TO:
Queens Borough Culvert (Plans AKA : The Village at Queensridge Culvert)		G. C. Wallace, Inc.
Cross Streets:	NEC of Alta Drive & Rampart Boulevard	JMA Architecture
File Number:	F:\Depot\DSMEMOS\DS3674F.ZNA.doc	Bart Anderson, P.E., DevCo
Parcel Number:	138-32-601-003	CCRFC
FEMA Flood Zone	YES X NO	
Proposed Storm Drain	YES X NO	

HISTORY	DATE RECEIVED	DATE REVIEWED	COMMENTS	REVIEW FEES	FEES PAID Trn. No.
1 st Submittal	10/25/2004	11/9/2004	Not Approved	\$400.00	11413: \$400
2 nd Submittal	12/6/2004	12/20/2004	See Comments Below	\$400.00	13199: \$400
3 rd Submittal	3/4/2005	3/18/2005	Conditionally Approved	N/C	--
4 th Submittal	8/9/2005	8/23/2005	See Comments Below	\$400.00	27281: \$400
5 th Submittal	12/15/2005	12/30/2005	See Comments Below	\$400.00	35359: \$400
6 th Submittal	2/28/2006 3/30/2006 & 4/20/2006	4/21/2006	See Comments Below	N/C	N/C
TOTAL FEES (LDDRS):				\$1,600.00	----

REMARKS: 6th Submittal: Revised the on-site RCB alignment at the northeast corner of the site. Revised the RCB outfall structure, to include additional grading within Angel Park and the relocation of the concrete access road.

The Drainage Study for the subject project has been reviewed and:

X	is approved subject to conformance to all City standards and the following conditions:
	must be resubmitted or supplemented including the following:
	is conditionally approved subject to Clark County Regional Flood Control District concurrence.

1. The existing 48'-public drainage easement (Doc # 20051129:04185) must be vacated and a new easement dedicated to reflect the revised storm drain location. Provide a new legal description and exhibit to the Right-of-Way Section with a copy to Flood Control for review and approval. The revised easement must record concurrently with the vacated easement. The new easement must record prior to the final approval of the future technical drainage study needed for onsite development or approval of any final maps. **It is noted that the public drainage easement must be privately maintained both on the surface and within the box culvert.**
2. The revised plans for the storm drain system (CLV # 107y4889-CUL) must be submitted to Land Development for approval of this proposed revision.

6283

CLV295914

REPLY APP 1207


3. The engineer has provided a copy of the FEMA Conditional Letter of Map Revision (CLOMR), Case No. 05-09-0420R for the subject project. The engineer is advised that they are required to obtain FEMA approval for this revision as well as the completed "As-Built" condition in order to obtain the Letter of Map Revision (LOMR). **The approved LOMR must be submitted to the City of Las Vegas prior to the release of the bond.**


NOTE: The engineer must submit the drainage study to FEMA for a Conditional Letter of Map Revision (CLOMR). A favorable CLOMR must be obtained prior to the issuance of any permits. This site is located in a FEMA Zone A. Clark County Regional Flood Control District (CCRFCD) review and approval is required prior to recordation of final map or issuance of building/grading permits. The Engineer must send a copy of the report to the CCRFCD for review. **The developer/engineer must also obtain a Letter of Map Revision (LOMR) using the approved drainage study as technical support to inform FEMA of the modifications within the flood zone. The approved LOMR must be submitted to the City of Las Vegas prior to the release of the bond.** FEMA Elevation Certificates, showing as-built finish floor elevations, must be completed for each building in the FEMA A Zone. The certificate must be submitted to the City of Las Vegas Flood Control Section prior to scheduling a framing inspection.

NOTE: Please be advised that all land surface area disturbances over 1 acre or any area adjacent to a water way must submit to the Nevada Division of Environmental Protection a "Notice of Intent" to discharge that certifies a stormwater pollution prevention plan has been developed and is maintained on site; for inclusion in the Stormwater General Permit No. NVR100000. A phased construction unit in a contiguous subdivision is considered under construction until all stripped or disturbed surface areas have been covered by paving, building construction or planting. For more information, including forms and applications see <http://ndep.nv.gov/bwpc/storm01.htm> or call (775) 687-9429.

END OF REMARKS
B&H/ays/pbj

T/R/S: T20S/R60E/32
AREA L-32





Station	Invert Elev	Depth (FT)	Water Elev	Q (CFS)	Vel (FPS)	Vel Head	Energy Grd.El.	Super Elev	Critical Depth	Flow Top	Height/Dia. -FT	Base Wt or I.D.	ZL	No Wth Prs/Pip
L/Elem	Ch Slope				SF Ave	HF	SE Dpth	Froude N	Norm Dp	"N"	X-Fall	ZR	Type Ch	
-3625.000	14.000	7.834	21.834	4497.00	17.38	4.69	26.53	.00	9.28	62.96		1	0	.0
TRANS STR	.0400				.0187	1.41	7.83	1.51			.035		IR-	
OPEN														
-3550.000	17.000	8.266	25.266	4497.00	13.55	2.85	28.12	.00	8.27	58.19		2	0	.0
TRANS STR	.0100				.0070	.35	8.27	1.00			.035		IR-	
OPEN														
-3500.000	17.500	10.031	27.531	4497.00	8.46	1.11	28.64	.00	7.33	75.12		3	0	.0
TRANS STR	.0328							10.031	.561		.040		IR-	
OPEN														
-3401.010	20.750	2.481	23.231	4497.00	31.66	15.56	38.79	.00	5.67	63.50		4	0	.0
TRANS STR	.0110				.0371	1.86	2.48	3.73			.015		IR-	
OPEN														
-3350.810	21.300	2.522	23.822	4497.00	33.25	17.16	40.99	.00	5.89	59.13		5	0	.0
TRANS STR	.0141				.0413	1.03	2.52	3.87			.015		IR-	
OPEN														
-3325.950	21.650	2.323	23.973	4497.00	34.29	18.26	42.23	.00	5.71	60.97		6	0	.0
TRANS STR	.0160				.0340	.34	2.32	4.12			.015		IR-	
OPEN														
-3315.950	21.810	5.925	27.735	4497.00	31.62	15.53	43.26	.00	10.29	25.00	12.000	25.000	.00	1 1.0
90.310	.0152				.0249	2.24	5.93	2.34	7.02	.015	.00	.00	BOX	
-3225.640	23.180	5.731	28.911	4497.00	32.69	16.60	45.51	.00	10.29	25.00	12.000	25.000	.00	1 1.0
2.320	-.0776				.0263	.06	5.73	2.46	.00	.015	.00	.00	BOX	
-3223.320	23.000	5.682	28.682	4497.00	32.98	16.89	45.57	12.00	10.29	25.00	12.000	25.000	.00	1 1.0
70.620	.0283				.0264	1.86	12.00	2.49	5.55	.015	.00	.00	BOX	

Starting WSE

Station	Invert Elev	Depth (FT)	Water Elev	Q (CFS)	Vel (FPS)	Vel Head	Energy Grd.El.	Super Elev	Critical Depth	Flow Top Width	Height/Dia.-FT	Base Wt or I.D.	ZL	No Wth Prs/Pip
L/Elem	Ch Slope					SF Ave	HF	SE Dpth	Froude N	Norm Dp	"N"	X-Fall	ZR	Type Ch
-3152.700	25.000	5.709	30.709	4497.00	32.82	16.73	47.44	.00	10.29	25.00	12.000	25.000	.00	1 1.0
17.410	.0276					.0262	.46	5.71	2.47	5.60	.015	.00	.00	BOX
-3135.290	25.480	5.714	31.194	4497.00	32.79	16.70	47.89	12.00	10.29	25.00	12.000	25.000	.00	1 1.0
85.300	.0279					.0260	2.21	12.00	2.47	5.58	.015	.00	.00	BOX
-3049.990	27.860	5.748	33.608	4497.00	32.60	16.50	50.11	.00	10.29	25.00	12.000	25.000	.00	1 1.0
143.470	.0279					.0253	3.63	5.75	2.45	5.58	.015	.00	.00	BOX
-2906.520	31.860	5.829	37.689	4497.00	32.15	16.05	53.73	.40	10.29	25.00	12.000	25.000	.00	1 1.0
203.401	.0278					.0238	4.83	6.22	2.39	5.58	.015	.00	.00	BOX
-2703.119	37.523	6.024	43.546	4497.00	31.11	15.02	58.57	.37	10.29	25.00	12.000	25.000	.00	1 1.0
165.794	.0278					.0214	3.54	6.39	2.28	5.58	.015	.00	.00	BOX
-2537.325	42.138	6.318	48.456	4497.00	29.66	13.66	62.11	.34	10.29	25.00	12.000	25.000	.00	1 1.0
103.695	.0278					.0188	1.95	6.65	2.12	5.58	.015	.00	.00	BOX
-2433.630	45.025	6.626	51.651	4497.00	28.28	12.42	64.07	12.00	10.29	25.00	12.000	25.000	.00	1 1.0
60.182	.0278					.0168	1.01	12.00	1.98	5.58	.015	.00	.00	BOX
-2373.448	46.700	6.888	53.588	4497.00	27.20	11.49	65.08	12.00	10.29	25.00	12.000	25.000	.00	1 1.0
55.228	.0278					.0150	.83	12.00	1.86	5.58	.015	.00	.00	BOX
-2318.220	48.238	7.224	55.462	4497.00	25.94	10.45	65.91	.00	10.29	25.00	12.000	25.000	.00	1 1.0
26.702	.0278					.0136	.36	7.22	1.74	5.58	.015	.00	.00	BOX

Station	Invert Elev	Depth (FT)	Water Elev	Q (CFS)	Vel (FPS)	Vel Head	Energy Grd. El.	Super Elev	Critical Depth	Flow Top width	Height/Dia. -FT	Base wt or I.D.	ZL	No with Prs/Pip
L/Elem	Ch Slope					SF Ave	HF	SE Dpth	Froude N	Norm Op	"N"	X-Fall	ZR	Type Ch
-2291.518	48.982	7.440	56.421	4497.00	25.19	9.85	66.27	.00	10.29	25.00	12.000	25.000	.00	1 1.0
34.206	.0278					.0123	.42	7.44	1.66	5.58	.015	.00	.00	BOX
-2257.313	49.934	7.803	57.737	4497.00	24.01	8.95	66.69	.00	10.29	25.00	12.000	25.000	.00	1 1.0
25.506	.0278					.0109	.28	7.80	1.55	5.58	.015	.00	.00	BOX
-2231.807	50.644	8.184	58.828	4497.00	22.90	8.14	66.97	.00	10.29	25.00	12.000	25.000	.00	1 1.0
18.679	.0278					.0096	.18	8.18	1.44	5.58	.015	.00	.00	BOX
-2213.128	51.164	8.583	59.748	4497.00	21.83	7.40	67.15	.00	10.29	25.00	12.000	25.000	.00	1 1.0
13.128	.0278					.0085	.11	8.58	1.34	5.58	.015	.00	.00	BOX
-2200.000	51.530	9.002	60.532	4497.00	20.81	6.73	67.26	.00	10.29	25.00	12.000	25.000	.00	1 1.0
60.785	.0080					.0080	.49	9.00	1.25	9.00	.015	.00	.00	BOX
-2139.215	52.016	9.002	61.018	4497.00	20.81	6.73	67.75	.00	10.29	25.00	12.000	25.000	.00	1 1.0
405.355	.0080					.0077	3.13	9.00	1.25	9.00	.015	.00	.00	BOX
-1733.860	55.259	9.255	64.514	4497.00	20.24	6.36	70.88	12.00	10.29	25.00	12.000	25.000	.00	1 1.0
54.700	.0080					.0074	.40	12.00	1.20	9.00	.015	.00	.00	BOX
-1679.160	55.697	9.355	65.051	4497.00	20.03	6.23	71.28	12.00	10.29	25.00	12.000	25.000	.00	1 1.0
95.423	.0080					.0069	.65	12.00	1.18	9.00	.015	.00	.00	BOX
-1583.737	56.460	9.811	66.271	4497.00	19.10	5.66	71.93	12.00	10.29	25.00	12.000	25.000	.00	1 1.0
18.737	.0080					.0061	.11	12.00	1.10	9.00	.015	.00	.00	BOX

FILENAME: Q812X12-U2.WSW CJK

Station	Invert Elev	Depth (FT)	Water Elev	Q (CFS)	Vel (FPS)	Vel Head	Energy Grd. El.	Super Elev	Critical Depth	Flow Top width	Height/Dia.-FT	Base wt or I.D.	ZL	No wth Prs/Pip
L/Elem	Ch Slope					SF Ave	HF	SE Dpth	Froude N	Norm Dp	"N"	X-Fall	ZR	Type Ch
-1565.000	56.610	10.291	66.901	4497.00	18.21	5.15	72.05	.00	10.29	25.00	12.000	25.000	.00	1 1.0
88.377	.0050					.0051	.45	10.29	1.02	10.85	.015	.00	.00	Box
-1476.623	57.053	10.793	67.846	4497.00	17.36	4.68	72.53	.00	10.29	25.00	12.000	25.000	.00	1 1.0
257.531	.0050					.0050	1.29	10.79	.95	10.85	.015	.00	.00	Box
-1219.092	58.343	10.853	69.196	4497.00	17.26	4.63	73.82	.00	10.29	25.00	12.000	25.000	.00	1 1.0
219.092	.0050					.0050	1.10	10.85	.94	10.85	.015	.00	.00	Box
----- WARNING - Flow depth near top of box conduit -----														
-1000.000	59.440	10.853	70.293	4497.00	17.26	4.63	74.92	.00	10.29	25.00	12.000	25.000	.00	1 1.0

APPENDIX E

Improvement Plans

EXHIBIT “YYYYYY-8”

FOR

APN: 138-32-301-005

APN: 138-32-301-007

INDEX OF DRAWINGS	SHEET TITLE
COVER SHEET	COVER SHEET
1-1	GENERAL NOTES
2-1	GENERAL NOTES
3-1	GENERAL NOTES
4-1	GRADING PLAN 1
5-1	GRADING PLAN 2
6-1	GRADING PLAN 3
7-1	GRADING PLAN 4
8-1	GRADING PLAN 5
9-1	GRADING PLAN 6
10-1	GRADING PLAN 7
11-1	GRADING PLAN 8
12-1	GRADING PLAN 9
13-1	GRADING PLAN 10
14-1	GRADING PLAN 11
15-1	GRADING PLAN 12
16-1	GRADING PLAN 13
17-1	GRADING PLAN 14
18-1	GRADING PLAN 15
19-1	GRADING PLAN 16
20-1	GRADING PLAN 17
21-1	GRADING PLAN 18
22-1	GRADING PLAN 19
23-1	GRADING PLAN 20
24-1	GRADING PLAN 21
25-1	GRADING PLAN 22
26-1	GRADING PLAN 23
27-1	GRADING PLAN 24
28-1	GRADING PLAN 25
29-1	GRADING PLAN 26
30-1	GRADING PLAN 27
31-1	GRADING PLAN 28
32-1	GRADING PLAN 29
33-1	GRADING PLAN 30
34-1	GRADING PLAN 31
35-1	GRADING PLAN 32
36-1	GRADING PLAN 33
37-1	GRADING PLAN 34
38-1	GRADING PLAN 35
39-1	GRADING PLAN 36
40-1	GRADING PLAN 37
41-1	GRADING PLAN 38
42-1	GRADING PLAN 39
43-1	GRADING PLAN 40
44-1	GRADING PLAN 41
45-1	GRADING PLAN 42
46-1	GRADING PLAN 43
47-1	GRADING PLAN 44
48-1	GRADING PLAN 45
49-1	GRADING PLAN 46
50-1	GRADING PLAN 47
51-1	GRADING PLAN 48
52-1	GRADING PLAN 49
53-1	GRADING PLAN 50
54-1	GRADING PLAN 51
55-1	GRADING PLAN 52
56-1	GRADING PLAN 53
57-1	GRADING PLAN 54
58-1	GRADING PLAN 55
59-1	GRADING PLAN 56
60-1	GRADING PLAN 57
61-1	GRADING PLAN 58
62-1	GRADING PLAN 59
63-1	GRADING PLAN 60
64-1	GRADING PLAN 61
65-1	GRADING PLAN 62
66-1	GRADING PLAN 63
67-1	GRADING PLAN 64
68-1	GRADING PLAN 65
69-1	GRADING PLAN 66
70-1	GRADING PLAN 67
71-1	GRADING PLAN 68
72-1	GRADING PLAN 69
73-1	GRADING PLAN 70
74-1	GRADING PLAN 71
75-1	GRADING PLAN 72
76-1	GRADING PLAN 73
77-1	GRADING PLAN 74
78-1	GRADING PLAN 75
79-1	GRADING PLAN 76
80-1	GRADING PLAN 77
81-1	GRADING PLAN 78
82-1	GRADING PLAN 79
83-1	GRADING PLAN 80
84-1	GRADING PLAN 81
85-1	GRADING PLAN 82
86-1	GRADING PLAN 83
87-1	GRADING PLAN 84
88-1	GRADING PLAN 85
89-1	GRADING PLAN 86
90-1	GRADING PLAN 87
91-1	GRADING PLAN 88
92-1	GRADING PLAN 89
93-1	GRADING PLAN 90
94-1	GRADING PLAN 91
95-1	GRADING PLAN 92
96-1	GRADING PLAN 93
97-1	GRADING PLAN 94
98-1	GRADING PLAN 95
99-1	GRADING PLAN 96
100-1	GRADING PLAN 97
101-1	GRADING PLAN 98
102-1	GRADING PLAN 99
103-1	GRADING PLAN 100
104-1	GRADING PLAN 101
105-1	GRADING PLAN 102
106-1	GRADING PLAN 103
107-1	GRADING PLAN 104
108-1	GRADING PLAN 105
109-1	GRADING PLAN 106
110-1	GRADING PLAN 107
111-1	GRADING PLAN 108
112-1	GRADING PLAN 109
113-1	GRADING PLAN 110
114-1	GRADING PLAN 111
115-1	GRADING PLAN 112
116-1	GRADING PLAN 113
117-1	GRADING PLAN 114
118-1	GRADING PLAN 115
119-1	GRADING PLAN 116
120-1	GRADING PLAN 117
121-1	GRADING PLAN 118
122-1	GRADING PLAN 119
123-1	GRADING PLAN 120
124-1	GRADING PLAN 121
125-1	GRADING PLAN 122
126-1	GRADING PLAN 123
127-1	GRADING PLAN 124
128-1	GRADING PLAN 125
129-1	GRADING PLAN 126
130-1	GRADING PLAN 127
131-1	GRADING PLAN 128
132-1	GRADING PLAN 129
133-1	GRADING PLAN 130
134-1	GRADING PLAN 131
135-1	GRADING PLAN 132
136-1	GRADING PLAN 133
137-1	GRADING PLAN 134
138-1	GRADING PLAN 135
139-1	GRADING PLAN 136
140-1	GRADING PLAN 137
141-1	GRADING PLAN 138
142-1	GRADING PLAN 139
143-1	GRADING PLAN 140
144-1	GRADING PLAN 141
145-1	GRADING PLAN 142
146-1	GRADING PLAN 143
147-1	GRADING PLAN 144
148-1	GRADING PLAN 145
149-1	GRADING PLAN 146
150-1	GRADING PLAN 147
151-1	GRADING PLAN 148
152-1	GRADING PLAN 149
153-1	GRADING PLAN 150
154-1	GRADING PLAN 151
155-1	GRADING PLAN 152
156-1	GRADING PLAN 153
157-1	GRADING PLAN 154
158-1	GRADING PLAN 155
159-1	GRADING PLAN 156
160-1	GRADING PLAN 157
161-1	GRADING PLAN 158
162-1	GRADING PLAN 159
163-1	GRADING PLAN 160
164-1	GRADING PLAN 161
165-1	GRADING PLAN 162
166-1	GRADING PLAN 163
167-1	GRADING PLAN 164
168-1	GRADING PLAN 165
169-1	GRADING PLAN 166
170-1	GRADING PLAN 167
171-1	GRADING PLAN 168
172-1	GRADING PLAN 169
173-1	GRADING PLAN 170
174-1	GRADING PLAN 171
175-1	GRADING PLAN 172
176-1	GRADING PLAN 173
177-1	GRADING PLAN 174
178-1	GRADING PLAN 175
179-1	GRADING PLAN 176
180-1	GRADING PLAN 177
181-1	GRADING PLAN 178
182-1	GRADING PLAN 179
183-1	GRADING PLAN 180
184-1	GRADING PLAN 181
185-1	GRADING PLAN 182
186-1	GRADING PLAN 183
187-1	GRADING PLAN 184
188-1	GRADING PLAN 185
189-1	GRADING PLAN 186
190-1	GRADING PLAN 187
191-1	GRADING PLAN 188
192-1	GRADING PLAN 189
193-1	GRADING PLAN 190
194-1	GRADING PLAN 191
195-1	GRADING PLAN 192
196-1	GRADING PLAN 193
197-1	GRADING PLAN 194
198-1	GRADING PLAN 195
199-1	GRADING PLAN 196
200-1	GRADING PLAN 197
201-1	GRADING PLAN 198
202-1	GRADING PLAN 199
203-1	GRADING PLAN 200
204-1	GRADING PLAN 201
205-1	GRADING PLAN 202
206-1	GRADING PLAN 203
207-1	GRADING PLAN 204
208-1	GRADING PLAN 205
209-1	GRADING PLAN 206
210-1	GRADING PLAN 207
211-1	GRADING PLAN 208
212-1	GRADING PLAN 209
213-1	GRADING PLAN 210
214-1	GRADING PLAN 211
215-1	GRADING PLAN 212
216-1	GRADING PLAN 213
217-1	GRADING PLAN 214
218-1	GRADING PLAN 215
219-1	GRADING PLAN 216
220-1	GRADING PLAN 217
221-1	GRADING PLAN 218
222-1	GRADING PLAN 219
223-1	GRADING PLAN 220
224-1	GRADING PLAN 221
225-1	GRADING PLAN 222
226-1	GRADING PLAN 223
227-1	GRADING PLAN 224
228-1	GRADING PLAN 225
229-1	GRADING PLAN 226
230-1	GRADING PLAN 227
231-1	GRADING PLAN 228
232-1	GRADING PLAN 229
233-1	GRADING PLAN 230
234-1	GRADING PLAN 231
235-1	GRADING PLAN 232
236-1	GRADING PLAN 233
237-1	GRADING PLAN 234
238-1	GRADING PLAN 235
239-1	GRADING PLAN 236
240-1	GRADING PLAN 237
241-1	GRADING PLAN 238
242-1	GRADING PLAN 239
243-1	GRADING PLAN 240
244-1	GRADING PLAN 241
245-1	GRADING PLAN 242
246-1	GRADING PLAN 243
247-1	GRADING PLAN 244
248-1	GRADING PLAN 245
249-1	GRADING PLAN 246
250-1	GRADING PLAN 247
251-1	GRADING PLAN 248
252-1	GRADING PLAN 249
253-1	GRADING PLAN 250
254-1	GRADING PLAN 251
255-1	GRADING PLAN 252
256-1	GRADING PLAN 253
257-1	GRADING PLAN 254
258-1	GRADING PLAN 255
259-1	GRADING PLAN 256
260-1	GRADING PLAN 257
261-1	GRADING PLAN 258
262-1	GRADING PLAN 259
263-1	GRADING PLAN 260
264-1	GRADING PLAN 261
265-1	GRADING PLAN 262
266-1	GRADING PLAN 263
267-1	GRADING PLAN 264
268-1	GRADING PLAN 265
269-1	GRADING PLAN 266
270-1	GRADING PLAN 267
271-1	GRADING PLAN 268
272-1	GRADING PLAN 269
273-1	GRADING PLAN 270
274-1	GRADING PLAN 271
275-1	GRADING PLAN 272
276-1	GRADING PLAN 273
277-1	GRADING PLAN 274
278-1	GRADING PLAN 275
279-1	GRADING PLAN 276
280-1	GRADING PLAN 277
281-1	GRADING PLAN 278
282-1	GRADING PLAN 279
283-1	GRADING PLAN 280
284-1	GRADING PLAN 281
285-1	GRADING PLAN 282
286-1	GRADING PLAN 283
287-1	GRADING PLAN 284
288-1	GRADING PLAN 285
289-1	GRADING PLAN 286
290-1	GRADING PLAN 287
291-1	GRADING PLAN 288
292-1	GRADING PLAN 289
293-1	GRADING PLAN 290
294-1	GRADING PLAN 291
295-1	GRADING PLAN 292
296-1	GRADING PLAN 293
297-1	GRADING PLAN 294
298-1	GRADING PLAN 295
299-1	GRADING PLAN 296
300-1	GRADING PLAN 297
301-1	GRADING PLAN 298
302-1	GRADING PLAN 299
303-1	GRADING PLAN 300
304-1	GRADING PLAN 301
305-1	GRADING PLAN 302
306-1	GRADING PLAN 303
307-1	GRADING PLAN 304
308-1	GRADING PLAN 305
309-1	GRADING PLAN 306
310-1	GRADING PLAN 307
311-1	GRADING PLAN 308
312-1	GRADING PLAN 309
313-1	GRADING PLAN 310
314-1	GRADING PLAN 311
315-1	GRADING PLAN 312
316-1	GRADING PLAN 313
317-1	GRADING PLAN 314
318-1	GRADING PLAN 315
319-1	GRADING PLAN 316
320-1	GRADING PLAN 317
321-1	GRADING PLAN 318
322-1	GRADING PLAN 319
323-1	GRADING PLAN 320
324-1	GRADING PLAN 321
325-1	GRADING PLAN 322
326-1	GRADING PLAN 323
327-1	GRADING PLAN 324
328-1	GRADING PLAN 325
329-1	GRADING PLAN 326
330-1	GRADING PLAN 327
331-1	GRADING PLAN 328
332-1	GRADING PLAN 329
333-1	GRADING PLAN 330
334-1	GRADING PLAN 331
335-1	GRADING PLAN 332
336-1	GRADING PLAN 333
337-1	GRADING PLAN 334
338-1	GRADING PLAN 335
339-1	GRADING PLAN 336
340-1	GRADING PLAN 337
341-1	GRADING PLAN 338
342-1	GRADING PLAN 339
343-1	GRADING PLAN 340
344-1	GRADING PLAN 341
345-1	GRADING PLAN 342
346-1	GRADING PLAN 343
347-1	GRADING PLAN 344
348-1	GRADING PLAN 345
349-1	GRADING PLAN 346
350-1	GRADING PLAN 347
351-1	GRADING PLAN 348
352-1	GRADING PLAN 349
353-1	GRADING PLAN 350
354-1	GRADING PLAN 351
355-1	GRADING PLAN 352
356-1	GRADING PLAN 353
357-1	GRADING PLAN 354
358-1	GRADING PLAN 355
359-1	GRADING PLAN 356
360-1	GRADING PLAN 357
361-1	GRADING PLAN 358
362-1	GRADING PLAN 359
363-1	GRADING PLAN 360
364-1	GRADING PLAN 361
365-1	GRADING PLAN 362
366-1	GRADING PLAN 363
367-1	GRADING PLAN 364
368-1	GRADING PLAN 365
369-1	GRADING PLAN 366
370-1	GRADING PLAN 367
371-1	GRADING PLAN 368
372-1	GRADING PLAN 369
373-1	GRADING PLAN 370
374-1	GRADING PLAN 371
375-1	GRADING PLAN 372
376-1	GRADING PLAN 373
377-1	GRADING PLAN 374
378-1	GRADING PLAN 375
379-1	GRADING PLAN 376
380-1	GRADING PLAN 377
381-1	GRADING PLAN 378
382-1	GRADING PLAN 379
383-1	GRADING PLAN 380
384-1	GRADING PLAN 381
385-1	GRADING PLAN 382
386-1	GRADING PLAN 383
387-1	GRADING PLAN 384
388-1	GRADING PLAN 385
389-1	GRADING PLAN 386
390-1	GRADING PLAN 387
391-1	GRADING PLAN 388
392-1	GRADING PLAN 389
393-1	GRADING PLAN 390
394-1	GRADING PLAN 391
395-1	GRADING PLAN 392
396-1	GRADING PLAN 393
397-1	GRADING PLAN 394
398-1	GRADING PLAN 395
399-1	GRADING PLAN 396
400-1	GRADING PLAN 397
401-1	GRADING PLAN 398
402-1	GRADING PLAN 399
403-1	GRADING PLAN 400
404-1	GRADING PLAN 401
405-1	GRADING PLAN 402
406-1	GRADING PLAN 403
407-1	GRADING PLAN 404
408-1	GRADING PLAN 405
409-1	GRADING PLAN 406
410-1	GRADING PLAN 407
411-1	GRADING PLAN 408
412-1	GRADING PLAN 409
413-1	GRADING PLAN 410
414-1	GRADING PLAN 411
415-1	GRADING PLAN 412
416-1	GRADING PLAN 413
417-1	GRADING PLAN 414
418-1	GRADING PLAN 415
419-1	GRADING PLAN 416
420-1	GRADING PLAN 417
421-1	GRADING PLAN 418
422-1	GRADING PLAN 419
423-1	GRADING PLAN 420
424-1	GRADING PLAN 421
425-1	GRADING PLAN 422
426-1	GRADING PLAN 423
427-1	GRADING PLAN 424
428-1	GRADING PLAN 425
429-1	GRADING PLAN 426
430-1	GRADING PLAN 427
431-1	GRADING PLAN 428
432-1	GRADING PLAN 429
433-1	GRADING PLAN 430
434-1	GRADING PLAN 431
435-1	GRADING PLAN 432
436-1	GRADING PLAN 433
437-1	GRADING PLAN 434
438-1	GRADING PLAN 435
439-1	GRADING PLAN 436
440-1	GRADING PLAN 437
441-1	GRADING PLAN 438
442-1	GRADING PLAN 439
443-1	GRADING PLAN 440
444-1	GRADING PLAN 441
445-1	GRADING PLAN 442
446-1	GRADING PLAN 443
447-1	GRADING PLAN 444
448-1	GRADING PLAN 445
449-1	GRADING PLAN 446
450-1	GRADING PLAN 447
451-1	GRADING PLAN 448
452-1	GRADING PLAN 449
453-1	GRADING PLAN 450
454-1	GRADING PLAN 451
455-1	GRADING PLAN 452
456-1	GRADING PLAN 453
457-1	GRADING PLAN 454
458-1	GRADING PLAN 455
459-1	GRADING PLAN 456
460-1	GRADING PLAN 457
461-1	GRADING PLAN 458
462-1	GRADING PLAN 459
463-1	GRADING PLAN 460
464-1	GRADING PLAN 461
465-1	GRADING PLAN 462
466-1	GRADING PLAN 463
467-1	GRADING PLAN 464
468-1	GRADING PLAN 465
469-1	GRADING PLAN 466
470-1	GRADING PLAN 467
471-1	GRADING PLAN 468
472-1	GRADING PLAN 469
473-1	GRADING PLAN 470
474-1	GRADING PLAN 471
475-1	GRADING PLAN 472
476-1	GRADING PLAN 473
477-1	GRADING PLAN 474
478-1	GRADING PLAN 475
479-1	GRADING PLAN 476
480-1	GRADING PLAN 477
481-1	GRADING PLAN 478
482-1	GRADING PLAN 479
483-1	GRADING PLAN 480
484-1	GR

[illegible][illegible]

LEGAL DESCRIPTION LOTS 1 AND 2 AS SHOWN IN FILE 170. PAGES 81 OF PARCELS MAPS, MAPS AND LOT 1 AS SHOWN IN FILE 130. PAGE 49 OF PARCELS MAPS.	DRAINAGE CERTIFICATION LOWRY, JAY, DOES NOT OWN AND HAS NO INTERESTS IN ANY OF THE LANDS SHOWN ON FILE AT THE CITY OF LAS VEGAS FOR THIS PROJECT.	OWNER/DEVELOPER SECURITY FORTS LLC FIVE STAGE 1 LTD 10000 S. MOHAVE BLVD SUITE 400 LAS VEGAS NV 89117
MARK & FAULTER FILE #911	DATE	

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----


[illegible][illegible]REPLY APP 1219


REPLY APP 1220


TV

US SUBMITTAL












STORM DRAIN - LATERAL 4



STORM DRAIN - LATERAL 3











EXHIBIT “YYYYYY-9”

CITY OF LAS VEGAS INTER-OFFICE MEMORANDUM			DATE: February 1, 2018
TO: Land Development Services Department of Building & Safety			FROM: Jennifer Shinn Flood Control Engr. Associate Department of Public Works
SUBJECT:	Drainage Study for: The 435 formerly The SEVENTY		COPIES TO: GCW Engineers
Cross Streets:	SWC of Rampart & Alta		Seventy Acres LLC
File Number:	F:\Depot\DSMemos\DS4787C.ZNA.doc		Bart Anderson, P.E., DevCo
Parcel Number:	138-32-301-005, 006, 210-008		CCRFC
Zoning Action:	SDR-62393; GPA-62387; ZON-62392		
FEMA Flood Zone	YES	X NO	
Proposed Storm Drain	YES	X NO	

HISTORY	DATE RECEIVED	DATE REVIEWED	COMMENTS	REVIEW FEES	FEES PAID Payment Trn #
1 st Submittal	3/3/2016 & 3/9/2016	3/23/2016	See Comments Below	\$400.00	425231: \$400
2 nd Submittal	9/18/17	11/9/2017	See Comments Below	\$400.00	490193: \$400
3 rd Submittal	1/11/18	2/1/2018	See Comments Below	\$400.00	492825: \$400
TOTAL FEES (LDDRS):				\$1200.00	----

REMARKS: This site development is within a **FEMA SPECIAL FLOOD HAZARD AREA, Zone A**. No permits of any kind will be issued for this project until a **Conditional Letter of Map Revision (CLOMR/CLOMR-F)** is received from FEMA.

The Drainage Study for the subject project has been reviewed and:

	is approved subject to conformance to all City standards and the following conditions:
X	must be resubmitted or supplemented including the following:
	is conditionally approved subject to Clark County Regional Flood Control District concurrence.
	is conditionally approved subject to NDOT concurrence.

1. An effective HEC-RAS model to determine the existing water surface elevation within the FEMA Special Flood Hazard Area Zone A is required. This model will serve as the base model to develop the duplicate effective model, corrected effective model, pre-project condition model and post-project condition model.
2. Provide a comparison summary of the HEC-RAS results for the existing, interim, and proposed wash conditions.
3. Extend the HEC-RAS model further upstream to analyze the effects of the sedimentation berms.
4. Additional HEC-RAS cross sections are required at the weir (upstream and downstream), at the sediment berms, and the turn within the open RCB. Update the model and exhibits accordingly.

5. For the FEMA flood zone WSE evaluation, the computational flow regime should be “sub-critical flow” not “mix flow” to provide a conservative WSE for floodplain assessment.
6. The hydraulic models do not provide a relationship between Mainline 2 and Mainline 1 at the junction structure. The junction structure acts as a major point of confluence and is a critical section of the system. Revise the WSPG and HEC-RAS models to better demonstrate the interaction of the systems (Mainline 1, Mainline 2, and wash) at the junction.
7. Based on the results of Comment 6, the computed flow depth at the end of the Mainline 2 system should be used as the initial flow condition at Mainline 1 Station -7536.97 and should be applied as the boundary condition for the HEC-RAS model when conducting the WSE evaluation.
8. There is an existing hydraulic jump at the end of the Mainline 1 system per sheet C-6 of the referenced plan for “The Village at Queensridge Culvert”. The WSE of 2635.91 should be used as the downstream boundary condition (SO) to incorporate the hydraulic jump impacting the overall storm drain hydraulic performance and avoid any negative impacts to the downstream condition; Or input parameters should be adjusted to reproduce the hydraulic jump as shown on sheet C-6 to evaluate the proposed storm drain system hydraulic performance.
9. The Mainline 1 system includes an existing 72-inch (Station -9391.3) with a WSE of 2669.252. Provide a comparison between the current design and the previously approved study/design to assess any negative impacts to the upstream and downstream facilities.
10. Include curvature information in the WSPG model for Mainline 2 to estimate super-elevation. Furthermore, with the high flow quantity over 2,000-cfs and a flow velocity of 38.04-fps, which is equal to 22.5-feet of velocity head and super-critical flow condition, roll wave in the straight reach, super-elevation and cross wave along a curve reach and a possible oblique jump should be considered. Ensure the proposed channel cross section provides a stabilized flow condition with sufficient freeboard.
11. Provide headwater calculations at the RCB entrance from the open box section.
12. Provide updated weir calculations for the revised weir length of the open RCB.
13. The future minimum finished floor elevations must be higher than the manholes/road grades of the future road. Revise accordingly.
14. Show 16-foot min. width gates and provide details at maintenance access points from Alta Drive and Rampart Boulevard.
15. Verify the existing golf course bridge has adequate capacity and clearance for maintenance vehicles and equipment.
16. Show a maintenance access road down to the interim channel area.
17. Revise the post and cable details to reflect a 3-cable fence system.
18. A levee is proposed along the northern side of the interim channel, adjacent to southwestern future development lots. Per Section 303.6.2 of the Manual, since the flood control levee is proposed within a FEMA SFHA and a map revision will be requested based on the levee providing protection against the 100-year flood, FEMA’s levee criteria shall be used in order for FEMA to credit the levee. For FEMA to accredit a levee system with 1-percent-annual-chance flood hazard reduction capability on a FIRM, the community/levee owner must submit a package containing the required data and documentation to show that the levee system meets all design and operation requirements of 44 CFR 65.10.

19. It is unclear on the profile on Sheet C5.03 where the bottom of the channel is located and how high the HGL is at this section. It appears that the upstream end of the open box is only 2-feet high which means the western wall of the RCB is not fully constructed. Clarify the design of open box section.
20. Verify the stationing of SDMH #109 on the profile on Sheet C5.04.
21. Revise the call outs on the lateral profile sheets to call out Construction Note 12 to install temporary plug and cap storm drain line.
22. Revise Sections 5 and 9 on Sheet C8.01 to show the same rip rap specifications for the bottom of the interim channel.
23. Revise Sections 3 and 8 on Sheet C8.01 to specify the same scarification extents.
24. Provide details of the proposed walls at the entrance into the 20' x 12' RCB.

The following comments are repeated to reflect routine items previously acknowledged by the Engineer.

25. This site development is located within a FEMA SPECIAL FLOOD HAZARD AREA, Zone A. **No permits will be issued until a Conditional Letter of Map Revision (CLOMR/CLOMR-F) is received from FEMA. Permits may be issued upon the receipt of Conditional Letter of Map Revision (CLOMR or CLOMR-F) from FEMA.**
26. A Letter of Map Revision (LOMR/LOMR-F) must be obtained from FEMA after the completion of any project within a FEMA Special Flood Hazard Area, Flood Zone "A". The bonded improvements shall include a line item of **\$50,000.00** for the LOMR. The bonded improvements will not be released until the LOMR/LOMR-F is obtained from FEMA and filed with the City of Las Vegas.
27. The site is located within the Flood Zone A and is adjacent to an existing or proposed *Clark County Regional Flood Control District (CCRFCD)* master planned facility. Therefore, CCRFCD concurrence is required prior to final approval of the drainage study.
28. Please obtain necessary 404 permits from US Army Corps of Engineers and provide a copy of the permit to City of Las Vegas Flood Control Section prior to issuance of the grading permit. Contact the St. George Field Office of the US Army Corps of Engineers for permit information.
29. Provide complete *Plans and Project Specifications* for approval by the *City of Las Vegas*. The Structural Plans and Details shall be a part of the Civil Improvement Plan set. This project is considered as a *Capital Improvement Project (CIP)* with developer funding.
30. Structural plans for the proposed storm drain improvements and pertinent flood control facilities must be submitted for review. Provide a soils report, structural calculations and specifications, two wet stamped structural sets, and a grading plan to the *Building Department* for processing. The engineer must provide a copy of *Building Department* approval of the structures to Regional Flood prior to their concurrence and to *Flood Control* prior to final acceptance of the drainage study.
31. All proposed improvements associated with the Storm Drain facilities shall be bonded and inspected. This project shall require Special Inspection. Coordinate the requirements of and the Agreements needed for Special Inspection with the Building Department.
32. The proposed improvements show drainage facilities of a size that must be reviewed for access and maintenance concerns. The engineer must submit an extra set of improvement plans to the *City Streets & Sanitation Department* for their review and comments. *Streets & Sanitation Department's* approval must be secured prior to the conditional drainage study approval.
33. Provide new public drainage easements for the area of the site impacted by the proposed MPU facility improvements. The easement shall note that the public drainage improvements (MPU

facilities) are publicly maintained and all onsite storm drain and surface improvements are privately maintained and the easement must be dedicated and recorded by separate document prior to the final acceptance of the improvement plans. Provide legal description and an exhibit of the drainage easement to Flood Control and *Rae Heller* (702-229-2139) of *City of Las Vegas Right of Way Section* for the recordation process after the subject drainage study is conceptually approved. The existing drainage easements shall be vacated by separate action and the recording of the new easements shall be done consecutively.

34. Technical drainage studies are required for each of the future development super pads. The technical drainage studies for the developments may not be submitted until the conditional approval of this pertinent infrastructure drainage study is obtained. Final approval for the infrastructure study must be obtained prior to conditional approval of the impacted development super pad drainage studies.
35. This project currently has no Proposed Buildings or Structures. Should the project propose changes to this design assumption, then the Engineer is to update the drainage study detailing the flood zone impacts and provide addresses for each building in a FEMA Flood Hazard Zone prior to obtaining a grading permit. This information is necessary to insure that the elevation certificates are provided for each address prior to completion of construction. This information is required until such time as a LOMR is approved that removes the development from the SFHA.

Flood Control understands that this overall project will be developed in Phases. The following comments are repeated to reflect items that shall be addressed in future study updates as the Phases develop.

36. Proposed storm drain laterals have been identified to collect flows from Peccole West Lot 9 and Queensridge Fairway Homes. Extend the storm drain system to collect the 100-year flows from these adjacent subdivisions.
37. Continue to coordinate the MPU facility changes that are proposed with this development.
38. Storm drain facilities are located on cut/fill slopes. Revise the slopes and/or the storm drain alignment to maintain 12-foot access roads. Provide a cross section detail of the maintenance access.
39. Provide a concrete pad and maintenance access to the inlet structures for the local storm drains. Show the needed drainage easements for these facilities.
40. The existing and proposed utility crossings of the storm drain must be shown on the storm drain plan and profiles sheets and on the lateral profiles. Indicate the type of pipe material for water and sewer lines. Review separation requirements between utilities and show all of the utility crossings of the storm drains.

NOTE: Please be advised that all land surface area disturbances over 1 acre or any area adjacent to a water way must submit to the *Nevada Division of Environmental Protection* a "Notice of Intent" to discharge that certifies a stormwater pollution prevention plan has been developed and is maintained on site; for inclusion in the Stormwater General Permit No. NVR100000. A phased construction unit in a contiguous subdivision is considered under construction until all stripped or disturbed surface areas have been covered by paving, building construction or planting. For more information, including forms and applications see <http://ndep.nv.gov/bwpc/storm01.htm> or call (775) 687-9429.

NOTE: The engineer must submit the drainage study to FEMA for a Conditional Letter of Map Revision (CLOMR). A favorable CLOMR must be obtained prior to the issuance of any permits. This site is located in a **FEMA Zone A**. *Clark County Regional Flood Control District* (CCRFCD) review and approval is required prior to recordation of final map or issuance of building/grading permits. The Engineer must send a copy of the report to the CCRFCD for review. **The developer/engineer must also obtain a Letter of Map Revision (LOMR) using the approved drainage study as technical support to inform FEMA of the modifications within the flood zone. The approved LOMR must be submitted to the *City of Las Vegas* prior to the release of the bond.** FEMA Elevation Certificates, showing as-built finish floor elevations, must be completed for each building in the FEMA A Zone. The certificate must be submitted to the *City of Las Vegas Flood Control Section* prior to scheduling a framing inspection.

END OF REMARKS
JKS/PBJ

T/R/S: T20S/R60E/12
AREA L-32